



This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

- + *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.
- + *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.
- + *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.
- + *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at <http://books.google.com/>

UC-NRLF



B 3 467 334




LIBRARY
OF THE
UNIVERSITY OF CALIFORNIA.

GIFT OF

Knights of St. Patrick
Class

Log



Works for Tourists in Ireland,

PUBLISHED BY

JAMES M^cGLASHAN, 21 D'OLIER-STREET,

Dublin.

SOLD BY ALL BOOKSELLERS.

I.

A HANDBOOK FOR TRAVELLERS IN IRELAND. By JAMES FRASER. A new Edition, with Map, and an Introductory Chapter descriptive of the various Railways open. Crown 8vo., price 8s.

II.

DUBLIN AND ITS ENVIRONS. With a Map of the City, and numerous Illustrations engraved on Wood. A neat Pocket Volume. Price 3s. Cloth; 2s. 6d. sewed.

III.

PLAN OF DUBLIN. Carefully corrected. Price 6d.

IV.

IRISH RAILWAY GUIDES, being complete Charts of the Lines, pointing out every Object of Interest in their Vicinity. Each copiously illustrated with Wood Engravings and a Map of the Railway.—I. DUBLIN to CARLOW.—II. DUBLIN to TIPPERARY and LIMERICK. Price 6d. each.

V.

A WEEK IN THE SOUTH OF IRELAND, including Notices of Cork, Limerick, Killarney, and Glengariff. With a Map. By AN OLD TRAVELLER. Price 6d.

VI.

THE IRISH WATERING PLACES; their Climate, Scenery, and Accommodations; including Analyses of the principal Mineral Springs, by Sir ROBERT KANE, and Remarks on the various Forms of Disease to which they are adapted; together with Directions for the Regimen of Invalids, and Observations on Indigestion, Gout, Pulmonary Consumption, and other Diseases of the Chest, Stomach, and Nervous System. By ALEXANDER KNOX, M. D., Surgeon to the Strangford Dispensary, &c. Price 7s. 6d. Cloth.

VII.

A HANDBOOK OF IRISH ANTIQUITIES, PAGAN AND CHRISTIAN; especially of such as are easy of Access from the Irish Metropolis. By W. F. WAKEMAN. With 100 Illustrations drawn by the Author. A beautiful Pocket Volume, fcap. 8vo., price 5s. Cloth.

VIII.

REVELATIONS OF IRELAND. By D. OWEN-MADDEN. Post 8vo., 10s. 6d. Cloth.

CONTENTS.—1. The old Munster Bar. 2. Irish Pulpit Eloquence—Dean Kirwan. 3. Romance in High Life. 4. O'Connelliana. 5. Power of the Priesthood—Endowment. 6. Defence of Highfort. 7. The Penal Days. 8. Provincial Ambition—Gerald Callaghan. 9. A Night of Horror. 10. Terrors of the Law. 11. A Scotchman in Munster. 12. The Irish Nobility—Imperial Nationality.

IX.

IRELAND SIXTY YEARS AGO. A new and cheap Edition. Price 1s.

CONTENTS.—1. State of Society and the City of Dublin—Liberty Boys and Ormond Boys—College-boys—Police—Bucks and Bullies—Chalkers. 2. Duelling—Judicial and legal Duellists—Duelling Clubs and Rules—Hayes—Pat Power—Bryan Maguire—Trials for Duels. 3. Abduction—Abduction Clubs—the Misses Kennedy—Miss Knox. 4. Civic Processions—Riding the Franchises—the Liberties—the Lord Mayor's Penance. 5. Drunkenness—Notions of Conviviality. 6. Gambling—Lottories. 7. Shoe-blacks—the Streets—Public Vehicles. 8. Slang Songs—Prison Usages—the Night before Larry was stretched—the Kilmainham Minit—Executioners—Bull-baiting—Lord Altham's Bull—the Bush. 9. Rapparees and Robbers—Hedge Schools—Fremey—Northern Robbers—Shawn Crossach—William Crotty—Crotty's Lament—Felons' Bodies—Frederick Caulfield. 10. Tiger Roche. 11. The Kingdom of Dalkey—The Dalkey Gazette—O'Meara. 12. the Visitation of 1798—United Irishmen—James Farrell—Expulsion of Power and Ardagh—Cause of the Visitation—its Proceedings—Lord Clare—Dr. Browne—Dr. Stokes—its Effects—Sketch of Farrell—of Corbett. 13. Lord Clare's Funeral. 14. The Gib's Parliamentary Privileges—Fire in the House of Commons.

X.

SPECIMENS OF THE EARLY NATIVE POETRY OF IRELAND, in English Metrical Translations, by Miss Brooke, Dr. Drummond, Samuel Ferguson, J. C. Mangan, T. Furlong, H. Grattan Curran, Edward Walsh, J. D'Alton, John Anster, LL. D., &c. &c. With historical and biographical Notices. By HENRY R. MONTGOMERY. 2s. 6d. Cloth, gilt edges.

XI.

IRISH POPULAR SONGS; with English Metrical Versions, English and Irish interposed. By EDWARD WALSH. 2s. 6d. sewed.

XII.

THE DEEP SEA AND COAST FISHERIES OF IRELAND, with Directions for a Fishing Company. By WALLOP BRABAZON, Esq. Copiously illustrated, 8vo., 5s. Cloth.

XIII.

FLORA HIBERNICA; comprising the Flowering Plants, Ferns, Charachia, Musci, Hepaticæ, Lichenes, and Algæ of Ireland, arranged according to the Natural System. With a Synopsis of the Genera according to the Linnæan System. By JAMES TOWNSEND MACKAY, M. R. I. A., Associate of the Linnæan Society, &c. &c. 8vo., 16s. Cloth.

DUBLIN: JAMES McGLASHAN, 21, D'OLIER-STREET.

WM. S. ORR & CO., 147, STRAND, LONDON; AND LIVERPOOL

SOLD BY ALL BOOKSELLERS.

THE
BEAUTIES OF THE BOYNE,
AND ITS TRIBUTARY,
THE BLACKWATER.

BY
WILLIAM R. WILDE.



DUBLIN:
JAMES M^cGLASHAN, 21 D'OLIER-STREET.
WILLIAM S. ORR AND CO., LONDON AND LIVERPOOL.
MDCCCXLIX.

DA 990
B7W6

KNIGHTS OF ST. PATRICK

DUBLIN :
PRINTED AT THE UNIVERSITY PRESS,
BY M. H. GILL.

L.C.

TO

GEORGE PETRIE, LL.D., M.R.I.A.,

Whose Learning and critical Research have placed the Archæology of
this Country on a philosophic Basis,
And by whose Pencil its Scenery and Antiquities have been so
happily Illustrated :

AND TO

JOHN O'DONOVAN, M.R.I.A.,

PROFESSOR OF THE IRISH LANGUAGE IN QUEEN'S COLLEGE, BELFAST,

The Irish Historian of the Nineteenth Century,

This Book,

The Composition of which their labours have so much facilitated,

IS DEDICATED,

In Testimony of public Respect, and private Affection,

By their Friend,

THE AUTHOR.

219386

P R E F A C E .

THE materials for this book were collected during excursions, made from time to time, to the Boyne, for health, amusement, or instruction. With a desire to illustrate some of the scenery and antiquities of our native land, fragments of the original rough sketches were published in the Dublin University Magazine, among the series of "Irish Rivers," now appearing in that periodical. Although the space allotted to such subjects in a serial did not permit of lengthened descriptions of any of the places of note which fringe this river's banks, the interest which had been awakened by those rapid sketches of the Beauties of the Boyne, was such as to induce the Publisher to request that I would again visit the great river of Meath, make further observations, collect additional information, include the Black-water, and publish the materials thus obtained, in the form of an illustrated Hand-book for these charming but hitherto neglected streams.

It may be regarded as a boast, but it is nevertheless incontrovertibly true, that the greatest amount of authentic Celtic history in the world, at present, is to be found in Ireland; nay more, we believe it cannot be gainsaid that no country in Europe, except the early kingdoms of Greece and Rome, possesses so much ancient written history as Ireland. It is, however, generally speaking, unknown; heretofore it has neither been appreciated nor understood; until very lately the

great mass of Irish historic manuscripts was scattered and inaccessible. Many of these have, within the last few years, been collected together, and several have been translated and published; others are in course of publication, but in forms which (though no doubt the very best) are not within reach of the general reader, neither would they be always understood or valued by such. To popularize these—to render my countrymen familiar with facts and names in Irish history—has been one of the objects I have had in view in the historic portion of this work. Materials for books of this description are now so abundant that the chief difficulty is in selection.

Throughout the following pages I have alluded to the want of a correct Irish history, and the neglect of such histories of our country as we possess. I would here again (because I do not think it can be done too often) revert to this subject. The Board of National Education,—with whose scheme of instruction, so far as it goes, I agree, and many of whose books I very much admire,—while they teach the history of Kamtschatka, and the geography of the Andes, never once allude, in their system of education, to the national history of the people they are employed to teach. Nor need this be wondered at, when I mention the fact that an eminent publisher of my acquaintance having, some few years ago, in the issue of a popular, and, to my mind, a very unprejudiced abridgment of Irish history, written a circular to the different schoolmasters in Ireland, calling their attention to this little work, was answered by some of those who deigned to honour him with a reply, that the time devoted by their pupils to the study of history of any kind was barely sufficient for those of Greece, Rome, and England! How long will parents and guardians submit to this? That Irish history is looked upon as a fable by many ignorant persons is not surprising; but that the ordinarily educated—

and, above all, that the learned of any country—should be unacquainted with the materials of our Irish history, is a lamentable fact, and shows either want of knowledge, or utter indifference to the subject.

I was forcibly reminded of this a short time ago, in casting my eyes over that very beautiful book, Macaulay's "Lays of Ancient Rome," in the preface to which, when speaking of the early literature and metrical romances on which the history of most nations is founded, the great modern historian very justly says: "A man who can invent or embellish an interesting story, and put it into a form which others may easily retain in their recollection, will always be highly esteemed by a people eager for amusement and information, but destitute of libraries. Such is the origin of ballad poetry,—a species of composition which scarcely ever fails to spring up and flourish in every society, at a certain point in the progress towards refinement. Tacitus informs us that songs were the only memorials of the past which the ancient Germans possessed." And so the author passes in review the early "poetic literature" and "ancient lays" of the various nations of the earth; the Gauls, the primitive Teutonic and Celtic races of the European continent, the Danes and Anglo-Saxons, the Welsh and Scottish Highlanders, the Servians and Peruvians, the people of Persia and Turkomania, the Sandwich Islanders, the Etruscans and Castilians, the ancient Greeks, and even the inhabitants of Central Africa, whose bards have sung, and whose traditions have perpetuated the story of their early history;—all, except that of the neighbouring island, Ireland, are deemed worthy of a place in the preface of the English statesman and historian.

But worse than this, the last historian who has attempted to compile and arrange the annals of our country knew little

or nothing of those rich sources of knowledge in the ancient Gaelic manuscripts from which alone our history can be obtained. Thus remarks Mr. O'Donovan, in his preface to *The Battle of Magh-Rath*, which, with the name of the monarch who fought it, is not even once alluded to in Moore's *History of Ireland*: "Mr. Moore is confessedly unacquainted with the Irish language; and the remains of our ancient literature were, therefore, of course inaccessible to him. That great ignorance of these unexplored sources of Irish history should be found in his pages is, therefore, not surprising; but he ought to have been more conscious of his deficiencies in this respect than to have so boldly hazarded the unqualified assertion that there exist in the Irish annals no materials for the civil history of the country."

The scientific as well as the literary and archæological character of our country has not stood still of late years; our University and our schools of medicine have borne an honourable part in the advance of astronomy, mathematics, and medicine. Three new colleges have been lately established. The greatest telescope, the most scientific magnetic observatory, and the first atmospheric railway, were constructed in Ireland. A survey, the most accurate in its details, and the most extensive in its objects, that any country in Europe has yet been submitted to, has just been completed; and the last enumeration of the people has been, with justice, pronounced by the London Statistical Society, "a model for a Census." Unfortunately for the country, either from the indifference of ministers, the unjust economy which the English Exchequer has ever pursued towards Ireland, or from mismanagement at home, —perhaps from a little of each or all,—the memoirs of the Irish Ordnance Survey have—I would hope only for the present—been abandoned. I would go further, and say, that

as the materials which have been collected for them are the property of the country, and are a necessary portion of her history, they must some day, sooner or later, meet the light; and yet—can it be believed?—an endeavour was made not long since to remove these records to Southampton! I need only refer to the memoir on Templemore, as a specimen of what these county histories would be.

The Board of Works has of late done good service, particularly to the inland navigation of the country; and our agricultural and industrial resources have also, within the last few years, received an impulse which we would ardently anticipate may be both permanent and extensive.

In the last ten or fifteen years much has been done to develop the literary resources of this country. The Royal Irish Academy, the old chartered patron of Irish literature and antiquities, has awoke from the apathetic slumber in which it remained during the early part of this century, when papers and communications were admitted into its Transactions, of which, some were not founded on fact, and others, by the crude and fanciful theories of their authors, brought upon us the ridicule of other European nations; while, at the same time, it permitted some of our oldest and best records, and most valuable antiquities, to pass into another country. Of late, however, a zeal and an enthusiasm, and, we would hope, a nationality, unparalleled in the history of any other Irish institution, has been infused amongst its members and its council, and it has amply redeemed its past indifference, by creating a museum of Celtic and early Christian antiquities, unexampled in the British isles, and only surpassed (if it be surpassed) by that of Copenhagen, which is, however, inferior to our's in this respect, that the same historic references do not exist there with regard either to the Pagan

or Christian antiquities, but particularly the latter, which are also less numerous and interesting. And although the Pagan antiquities at Copenhagen are much more numerous than our's, it does not appear that the types of form or structure are much more diversified than those which the museum of the Irish Academy possesses. Why has the catalogue of this, our national collection, been so long delayed? Why is not each new specimen of interest figured in the Proceedings of the Academy, and its description thus widely distributed among the public? We know that many valuable acquisitions have been gained by visitors calling accidentally at the museum; many more would, we feel convinced, find their way into this collection, if some general and popular means existed of giving an account of those which are there already. The miserable pittance which is doled out to this noble institution by Parliament may be urged as a reason against this project; but, while we acknowledge the full effect of all this, we would suggest that wood-engraving, which is quite applicable to all purposes of antiquarian delineation, and is now remarkably cheap, should be extensively employed; and as most of the antiquities have already been drawn at the expense of the Academy, even fifty pounds a year would do much towards illustrating them. By Dr. Petrie's great work upon the Ecclesiastical Architecture and Round Towers of Ireland, the Academy has widely extended its fame, and the first great impetus has been given to the true eclectic investigation of Irish history and antiquities. But not by deep archæological research alone, but by his popular sketches in the Penny Journals, has Dr. Petrie generated a taste, and created a school of Irish Archæology. He should have written this book; his profound knowledge of Irish history and antiquities,—his intimate acquaintance with the subject on which it treats,—his graphic powers of descrip-

tion, and his surpassing abilities as an artist, all combine to render him better suited for the task than any other man living. Because he has not done so I have ventured, *sed longo intervallo*, to describe the scenery presented along the Boyne and the Blackwater, to direct public attention to their antiquarian remains, and to popularize their annals and history.

We have lately had a proof of the growing interest which is taken in the antiquarian department of our Academy, not only by our own, but by other nations. The Danish government sent over a gentleman of distinguished merit, great shrewdness of observation, and most captivating manners, to investigate and report upon our collection. With a becoming spirit of liberality, the Academy presented to the Royal Society of Northern Antiquaries, through Mr. Worsaae, to whom I have just alluded, a splendid series of drawings, illustrative of our finest antiquities, and also several specimens of the antiquities themselves, of which duplicates existed. In return, that learned body have lately presented a collection of Danish antiquities to the Academy. This is, I believe, the first instance of good feeling between the Irish and the Danes which our annalists have as yet been able to record.

In the historic department, the Irish Archæological Society has done more to elucidate the annals and records of our country than had been effected for the century previous. Private individuals and enterprising publishers are likewise engaged in this good work. The publication of the *Annals of the Four Masters* by Messrs. Hodges and Smith, is the greatest acquisition ever made to Irish history. The Celtic Society also promises well in this department of research. We are, moreover, happy to find that this body does not consider itself a mere transcriber, translator, and commentator on the written labours of the past; but has also constituted itself a conservator of those monuments and architectural remains which the Van-

dalism of modern commissioners—some of whom possess little knowledge of, and less taste and interest in, those relics that teach the antiquary, mark the historic era, or adorn the landscapes of our native land—would destroy.

The nonsensical fancies of Vallancey and his school of imaginary antiquaries have long since been dispelled by the labours of Petrie, O'Donovan, Hardiman, Todd, Eugene Curry, Reeves, Graves, and other modern investigators.

Strangers even who lately visited our soil have become infected by the general feeling of enthusiasm which has pervaded all classes and parties, and have ably and generously devoted the pages of their periodicals to Irish history and antiquities.*

Her Majesty Queen Victoria, with her illustrious consort, has just visited this portion of her dominions, and by their coming amongst us, have done more to put down disaffection, and elicit the loyal feelings and affections of the Irish people, than armies thousands strong, fierce general officers, trading politicians, newspaper writers, and suspension of the Habeas Corpus Act, &c. &c. Let us hope that her welcome visit will be soon repeated.

I have now but to express my obligations to those kind friends who have assisted me in the compilation of the historic and antiquarian portion of this work. First, to my excellent friend, John O'Donovan,—whose labours in the cause of Irish Archæology are already so well known to the learned in Great Britain, and which are so frequently referred to in this book, that it seems scarcely necessary to allude to them here;—who has assisted me largely, and devoted much time and attention in the revision of proofs, and in pointing out the sources

* See the Historical Tableaux, in numbers 160 and 162 of Chambers's Edinburgh Journal for 1847.

from which I might gain illustrative materials. I know no man possessing the same amount of knowledge, gleaned with the same labour and research, who is more liberal of it than Mr. O'Donovan, and to this every one who has been engaged, either in strict archæological research, or, like myself, in popularizing our history, must bear testimony.

The Very Reverend Richard Butler, Dean of Clonmacnoise, has also placed me, as regards this work, under many obligations. His long residence at Trim, of which he has become the historian, and his intimate acquaintance with the ancient history of the county of Meath, render him better fitted for the task of a critic upon a book treating of the Boyne, than any other living antiquary; and in the same generous manner as Mr. O'Donovan, he has always assisted those who require the aid of his matured judgment and extensive reading.

I have to express my obligations to my friend George Smith, the enterprising publisher of so many works connected with the history of Ireland, for permission to examine and extract from the early portion of that part of the Annals of the Four Masters now in course of translation by Mr. O'Donovan. In the most generous manner he placed (with the Editor's permission) the unpublished sheets of that great work at my disposal.

In writing the original sketches of the Boyne, which appeared in the Dublin University Magazine, I derived many valuable hints from my learned friend, Mr. Eugene Curry.

Indeed, without the assistance of so many generous as well as learned friends, I could not have produced this work in its present form. I do not profess to be an antiquary or an historian; other avocations of a professional nature occupy more of my time than the acquirement of strict and exact archæological knowledge would permit; but I have endeavoured,

with the assistance of my friends, and by means of such sources of information as were readily at hand, while I popularized our history and sketched our scenery (chiefly as a source of healthful relaxation from more fatiguing pursuits) to present nothing to the reader that was not strictly true. Had more time been devoted to the subject, this might, perhaps, have been made a better book, but we doubt whether it would be more suitable for the purpose for which it is intended.

With the exception of the illustration upon the first page and the woodcut at page 67, which were drawn by Mr. Grey, and the drawings by Mr. Connolly, engraved at pages 38, 40, and 195, all the illustrations of this work have been sketched, and afterwards drawn on wood by Mr. Wakeman, who is already so favourably known, both as an artist and an antiquary, by his useful *Handbook of Irish Antiquities*, and who combines great artistic skill with a peculiar knowledge of the salient points of the antiquities or ruins he may be engaged in illustrating. I am likewise indebted to Mr. Wakeman for much local information, which his residence on the bank of the Boyne for the last two years enabled him to collect.

Mr. Hanlon, the wood-engraver, has also borne no inconsiderable part in the illustrations of the *Beauties of the Boyne*; and I cannot but congratulate Mr. Gill upon the admirable manner in which the work has been printed,—printed, moreover, within the short space of one month.

And last, though not least, whatever pleasure or profit the fireside reader or the tourist may derive from the perusal of this little book, is chiefly due to the enterprise of its spirited publisher, Mr. M^cGlashan.

CONTENTS.



	PAGE.
ITINERARY,	xxi

CHAPTER I.

THE RIVER'S SOURCE AND HISTORY.

Introduction—The Beauties of the Boyne ; its Scenery and Historic Interest ; its Archæological Remains—Description of the ancient Kingdom of Meath ; its History and Topography—The Plains of Breghia—The English Conquest—Dearvorgail, the Helen of the Irish Iliad—The Pale—Geographical Description of the River—The Source, Origin, and Derivation of the Boyne—Trinity Well ; its Legends and Antiquities—The Story of Boan and Dabella,	1
---	---

CHAPTER II.

FROM CARBURY TO CLONARD.

Carbury ; its ancient History, Hill, and Castle—Genealogy of the Duke of Wellington—The Boyne's Progress through the King's County—Edenderry—Ruins of Monasteroris—The Berminghams—Alteration of English into Irish Names—Return to Kildare—Kinnafad Castle—A Battle-field ; the Men who fought there, and their Weapons—Grange—The Hill of Carrick ; its Church, Well, and Castle—View of the Plains of Leinster—Toberaulin—Lady Well—Irish Holy Wells—Ballybogan ; its Church and Priory,	27
---	----

CHAPTER III.

CLONARD, AND THE BOYNE TO TRIM.

PAGE.

Clonard—Descriptions of Caesar Otway—The Battle of 1798—Ancient Seat of Learning—History of St. Finian—The Abbey, Monastery, and Round Tower—Disasters and Desecrations, ancient and modern—Antique Font and Lavatory—Recovery of an Ecclesiastical Stoup—The Pagan Remains at Clonard—The Moat and Fort; Speculations on their Origin and Uses—The Battle-field of Rathcore—The Battle of Bolg-Boinne—Ticroghan—Donore Castle—The Boyne to Trim—Trimblestown,	55
--	----

CHAPTER IV.

TRIM.

Trim; First Impressions; History, ancient and modern; Accommodation; Origin and Foundation—St. Mary's Abbey and Yellow Tower—Geoffrey De Geneville—Military Buildings—The Early Irish Castles—The Saxon, who?—Death of Hugh De Lacy—The present Castle of Trim; its Chapel and Mint—Talbot's Castle—The early Residence of the Duke of Wellington—Laracor, Swift, and Stella—Newtown; its Abbey, Tombs, and Ruins.—Monastic Castle and Priory of St. John, . . .	79
--	----

CHAPTER V.

FROM TRIM TO NAVAN.

Scurlogstown; its Tumulus, Church, and Castle—Trubly—Bective Abbey—Interment of Hugh De Lacy—Clady; its Subterranean Chambers, Church, and ancient Foot-Bridge—The House of Cletty—Riverstown Castle—Tara; its History and Associations; its Topography—Raths—The Lia-Fail—Skreen—Hymn of St. Patrick—Ardsallagh—St. Bridget's Well—Kilcarn Font—Athlumney Castle; its last Occupant—Navan; recent Discoveries there,	103
---	-----

CHAPTER VI.

THE BLACKWATER.

	PAGE.
General View of the Blackwater of Meath; Origin of its Name—St. Patrick's Curse—The River's Source at Lough Ramor—Virginia—St. Kieran's Well, Church, and Crosses—Square Forts—Hill of Lloyd—Kells; its Early History—House of St. Columbkille—Round Tower—The Cross—Annals of Kells—Headford—Tailtean, one of the ancient Seats of Monarchy; its early History; its Games, Battles, Fairs, and Marriages—The present Appearance of Teltown; its Hill, Rath, and Legends—St. Patrick and King Loeghaire—Donaghpatrick; its History; the Moat and Churchyard—The Church and Castle of Lisacarton—Rathaldron; its Castle—Monumental Cross of Nevinstown, .	136

CHAPTER VII.

THE BOYNE FROM NAVAN TO SLANE.

Donaghmore Round Tower—Blackcastle—Babes' Bridge—Ardmulchan—Dunmoe—Stackallan Bridge—Castle Dexter—Beauparc—Fennor—Slane Castle—The Hermitage of St. Eric—View from the Hill of Slane—The arrival of St. Patrick—Name and Origin of Slane—Ferta-Fear-Feig—The Monastic and Ecclesiastical Ruins—An ancient Tomb, .	159
--	-----

CHAPTER VIII.

THE ROYAL CEMETERY OF BRUGH-NA-BOINNE.

The Senchas-na-Relic—Brugh-na-Boinne—The Interment of King Cormac—Ros-na-Righ—Knowth—The Tumulus of New Grange; its Entrance, Passage, and Chamber—Crypts in the Interior—Antique Carvings—Ancient History of this Mound—Dowth—Recent Examination of its Interior—Description of its Chambers and Passages—Rossan—Cloghlea—Netterville,	184
---	-----

CHAPTER IX.

THE ETHNOLOGY OF THE ANCIENT IRISH.

PAGE.

Modes and Means of studying Ethnology—Who are the Irish?—Historic References—What Remains of the original Stock exist—The Celts—The Fírbolgs—The Tuatha De Danaan—Early Irish Forms of Burial—Tumuli, and their Contents—Cromlechs—Kistvaens—Sepulchral Urns—Incineration—Scandinavian Researches—Crania of the ancient Irish—Battle-fields—Advice to Tomb-Openers,	212
---	-----

CHAPTER X.

THE BATTLE-FIELD OF OLDBRIDGE—DROGHEDA.

The Boyne in Louth—The Campaign of 1690—Description of the Battle-field of Oldbridge—Position of the Irish Army—The Hill of Donore—Position of the English Army—The King's Glen—Plan of the Battle of the First of July—Wounding of King William—The Battle of Rossnaree—Turning of the left Wing of the Irish Army—The Passage of the Boyne—Death of Schomberg—The Fight upon Donore—The Retreat to Duleek—What Effects have followed—New Ballad of the Boyne Water—Drogheda; its early History; its Antiquities; its Walls—St. Laurence's and the West Gate—St. Mary's Church—The Magdalen Steeple—The Mouth of the Boyne—Colpe—The Maiden Tower,	241
---	-----

LIST OF ILLUSTRATIONS.

	PAGE.
1. Bird's-eye View of the River Boyne,	1
2. Carbury Castle,	27
3. The Ruins of Monasteroris,	35
4. Kinnafad Castle,	37
5. Antiquities found in the Boyne at the Pass of Kinnafad,	38
6. Skulls found in the same Locality,	40
7. The Church and Castle of Carrick-Oris,	40
8. Ballybogan Priory Church,	51
9. The ancient Font of Clonard,	64
10. Antique Vessel found at Clonard,	67
11. The Mound of Clonard,	68
12. The Castle of Donore,	77
13. The Yellow Steeple and Sheep-Gate of Trim,	84
14. The Castle of Trim,	94
15. Monastic Ruins at Newtown Trim,	99
16. The Dillon Monument at Newtown,	100
17. Scurlogstown Castle,	104
18. Bective Abbey,	108
19. The Cloisters at Bective,	111
20. The ancient Bridge and Church of Clady,	113
21. The Lia Fail, or Stone of Destiny at Tara,	124
22. Cannistown Church—Choir Arch,	129
23. Ancient Font at Kilcarn,	130
24. Sculptures on Kilcarn Font,	131
25. Ditto, ditto,	ib.
26. Athlumney Castle,	132
27. St. Kieran's Cross at Castle Kieran,	139
28. St. Kieran's Well and Tree,	141
29. St. Columbkil's House at Kells,	144
30. Window in ditto,	145
31. The Round Tower of Kells,	146
32. The Great Cross of Kells,	148
33. Liscarton Castle,	156
34. Donaghmore Church and Tower,	160
35. Sculpture over Door of Donaghmore Round Tower,	162
36. Sculptured Stone at Ardmulchan Church,	165

	PAGE.
37. Dunmoe Castle, with the Boyne and Mill, &c.	167
38. Castle Dexter,	173
39. Slane Castle,	174
40. The Hermitage of St. Erc, at Slane,	175
41. Remains of sculptured Tomb at ditto,	ib.
42. The Ecclesiastical Ruins at Slane,	178
43. Ancient gable-shaped Tomb at Slane,	182
44. The Mound of New Grange,	189
45. Pillar-stones in the Circle of New Grange,	190
46. The Entrance of New Grange, with its sculptured Stones,	192
47. Sculptured Stone at Mouth of New Grange Cave,	193
48. One of the upright Groove Stones in the Passage of New Grange,	194
49. The eastern Recess in the Chamber of New Grange,	195
50. Illustrations of the spiral Carvings at New Grange,	197
51. ————— the lozenge-shaped Carvings at New Grange,	198
52. ————— the oval and semicircular Carvings at New Grange,	ib.
53. ————— the zig-zag Carvings at New Grange,	199
54. ————— the supposed Writing at New Grange,	ib.
55. ————— the Fern-shaped Carving at New Grange,	200
56. The double Basin, or shallow Stone Sarcophagus,	201
57. The single Basin in the Western Crypt,	ib.
58. The Mound of Dowth prior to the recent Excavation,	204
59. The Entrance to the Passage at Dowth,	206
60. Carvings on the Stones at Dowth,	207
61. One of the Pillar-Stones at Brugh-na-Boinne,	210
62. Remains of a Stone Circle at Cloghlea,	211
63. Globular Scandinavian Skull,	226
64. Elongated ditto,	227
65. Skull of the long-headed Irish Race,	229
66. Skull of the round-headed Irish Race,	232
67. Skull of St. Donatus,	236
68. The Obelisk on the Battle-field of the Boyne,	241
69. St. Lawrence's Gate, Drogheda,	259
70. The West Gate, Drogheda,	260
71. Ruins of St. Mary's Church, Drogheda,	260
72. The Magdalen Steeple, Drogheda,	262
73. The Maiden Tower and Finger,	263

TO THE BINDER.

74. Plan of the Battle of the Boyne,	<i>To face page 248</i>
75. Map of the Boyne and Blackwater,	<i>At the end.</i>

ITINERARY.

THE following directions with respect to the best mode of seeing the beauties of the Blackwater and Boyne will be found useful to the tourist.

The River Boyne may be visited, and its various objects of interest examined, comfortably, in three days. The Blackwater will require a fourth; and a distinct route from Navan to Virginia, along its banks, is given at p. xxiii of this Itinerary. As railways now approach the river at three different points,—at Enfield, Navan, and Drogheda,—tourists can return to Dublin, if they wish, each night, or, proceeding continuously down the river, they can divide the journey into three portions, sleeping the first night at Trim, the second at Slane, and the third at Dublin, as neither Navan nor Drogheda as yet present the very best accommodation.

The most ready mode of access to the Boyne's source, at Carbery, in the county of Kildare, is to proceed from the Broadstone, Dublin, in one of the early morning trains which starts by the Midland Great Western Railway, to Enfield, which can be reached in about an hour and a half. Here outside jaunting-cars can be hired at the rate of sixpence per mile for two persons, or one can be hired for the day, or by the job. From seven shillings and sixpence to ten shillings per day, with a *douceur* to the driver, will generally satisfy, but in every instance a special bargain should be made with the carman before starting. The tourist should first proceed to Carbery, distant about six miles, where the hill and Castle of Carbery should be visited, and afterwards the source of the Boyne, at Trinity Well, in the adjoining demesne of Newbery. About a mile and a half from Enfield, the Edenderry road through Carbery crosses the Blackwater rivulet, one of the tributaries of the Boyne; then the neat little village of Johnstown, and between that and Carbery we pass Mylerstown church and castle, about a mile to the right of the road. This latter

may be visited by those who have time to spare, and who had left Dublin by the early morning train.

From Carbery to Edenderry is not quite four English miles. Except the old castle, which is difficult of access, there is very little to delay the tourist in this town. Two roads—one direct to the Hill of Carrick, the other the most circuitous, by Monasteroris, Kinnafad, and Grange—lead downward, to Ballybogan. The former is the shorter, the latter by far the most interesting. From Edenderry to Monasteroris is not quite two miles; from thence to Kinnafad a mile, and by the Castle of Grange to the Hill of Carrick, two and a half miles more. The next point of interest is Ballybogan, four miles distant from Carrick, and eight from Edenderry. Here two roads, one on each side of the Boyne, lead to Clonard. If the tourist intends to return to Dublin the same night, the northern road upon the left bank of the river, by which the ruins of Ticroghan castle and chapel may be visited, will be found not only the most interesting, but the shortest. From Ballybogan Bridge to Clonard is two miles. Having visited the moat and the site of the ecclesiastical ruins adjoining, the tourist can either continue on to Trim, which is about twelve English* miles distant, by crossing to the right bank of the river, at the Boyne Aqueduct, or he can return by the Great Western road, over Leinster Bridge, to the railway station at Moyvalley, which is about four miles distant; and, taking the evening up-train from Mullingar, return to Dublin the same night. If the latter course is pursued, the tourist should proceed by railway to Moyvalley the second day; then visit Clonard; from thence proceed down the river by Trim to Navan, where a branch of the Drogheda railway will take him up to Dublin in something more than two hours.

Trim, and the Boyne from thence to Navan, one of the most interesting portions of the excursion, can be visited in a day, by taking a car from Enfield either direct to Trim, or by Dangan and Laracor: and proceeding from Trim, by Newtown and Scurlogstown, to Bective. Here we have again to make choice of roads; on the one side we have Clady, and on the other Assey, Rivers-town, Bellinter, and Tara.

To follow the route in detail from Trim downward, the most pleasing points of view will be gained by proceeding on the right bank of the river, then crossing over to visit the ruins of Newtown, about a mile distant, returning to the right bank, and proceeding to Scurlogstown, Trubly, and the Bridge of Bective, distant from Trim four miles and a half, and from Navan three and

* In this neighbourhood, and about Navan, distances are still counted in Irish miles.

a half miles. Here we cross to the left bank, and having seen the Abbey, proceed upon the same side to visit Clady, which is not a mile distant, and returning by the same route to Bective Bridge, follow the road upon the right bank to Riverstown Castle, and thence ascend the hill of Tara, which being seen, it will be found most advisable to proceed to the bridge of Bellinter, and cross over to the left bank, and then, passing through the demeane of Ardsalla, visit Cannistown. We next cross the Boyne at Athcarne Bridge, in order to see the font at Johnstown, described at page 130, about half a mile distant. It is then optional to proceed to Navan by the road upon the right bank of the river, by which one of the best views of Athlumney Castle can be gained, or to return again to Athcarne Bridge.

At Navan the tourist will decide whether he visits the Blackwater then, or makes a separate excursion to it afterwards. Cars can be hired to proceed by Kells to Virginia. The tourist will find it best in so doing to proceed up the river by Liscarton Castle, upon the left bank, to Kells, where the coach-road crosses to the right bank, and, having visited St. Kieran's church and well at Castlekieran, the most distant point of interest upon the Blackwater, and to return by Teltown, Donaghpatrick, and Rathaldron, to Navan, by the left or northern road. Coaches, however, proceed daily to Kells and Virginia, at both of which places cars can be procured to return to Navan. The examination of the Blackwater, by any of these means, will occupy an entire day. Tourists can leave Dublin by one of the early trains and go by Drogheda to Navan, from whence public conveyances proceed by Kells to Virginia; or cars can be hired at either of these places to visit the Blackwater, and return in time to catch the up-trains from Navan to Dublin.

From Navan to Kells is nine English miles; from Kells to Castlekeiran three; and to Virginia from the latter place nine miles.

From Navan to Slane we have again choice of roads: the most advisable plan will, however, be found to visit Donaghmore church and round tower, which is about a mile from Navan, on the left bank of the river, and then, returning to Navan, either procure a boat to proceed to Slane, or walk along the rampart or track-way of the canal. If neither of these two latter modes are feasible, Slane, being distant from Navan about six Irish miles, may be reached by either the eastern or western road; upon the former we have Ardmulchan and Beauparc, and upon the latter, Donaghmore, Dunmoe, Stackallan, Baronstown, and Slane demeane. A narrow by-road, about three-quarters of a mile long, leads down from the main road to Dunmoe.

Slane hotel will be found a very desirable residence for those who can spend a few days in visiting the charming scenery of this part of the Boyne, and excursions may be made from it to Navan, Tara, Trim, and the places intermediate, as well as to Kells, Duleek, the mounds of New Grange and Dowth, the field of the Battle of the Boyne, Mellifont, and Monasterboice.

From Slane to Drogheda, a distance of seven miles, the road upon the left bank of the river presents most objects of interest. The tourist should visit in succession, Knowth, New Grange, and Dowth, which can be reached by a by-road branching off near the first of these monuments. Having seen these antiquities and those in Netterville Park adjoining, we proceed by the little bridge over the Mattock river, and join the Slane road again near the ford of Oldbridge. Having examined the battle-field, should time permit, or that the tourist has slept at Slane upon the previous night, a detour may be made from Oldbridge, by the road leading up through King William's Glen to Mellifont, about one mile distant; from thence to Monasterboice is two, and having seen the latter, one can easily get upon the great northern road, and reach Drogheda, which is distant from Monasterboice four miles, time enough to get to town by the last train. Cars may be obtained at Drogheda to visit any of the places in the vicinity, as Donore, Mornington, and Maiden Tower. We suppose there will be a station on the Drogheda and Navan Railway near Slane. Fraser's admirable Guide-Book, and the Monthly Time Bills of the railways, will be found of great service.


THE BOYNE.

CHAPTER I.

THE RIVER'S SOURCE AND HISTORY.

INTRODUCTION.—THE BEAUTIES OF THE BOYNE; ITS SCENERY AND HISTORIC INTEREST; ITS ARCHAEOLOGICAL REMAINS.—DESCRIPTION OF THE ANCIENT KINGDOM OF MEATH; ITS HISTORY AND TOPOGRAPHY.—THE PLAINS OF BREGHIA.—THE ENGLISH CONQUEST.—DEAEVORGAIL, THE HELEN OF THE IRISH ILIAD.—THE PALE.—GEOGRAPHICAL DESCRIPTION OF THE RIVER.—THE SOURCE, ORIGIN, AND DERIVATION OF THE BOYNE.—TRINITY WELL; ITS LEGENDS AND ANTIQUITIES.—THE STORY OF BOAN AND DABELLA.

AMONG the many scenes of beauty and of interest with which this fair island abounds, we know of none which combines such variety of the former or so many objects of the latter as the "Pleasant Boyne." And although this river does not burst upon us amidst the wild and stern grandeur of the mountains, with dashing torrent o'erleaping in its rapid course all the barriers of nature, or making its echoes heard among the deep hollows of



dark-wooded dells, but pursues the quiet, even tenor of its way, through a flat but rich and fertile country, winding by "its own sweet will" through broad savannahs and by green inches, where the calm ripple of its placid waters disturbs not the song of the mavis; still it possesses charms and beauties, and that, too, without a rival in this or perhaps any other country. Slow, calm, and tranquil in its early course, the mower whets his scythe in the deep meadows by its brink, and the reaper gathers the corn from the very margin of its waters; the swift and the martin skim over its clear surface, and the robin sings in the ancient thorn that rises out of the adjoining hedge-row. The very may-fly, as it lights upon it, breaks the mirror of its surface. The wide-spreading circles which mark the springing of the trout, or the timid breathing of the roach, are all, save the flapping of the water-hen, or the easy paddle of the baldcoot, that disturb its placid bosom.

In this gentle stream there is no inequality—no roar of waters nor spray of cataract; it is not boisterous nor yet sluggish; neither broken by the sudden rapid, nor calmed by spreading into the broad lake; but, pure and undefiled, it springs from the crystal fountain of the living rock,—its source sanctified by religious veneration, and commemorated in legend and in song; serene and peaceful, like a true philosopher, it glides noiselessly on, in deep but calm repose, bestowing the blessings of fertility on the counties through which it flows; bearing on its bosom the intercourse which socializes man; enriching, beautifying, and civilizing, it receives in return the homage of its tributaries, and finally mingles with that eternity of waters, the sea. As Clutterbuck says of his story, in "The Fortunes of Nigel," "commencing strikingly, proceeding naturally, ending happily,—like the course of a famed river, which gushes from the mouth of some obscure and romantic grotto, then gliding on, never pausing, never precipitating its course, visiting, as it were, by natural instinct, whatever worthy objects of interest are presented by the country through which it passes." Winding through the heart of the ancient kingdom of Meath, green homesteads, picturesque villages, peaceful hamlets, and thriving towns rise on its banks; the hand of man has turned its power to good account, and mills and factories draw their animation from its waters; the freights of foreign lands, the luxuries of

far-distant countries, are borne on its stream towards the interior, and the produce of our own soil and the industry of our people is carried downwards on its tide. Deep hanging woods and rich plantations of noble parks and extensive demesnes, where the willows dip into its calm waters, and the oaks and elms of centuries are mirrored in the wave beneath, stretch for miles along its course, where

“Slow, and in soft murmurs, nature bade it flow.”

Towards its centre, and as it nears the sea, its banks become more elevated, their outline more picturesque. Here, rising abruptly from the water's edge, their castled crags, bending over the stream, remind us of the scenery that characterizes the Rhine between Cologne and Mayence; in other places, sloping gradually from the river, their sides are clothed with foliage of the deepest, darkest green, piled up in waving leafy masses to their very summits, so that the sun itself is hidden (except at noon) in many places from its dark waters. The summits of many of these verdant banks are crowned by ruins of castles, towers, and churches, feudal halls, and high baronial keeps, still noble even in their decay, and forming, as they are cut clear and sharp against the azure blue beyond, pictures in the landscape, unsurpassed in grace and beauty by any in the land. In the broad lawns that here and there interpose between these verdant banks and steep o'erhanging precipices, we find the noble mansions of some of the highest of our nobility, and many of the most memorable ecclesiastical remains—the cell of the hermit, the cloister of the monk, and the cross of the pilgrim—that Ireland, rich as she is in relics of the past, can boast of. Ancient stone circles, massive cromlechs, and numerous green mounds, raised by our Pagan ancestors, some clothed with velvet sward, but others fringed with young plantations, are thickly interspersed among the more attractive objects that catch the eye, as it descends upon the limpid surface of the Boyne. Highly cultivated lands, richly ornamented seats, and a population, generally speaking, more comfortable, more intelligent, and more advanced in civilization than the majority of our peasantry, may fill up the outline we have faintly and briefly endeavoured to draw of the general characteristics and present appearance of this celebrated river; and though Spencer has not sung its praises, nor Raleigh gossiped upon its banks, it has

been hallowed by events the most interesting in our country's annals. So memorable in ancient history, and so rich in monuments of the past is it, that we fear not to assert that the history of Ireland might be written in tracing its banks. Many a broad smiling plain through which it flows, now green with waving corn, or perfumed and decorated by the wild flowers of a pasture land, or by some delicate female hand cultivated into the elegant garden, in the bowers of which the birds of spring are singing, was once the scene of mortal strife, and crimsoned with the blood of warriors, where the clang of battle, the shout of the victorious, the groan of the dying, and the prayer of the suppliant, alone were heard. Scarcely a ford upon this river but was disputed in days gone by; every pass was a Thermopylæ; the bardic annals teem with descriptions of its battles; the fairy lore of other days yet lingers by its tranquil waters; and scarcely a knoll, or mound, or rock, or bank in its vicinity but still retains its legend. The peasant even yet paddles his corragh, or frail canoe of skins, across its waters, and many of the superstitious rites and customs of our ancestors are still observed by the people of that district. How time runs on, and science widens the circle of her power, yet man and many of his customs remain the same for centuries;—on one side of the bridge of Drogheda may still be seen the wicker corragh, with its horse-skin covering, the same in design and execution, perhaps, as floated there a thousand years ago; and on the other we find the latest invented and most improved screw-steamer!

The plains of Midhe, and the flowery fields of Bregbia, through which the Boyne flows, appear to have been the first cultivated in Ireland; and it is more than probable that one of the earliest waves of population which reached our island passed up the stream of this great river, and that the aborigines settled amidst the wooded hills and deep alluvial plains upon its banks, and have left their bones in the numerous barrows and tumuli still remaining upon its shores. Beyond all doubt, the earliest undoubted kings of Erin reigned upon its banks, where also the earliest laws were framed, the earliest poems sung, and the most profound druidical mysteries celebrated. Soldiers and sages, bards and brehons, have commemorated many of its localities; the romance of Irish history is laid amidst the scenery of this river, and much of the imagery of our earliest

poets was drawn from this fertile source. Christianity entered Ireland through this sacred stream; Patrick first landed at the Boyne's mouth, and raised the beacon of the cross at Slane; his first sermons were preached, and his first conversions took place

"Where, in delightful streams,
The Boyne, the darling of the ocean, flows."*

Foreign invaders, the Dane and the Norseman, first entered this kingdom on its waters. The earliest abodes of learning, and the most renowned schools of Christian philosophy which our annalists record, had their seats by its margin; parliaments and councils were held in its castles; and kingdoms—in battles fought by kings—were lost and won upon its banks.

These are not the fanciful speculations of the enthusiastic but imaginary writers of the last century; the monuments speak for themselves, their architecture tells their date and purpose; many of the historic annals which relate these circumstances, formerly difficult of access, and known or capable of being understood but by a few, have been recently published in the English tongue, and have satisfied even the most incredulous as to their antiquity and authenticity. It is acknowledged by all capable of forming an opinion on the subject, that the history of Ireland has yet to be written, but the materials for it are now being collected, and rendered accessible and instructive, by competent authorities, with an interest and an enthusiasm, and, moreover, with a critical regard to the simple and unbiassed statement of the authors, alike honourable to the country, and creditable to those engaged in the production of these works. We are not vain enough to boast of, nor credulous enough to believe, all that is related in many of the early Irish manuscripts, no more than we place implicit faith in all that is told in the great Grecian Epic, or that historians have set down in the primitive histories of other kingdoms; but we receive them as shadows of great historical events, and as highly characteristic of the manners and customs of the times and people they describe. And it may be here remarked, that so far from critical investigation or research

* "In regione BREG prope fluvium pulcherrimum et fertilem Boyn."—*Ussher, Primord.*, p. 850.

invalidating the testimony of our early Irish bards and annalists, it has been found, and every day's experience confirms the fact, that the more we collate, examine, and compare, manuscript with manuscript, author with author, and both with those monuments and antiquities which have still remained undefaced, and the more we test them with contemporaneous history, the more the shadow will be found to correspond with the substance of the truth they figure.* This is the age of true eclectic investigation. The country, notwithstanding all her present poverty and privation, is not only ripe for its reception, but cries loudly for her history. It is a fact strange but true, that either from prejudice, apathy, or indifference, while the histories of Greece, Rome, England, and Scotland, are taught, or at least boys are compelled to read them, at the schools for the sons of the Irish gentry and middle classes, the history of Ireland, such as it is, is never heard of.

In the historical remarks which we purpose introducing in order to illustrate the Boyne, it cannot be expected that, in a popular work of this description, we should break the text and stay the narrative by interlarding its pages with critical references to all the various sources of Irish history from which we have drawn these materials. Neither is it our intention to describe minutely all the geographical relations, and various industrial resources of this river; but to present a series of picturesque views from those points in which its scenic beauty is most remarkable, and particularly to draw the attention of the tourist and young antiquary to those localities which are memorable for their historical recollections, or venerated for their archæological interest; and, as we have already stated, no other river in Ireland affords the same scope for the study of these objects, combined with the same variety and extent of pastoral inland scenery, of such depth of colour, and such grace of outline, as the Boyne, for at least thirty miles of its course.

In proof of our assertion, with regard to the numerous monuments upon the Boyne, we may remark, that from Trim to Drogheda we have traces of every epoch of Irish history, from the ante-historic period, the date of which carries us back to

* We know no better proof of this statement than Mr. Petrie's Essay on the History and Antiquities of Tara Hill, published in the Transactions of the Royal Irish Academy, vol. xviii. part ii.

the primæval occupation of this island, and which is indelibly marked by the Pagan cromlech, the rude cell and altar, and the stone chamber or kistvaen with its surrounding mound, containing rude earthen urns, the incinerated bones, the shell ornaments, and stone weapons of our *Firbolg* and *Tuatha De Danaan* ancestors,* together with their circular raths and intrenched military forts, of which we have examples in the mounds and tumuli at Carbery, Clonard, Ardmulchan, Newgrange, Dowth, Knockminaune, and Brugh-na-Boinné. Here we may linger,

“By the cromlech sloping downward,
Where the Druid's victim bled,
By those towers pointing sunward,
Hieroglyphics none have read,
In their mystic symbols, seeking,
Of past creeds and rites o'erthrown,
If the truths they shrined are speaking
Yet in litanies of stone.”—*Speranza*.

The sacred well from which the river flows, with its half-fabulous legends, serves to connect the earliest historic period with preceding times, and marks a period shrouded in mystery and Druidism.

Tara, with its Lia Fail, or oracular stone, and its grassy mounds, stands alone, the crowning place of its kings, the forum of the sages, and the banqueting hall of the nobles of Erin, at least eighteen centuries ago. Then follow the early Christian buildings, the oratories and small missionary churches, sculptured crosses, carved fonts, and round towers, as at Monasteroris, Clonard, Donaghmore, and St. Eark, till such primitive buildings rose into the more stately edifices, churches, and monasteries of Slane, Trim, Bective, and Drogheda. The baronial halls of the Anglo-Normans and proud castles of the Pale stretching along its banks, and commanding every ford and pass,—as at Carbery, Trim, Athlumny, Dunmoe, and Castle-Dexter,—mark another era, and tell of the extended sway of the De Lacys, Husseys, Berminghams, Plunkets, Cusacks, Barnwells, Flemings, Prestons, Petits, Tuites, D'Arcys, and other English chieftains, from the time of the invasion to the age of Elizabeth. Although we do not find

* For a description of the *Firbolgs* and *Tuatha De Danaans* see the ethnological inquiry at the end of this volume, after the account of Dowth.

any well-authenticated architectural remains of the O'Meaghlin's, the ancient monarchs of Meath, still remaining, their written history enables us to note with tolerable precision the strongholds and fortresses, as well as the sites of the abbeys and churches founded by this memorable and ill-fated race,—ruins that still remain,—the foot-prints of history,—with

——— “Ivied arch and pillar lone,
Pleading haughtily for glories gone.”

The various holy wells sheltered by the ancient oaks and thorns, and alike venerated by the Druid priest and the early Christian saint and pilgrim, occur in spots so calm, so lone and peaceful, that religious veneration is there awakened, even in the most apathetic.

The town of Drogheda notes a memorable era in the time of Cromwell, and its numerous military and ecclesiastical remains extend over a period of undoubted authenticity for at least one thousand years. The site and story of the “Battle of the Boyne,” on that memorable occasion when, for the last time, two kings fought for the sovereignty of these realms, brings us down to a date almost within the memory of man; while the monster meeting at Tara, the last great effort of O’Connell and the “moral force Repealers,” occurred but a few years ago. And yet with all this we know of no river that has been more neglected by writers, and no scenery that is less known within the same distance of the metropolis, than that which the Boyne presents for the greater portion of its course. The modern writers upon Ireland have one and all carefully avoided it. Inglis encircled Ireland, but “did” the Boyne while the northern mail whirled him over the bridge of Drogheda. Barrow no sooner approached its waters than he fled from them in dismay. The “Angler in Ireland” appears to have omitted it by particular desire; and with the exception of Mr. and Mrs. Hall’s account of its appearance at Trim, it has remained unnoticed and undescribed by all modern systematic writers upon the scenery of this portion of the British dominions.

Dr. Petrie, who first drew attention to its beauties in a short paper published in the last volume of those valuable records of Irish history, the Penny Journals, thus graphically describes a portion of this river: “It is of a character as beautiful as could be found anywhere, or even be ima-

gined. Scenery of this class, of equal richness, may be often found in England, but we do not know of any river's course of the same length in which natural beauty so happily combines, or in which so many interesting memorials of past ages could be found. Scattered in rich profusion along the banks of this beautiful river, we find the noblest monuments of the various races of men who have had sway in Ireland. It is on its luxuriant banks, amid so many instructive memorials of past ages, that the history of our country, as traced in its monuments, could be best studied."

Nor will our readers cavil at this broad assertion, when they remember the various remains which we have enumerated, and the great and numerous historic events to which we have alluded: while, from among the ruins with which it abounds, and underneath the very sod turned up by the spade of the labourer, in the vast and fertile plains of Leinster traversed by the Boyne, a mine of Irish antiquities has been, and is daily being worked, which has largely assisted to stock the museums of our own and other countries. Stone weapons, hatchets, knives, and arrow-heads of various shapes and sizes; bronze celts, swords, and spear-heads; terra-cotta vases; golden torques, rings, bracelets, and ornaments of great value, and of the most beautiful forms; musical instruments of brass; rings, pins, and fibulæ of silver; knives, swords, axes, shears, and domestic utensils of iron; combs and pins of bone and wood; besides other warlike, culinary, or decorative implements and ornaments of the early people of Ireland, have been here found in rich profusion. Here, moreover, may the naturalist speculate on the various races of the extinct animals of this country,—the gigantic elk, almost peculiar to Ireland, the antlered stag, the noble wolf-dog, the different varieties of horned cattle and domestic animals, whose remains are found in its bogs and marshes; or of fowl and other small animals occasionally discovered among the incinerated bones in the urns and tumuli: where also the ethnologist may procure ample means for study and speculation. Shrines, bells, and croziers of the most chaste form and moulding, to many of which an undoubted authentic history is attached, have likewise been discovered in this rich locality. If the remains of plants and animals, fixed in the enduring rocks, mark for the geologist epochs of time, convulsions of nature, transition periods, and great physical

revolutions on the surface of our globe, how much more do the weapons, ornaments, and tombs with their contents and architectural remains, afford the antiquary and historian a means of ascertaining, with much greater precision, their historic epochs, and of forming an acquaintance with the habits, manners, and customs, the religion, arts, music, sports, and warfare, of the people to whom such antiquities belonged.

Moreover, along the Boyne and its tributaries may the angler enjoy good sport, with both trout and salmon, and the botanist reap a plenteous harvest of some of the richest and rarest plants peculiar to the inland districts of Ireland.

Let us wander together by the banks of the Boyne, when the sun is high in heaven, when the warm air of summer is around us, the trees still green with the foliage of spring, and musical with the notes of birds, and the kine stand in the ford, splashing in the stream which quietly ripples by them; then, when the cuckoo revels in the grove, and the rail crakes in the meadow, while the perfume of the thorn still lingers about the hedge-rows, and the dragon-fly is flitting to and fro among the flaggers by the water's edge, let us wend our way along its peaceful margins. Such has been the character of the scene, and such the impressions made upon us, when the notes from which this little work has been compiled were written down; and as such we would present it to our readers, and describe it from our summer recollections, when piles of the richest foliage were shadowed in the deep pools of the placid waters, when the lark carolled high above us, and the long calm twilight of midsummer, with all its poetic associations, induced us to linger amidst these lovely scenes of beauty, fairy legend, and historic interest.

As the season has advanced the scene is changed over all the land; the corn has been gathered in, and now stands in well-built stacks round the snug homestead; the stream has filled up its brinks, and spread partly into the adjoining meadows, while its surface is ruffled by the fitful gusts of the October blast, or thrown into bubbles by the heavy patter of the passing shower of this autumnal April. The various shades of green which decked the forest and plantation have given place to the glowing orange, or the more sombre russet tints of umber and sienna; the haws have crimsoned the hedges, and the leaves are falling fast, and rustling into nooks and crannies for shelter;

occasional gleams of bright sunshine give, at times, a glow of warmth to the landscape, but they nevertheless forebode the shower, or herald in the rainbow. A few of the early trees have already become stripped of their foliage, and form graceful studies for the student of nature, who, if he would excel in painting trees with their foliage on, should study the anatomy of the leafless branches with as much care as the figure-painter devotes to the dry bones of the skeleton. The lapwing wheels and *peewees* over the dreary moor, and clouds of field-fares and starlings appear in the distance, as if gathering for the winter's campaign.

But whether it be early spring, with all its morning freshness and elasticity, or sultry summer, or yellow autumn, there is still the same sylvan beauty, the ever-changing tints which the green foliage, the graceful undulation of surface, the glancing river, and the picturesque ruin, impart to the landscape of the British Isles, nowhere else to be met with, whereon the eye never wearies, the mind never palls, and of which the memory never loses sight.

As this is the great river of Meath, a few observations on that ancient province may not be out of place. Under the denomination Meath, Meth, Mide, Media, or Meidhe, and in part that of Magh-Breagh, was formerly included a far wider and more extensive territory than that comprised in the present county of this name. The district included under this title is one of the most level and fertile in the kingdom, and originally stretched from the interior of the island to the sea; hence Camden and other English writers derive its name of Media. Ptolemy places the Laberus, or ancient central castle and city of this kingdom, in the territory of Meath; but antiquaries are as yet undecided whether the present Kells, Tara, or Killaire Castle, occupies the site of that memorable spot; though Tara seems obviously the place intended by the great geographer, whose transcribers and commentatators in all probability mistook the word Taverus for Laberus.

There is an ancient tradition handed down through our manuscripts, that the Firbolgs, or Belgæ, as they have been termed, first settled in this locality; and it is not at all improbable that a rude and primitive people, living by hunting and fishing, such as we may suppose the early inhabitants of this country were, would, upon their arrival on the north-eastern

shores of Ireland, seek the interior through the noble stream that traversed this great plain, where the woods and forest glades afforded plenty of game, the waters abundance of fish, and, in process of time, as civilization advanced, its fertile limestone soil returned a plenteous crop, and its luxuriant pastures produced numerous herds of cattle. The old writer, Bartholomeus Anglicus, as quoted by Camden, described it as "A soil which yields plenty of wheat and pastures, well stocked with herds, abounding with fish, flesh, and other provisions, butter, cheese, and milk, and well watered by rivers; the situation of it is delightful, and the air healthy. The woods and marshes in its extremities defend its approaches, and from the number of people, the strength of its castles and towns, and the peace which it enjoys in consequence thereof, it is commonly called *The Chamber of Ireland*."

The first fortified houses and stone buildings that we read of were in Meath.* The earliest chronological era to which the most veracious of the modern Irish historians refer, is about the middle or towards the end of the second century, when Tuathal Teachtmair, one of the Scotie or Milesian Pagan monarchs, reigned at Tara. He erected Meath into a fifth province, as mensal lands or appanage for the monarchy, by taking in portions from each of the other four; hence the Irish historians derived its name of Meidhe—a neck—on account of its being formed by necks taken from the surrounding districts or provinces. The fact of the Gospel having been first preached and received in Meath is a proof of its civilization, in comparison with the other parts of the island at that period; and the immediate reception and rapid extension of the Christian doctrine among the kings and nobles assembled on the banks of the Boyne on St. Patrick's arrival, speaks loudly for the state of education in Ireland at that time.† If the Gospel came to

* By this we do not mean *castles*. One of the earliest castles erected in Ireland of which there exist any remains is believed to be Caislean na Kirka, or the Hen's Castle, upon a rock in the upper lake of Lough Corrib, one of the wildest and most picturesque spots in Ireland. Some portions of the ruins of this building still remain. We have slept there when a boy. See an account of this castle by Dr. Petrie, in the Irish Penny Journal, for July 25, 1840.

† Patrick certainly first preached in Meath, and probably the earliest great conversion to Christianity took place there; but it should be here remarked, that it has been the boast of the Munstermen (at least for the last thousand years)

Ireland in the fifth century, and was received, as it is stated to have been, and as we have every reason to believe it was, then, indeed, the tone of the bards and annalists who describe the high state of the arts, and who place such noble sentiments in the mouths of our kings and chieftains at that time, is not as vaunting as some critics have supposed.

The province or kingdom of Meath, as established by Tuathal, extended from Dublin to the Shannon, and from the centre of Ireland to the sea, and included both east and west Meath, with portions of Dublin, King's County, Longford, and Cavan. A part of it was then styled Magh Breagh, "the magnificent plain," or the Campus Brigantium of Dr. O'Connor and other authors. The Owen Ree (King's River), now called the Rye-water, was the boundary of this region on the one side, and the Casan, in Louth, on the other. It is thus described in an old Irish rann:

"From *Lough-bo-deirg* to Birr,
From the Shannon east to the sea,
To Cumar Chluana-Iraird,
And to Cumar Cluana aird."

The ancient manuscripts are very rich in the topographical descriptions of this district. It was the seat of Irish monarchy for some centuries after its erection into a province, and one of our oldest coins is that of Aedh, King of Meath. There were four royal palaces of great note and celebrity in this province in ancient times, at Tara on the Boyne, Tailten on the Blackwater, Tlachtga on the Hill of Ward near Athboy, and Uisneach in Westmeath.

Sylvester Giraldus Cambrensis thus describes this portion of the Pentarchy: "There arrived in Ireland five brethren that were valiant and martial gentlemen; to wit, Gandius, Genandius, Sagandus, otherwise named Gangandus, Rutheragos, or Rutheranus, and Slanius. These five, perceiving that the country was not sufficiently peopled, were agreed, as it were, to cast lots, and to share the whole realm between themselves.

that they were the first Irish believers in Christ, and that the Cross was originally raised in Ireland (where it still stands) on the strand of Tra-Kieran, on the island of Cape Clear. This Munster tradition has been preserved in the Books of Lecan and Ballymote, and given to the world by Ussher, Harris, Dr. Smith, and a host of other writers.

The four elder brethren severing the country into four parts, and being loth to use their youngest brother like an outcast or step-son, condescended that each of them should, of their own portion, allot to Slanius a parcel of their inheritance, which being as heartily received of Slanius as it was bountifully granted by them, he settled himself therein, and of that portion it took the appellation of Media, Meeth. The four parts meet at a certain stone at Meeth, near the castell of Killaire, as an indifferent meare to sever the four regions.* And in another place the same authority describes this stone as "Umbilicus Hiberniæ, quasi in Medio in Meditullio terri positus." This large rock is still to be seen on the hill of Uisneach, near Killare, county of Westmeath, and is now called Cat-Uisnigh by the natives. And in the additions which Hooker has made to the first portion of the work of the English chaplain, we read: "Meth, in Latine Media, is one of the five portions of Ireland, according to the first division. It is the least portion, being but of eightene cantreds, but yet the best and most fertile, and lieth for the most part all within the English Pale: and ever since the conquest of king Henrie the Second, hath beene subject and obedient to the English laws and government: and bicause it lieth as it were in the navill and bowels of the land, it taketh the name accordinglie, being called *Media*, which is the middle;" and he adds: "There was no prince sole governour of this, as was of the other portions; bicause it was alwaies allowed and allotted to the monarch, whom they called *Maximum Regem*, or *Regem Hiberniæ*, as a surplus towards his diet." This latter, however, like many other statements of the same authorities, is to be received with caution.

Slanius, it is said, soon enlarged his dominions, so that he obtained the monarchy of Ireland. "This Slanius is entombed at a hill in Meeth, which of him is named Slane."

In subsequent times, and up to the date of the English invasion, the five provinces were thus possessed: the O'Melagh-lins ruled in Meath; the O'Conors in Connaught; the Mac Murroughs (afterwards called Cavanaghs) in Leinster; and the O'Briens in Thomond or Munster.

To this day Meath is the great grazing ground of Ireland; in it are to be found the most extensive sheep-walks and pas-

* See Giraldus's *Topographia Hibernica*, translated by Stanihurst.

ture lands; the finest horned cattle, with the exception of those of Roscommon, are bred in Meath; and its vicinity to the metropolis and the sea has always afforded it a ready home consumption, and an easy mode of transit to the English markets. Its crops are generally so luxuriant, and its land so fertile, that it has been asserted that if it were all grown in corn it would feed and might form the granary for the whole of Ireland. Its natural capabilities, and particularly its flat level surface, must have rendered it easy to retain when once possessed by an invading army, and easy to colonize by an industrious people. The fertility and riches of Meath more than once excited the cupidity of the roving Northmen; and several incursions of the Danes are enumerated in the Annals, but particularly that of Turgesius, in the ninth century. Naturalists have been at some pains to discover from whence or through what breeds the present improved English race of short-horned and other highly esteemed varieties of domestic oxen have been obtained, and indeed the question is not yet decided; this fact, however, is certain, that in the bogs and marshes of Meath, at Dunshaughlin, not far from the river Boyne, numerous remains of the ancient animals, both wild and domestic, which formerly existed in this country, have been discovered, and particularly those of oxen, which for beauty of head and horn might vie with the finest modern improved breeds of England, notwithstanding all the pains and expense that have been gone to in bringing them to their present state of perfection; and yet there can be little doubt of those bones, to which we have referred, having lain beneath the surface for many centuries.*

The early population of Meath must have been very great; but, owing to the "clearance system" which has long existed in this county, and produced those extensive pasture lands to which we have alluded, it is now much less, in proportion to its cultivateable land, than that of any county in Ireland, and, therefore, in several parts of it, the amount of labour is unequal to the demand. The peasantry are handsome, well made, stout, and healthy, but more serious and taciturn than those in

* See an account of these remains by the Author of this book, in the Proceedings of the Royal Irish Academy, vol. i. p. 420; and in Mr. and Mrs. Hall's Ireland, where the heads of these cattle are figured, vol. ii. p. 393.

the mountain districts of our island; and, as might be expected, the admixture of races is here so great, that the ethnologist is puzzled to make out Celts from Saxons, or distinguish Milesians from those retaining any vestige of the primitive tribes, as may be done in other parts of the island. The colour of their frieze is a light grey, contradistinguished from the blue of the west, and the dark brown of the south; the costume of the females has of late become less national than in other parts of the kingdom; and as civilization extends, the English broad-cloth is worn by great numbers. Some twenty or thirty years ago, before the large flax-mills and factories were established on the Boyne, the female attire was more picturesque and less diversified. In the flourishing days of the linen trade, when the fields waved with the beautiful bells of the flax, and pipers played at the camps and princkums* in all the villages, most of the females, young and old, were then employed in spinning, and dressed in black felt hats, like the Welsh of the present day, green linsey-woolsey gowns, and red flannel petticoats. When their occupation ceased, on the establishment of the flax-mills, and the decline of the linen trade, this dress was abandoned, perhaps from the means of procuring it being withdrawn, but also owing in a great measure to the breaking up of the clanship which then existed amongst the spinners, who used to meet in numbers at the farmers' houses, and work, and dance, and sing, almost without intermission, for several days together.

Native music and poetry are not found to flourish on great plains, such as Meath, as luxuriantly as they do in the hills and dells of more elevated regions; yet the lasses of the Boyne are by no means as sombre and phlegmatic as the men; and songs, tales, fairy legends, country dances, and planxties, with wandering bards, and shanaghies and their tales of pishogues, thivishes, and superstitions, together with blind pipers and lame fiddlers, are not wanting to enliven the dull, tedious evenings of winter, from Kells to Maiden Tower.†

* A word applied, in some parts of the west of Ireland, to a merry-making.

† The Meathmen, who were very Irish in the last century, used to boast that they spoke better Irish, and had more poets, minstrels, and men of genius among them, and that they were more lively and energetic than the boors of Leinster, whom they always defeated at hurling, boxing, wrestling, and other athletic exercises. Up to about fifteen years ago, the men of Meath used to

Passing over the occupation of Meath by a line of heroes that certainly were not, when the foregoing topographical descriptions were given, a "royal ragged race of Tara," and the early monarchs and chieftains, from Con of the Hundred Battles, the venerable Cormac Mac Art, Niall of the Nine Hostages,* and Finn Mac Cumhaill, the Fingal of Mac Pherson's Ossian, whose history, as exhibiting the state of civilization in Ireland, as well as the habits, manners, and customs of the people in their times, is well worth the attentive study of our readers; we arrive at the days of the O'Melaghins, who were kings in Meath at the time of the English invasion, when a daughter of that royal line, Dearvorgail, the faithless bride of Brefney, and the Helen of the Irish Iliad, was seduced by the ill-fated Dermot Mac Murrrough, King of Leinster:

——— "Oh, degenerate daughter
Of Erin, how fallen is thy fame;
And through ages of bondage and slaughter
Thy country shall weep for thy shame."

The English monarch deposed the rightful O'Melaghlin, and made a grant of the fair province of Meath to Hugh de Lacy, one of the fiercest of the soldiers of Strongbow, with, according to some authorities, the title of Lord Palatine. The Boyne's bank became, in after years, the boundary of "The English Pale;" and numerous castles and strongholds rose along it, occupied by the Anglo-Norman families already enumerated. In the reign of Henry VIII. Meath was divided into east and west.

Notwithstanding our promise not to enter too minutely into the subject of Irish history, or break the text by constant references to authorities, we cannot prevent ourselves, though

exhibit their powers in wrestling matches with the men of Kildare and Dublin in the Phoenix Park. We often witnessed these encounters, which resembled the *Dornghal*, or boxing-battle, of Bri-Eile, described in the Annals of the Four Masters, A. D. 468.

The last great patron of Irish wrestling was the witty and eccentric Brennan, the writer of the Milesian Magazine, generally known among the lower orders as the "wraslin-doctor," while among his professional brethren he was commonly denominated "Turpentine Brennan," who used to preside over and sometimes partake in the wrestling matches which took place on a Sunday morning at the Broadstone harbour.

* From Niall sprung the two great clans of the northern and southern Hy Nialls, who figure so conspicuously in our Irish history.

at the risk of detracting from the interest of the romance, relating a few truths—at least, a few well-authenticated historic facts—connected with some of the *dramatis personæ* of the English invasion. The day has gone by when the fable and fact of history could be presented to the reader indiscriminately; and Irishmen, in particular, so often accused of expressing themselves in superlatives, jumping at conclusions, and drawing so largely upon their imaginations, should endeavour, while they popularize their history, to present nothing, even in a guide-book, but what is strictly founded on good authority. The elopement of Dearvorgail (or Dearvorgailla, which means in Irish “the true pledge”) with Dermot Mac Murrough is generally believed to have been the sole cause of the English invasion; but this is questionable; at least the subject requires to be further investigated, although there can be little doubt but it rendered the king of Leinster more obnoxious to O’Rourke and his connexions, the O’Conors of Connaught, than he had previously been, and probably hastened the catastrophe. O’Rourke was blind of one eye, and, at the time of the elopement, must have been as old as Dermot at least, and, consequently, several years senior to his wife, who, we know to a certainty, was born in the year 1108, and was therefore in her forty-fourth year in 1152, the date of her and our misfortune. At this time Dermot was in his sixty-second year! and appears from all accounts to have been of a most unamiable disposition and ungainly person. Giraldus Cambrensis, who must have seen him frequently, thus describes him (we quote from Hooker’s translation): “This man, from his verie youth, and first entrie into his kingdome, was a great oppressor of his gentlemen, and a cruell tyrant over his nobles, which had bred him great hatred and malice. Dermot Mac Morough was a tall man of stature, and of a large and great bodie, a valliant and a bold warrior in his nation; and, by reason of his continuall hallowing and crieing, his voice was hoarse. [*Ex crebro continuoque belli clamore voce raucenosa, &c.*] He rather chose to be feared than loved. He would be against all men, and all men against him.” After the battle of Ossory, it is recorded that when the heads of the slain were brought before him by the soldiers of Robert Fitzstephen, “among them there was the head of one whom especiallie and above all the rest he mortallie hated. And he taking up that by the heare and eares

with his teeth most horrible and cruellie bit awaie his nose and lips.”* Speaking of O’Rourke, the same author writes, that when he heard of his wife’s flight, he “was forthwith marvellouslie troubled, and in great cholor, but more grieved for shame of the fact than for sorrow or hurt, and therefore was fullie determined to be avenged.”

O’Rourke was on a pilgrimage at Croagh-Patrick at the time, and not at Lough-Dearg, as has generally been stated; and the Irish historians inform us that the Princess of Brefney left her husband’s roof, and fled with the King of Leinster, taking with her her ornaments and her cattle, with the knowledge and even at the instigation of her own brother, O’Melaghlin, son of the King of Meath. The Annals of the Four Masters inform us that “Dearvorgilla (i. e. the wife of Tiernan O’Rourke), daughter of Murrough O’Melaghlin, died in the monastery of Drogheda [Mellefont], in the eighty-fifth year of her age.” A. D. 1193.† It should be remembered also that Mac Morough was not expelled from his kingdom for several years after.

Civil wars, family feuds, and the rivalry and jealousy of clans and chieftains, seem, therefore, to have had as marked an influence on the destiny of our unhappy country at that time, as the jealousy of husbands and lovers.

Some observations upon a subject to which frequent reference will be made in the course of this work, may here be found useful. The boundary of the English Pale or territory towards the north and west was chiefly, in later times, formed by the river Boyne, which will account for the number of border castles built upon its banks; but it is difficult to define this line with any degree of accuracy, for it constantly varied, being from time to time narrowed or increased as each party prevailed, so that it has been said that at one period long after the so-called conquest, the King’s writ would not run for twenty square miles. In Stanihurst’s additions to Giraldus Cambrensis we read, that, “when Ireland was subdued by the English, diverse of the conquerors planted themselves near to Dublin and the confines thereto adjoining; and so, as it were, inclosing and impaling themselves within certeine lists and territories, they

* This description forcibly reminds us of a similar scene in Dante’s *Inferno*, where Ugolino is found gnawing the skull of his enemy Ruggieri.

† See Dr. O’Conor’s *Prolegomena ad Annales*, Part ii. p. 146.

teased awaie the Irish, insomuch as that countrie became mere English, and therefore it was termed the English Pale; which, in ancient time, stretched from Dundalke to Catherlagh or Kilkennie. But now [in 1584], what for the slacknesse of marchuors and encroching of the Irishemie, the scope of the English Pale is greatly impaired and is cramped and coucht into an od corner of the countrie named Fingall, with a parcel of the king his land Meeth, the counties of Kildare and Louth, which parts are applied cheeflie with good husbandrie, and taken for the richest and civelest soiles in Ireland." The extent of English territory north-west of Dublin, particularly in Meath, may be learned from the several grants made at different times to Anglo-Saxon nobles and ecclesiastics; as, for instance, the grant of Meath to Hugh De Lacy by Henry II.; De Lacy's grant to Gilbert De Nugent; and Walter De Lacy's grant to the Bishop of Meath in the reign of Henry III., all of which have been published by Dean Butler,* and the two latter of which are in the collection of our friend Sir William Betham.

From the Statute of Kilkenny, lately published by Mr. Hardiman, in the Irish Archæological Society's publications, we learn in a note by that learned author, that "in the reign of Henry VII. the influence of the English extended little farther than four counties; and so straitened were they that it was found necessary to protect them from the incursions of the Irish by a ditch raised along the borders of the Pale. For this purpose an Act was passed in the celebrated Parliament held at Drogheda in A. D. 1494. As this curious Act has been passed over in silence by Cox, and has never been printed, I take the following extract from the original roll, preserved in the Rolls Office, Dublin: 'As the marches of four shires lie open and not fensible in fastness of ditches and castles, by which Irishmen do great hurt in preying the same: it is enacted that every inhabitant, earth-tiller, and occupier in said marches, i. e. in the county of Dublin, from the water of Anliffy to the mountain in Kildare, from the water of Anliffy to Trim, and so forth to Meath and Uriel, as said marches are made and limitted by an Act of Parliament, held by William Bishop of Meath, do build

* See some notices of the castle of Trim, collected from various authorities; 1840.

and make a double ditch of six feet high above ground, at one side, or part which mireth [meareth?] next unto Irishmen, betwixt this and next lammas, the said ditches to be kept up and repaired as long as they shall occupy said land, under pain of forty shillings; the lord of said lands to allow the old rent of said lands to the builder for one year, under said penalty. The Archbishop of Dublin and the sheriff of the county of Dublin, the Bishop of Kildare and the sheriff of the county of Kildare, the Bishop of Meath, and the sheriff of the county of Meath, the Primate of Armagh and the sheriff of the county of Uriel [Louth], be commissioners within their respective shires, with full power to call the inhabitants of said four shires to make ditches in the waste or *Fasagh* lands without the said marches.' This was a low state for *conquerors* to be reduced to after more than three centuries possession. The question of *conquest* is now of little consequence, but the integrity of history is at all times important, and it is therefore to be hoped that this subject, which can only be cursorily glanced at here, may attract the attention of some of our learned associates, who are versed in the history and antiquities of their native land."*

The Boyne rises in the barony, and near the little village of Carbery, in the county of Kildare, about seven miles south-east of Enfield,† and four from Edenderry, at Trinity Well, in the demesne of Newbury, 289 feet above the level of the sea; one of those holy wells so numerous in Ireland, and to which so much interest, historical as well as superstitious, is attached. Running westward for a few miles, it reaches the King's County, and then becomes the boundary for a short distance between that part of Leinster and its parent county, draining in its course the surplus waters of the adjacent great Bog of Allen. Leaving King's County upon its north-western bank, it touches Meath near Castle-Jordan, and forms the boundary between that county and Kildare, till it reaches Ashford, below the bridge of Clonard. In this portion of its course it receives the Yellow River and Milltown stream, and, where

* See also the Rev. M. Kelly's Notes to *Cambrensis Eversus*, in the Celtic Society's recently published edition of that work.

† Formerly and correctly called Innfield, the field of the Royal Oak Inn. It is the nearest railway station, on the Midland Great Western or Mullingar line, to the Boyne's source. See Itinerary at the commencement of this work.

it enters Meath, the rivulet bearing the local name of the Blackwater, from Kildare, and the Kinnegad and Deel rivers, from Westmeath. Below Ashford it is crossed, at the Boyne aqueduct, by the Royal Canal and the Midland Great Western Railway, and from this point to a few miles above Drogheda it traverses the fertile plains of Meath, which county it divides into nearly equal parts. Passing onward in the same easy course, it reaches the celebrated town of Trim, and then Navan, where it receives the Blackwater from Cavan, which is there nearly as large as the Boyne itself, and, flowing onward by Slane to the borders of the south of Louth, near Oldbridge, the Mattock River empties itself into it a short distance above Drogheda. It enters the Irish Channel below that town by a broad, shallow estuary, having the county of Louth on its left or northern bank, and that of Meath on the right or southern. Following its various windings, from its source to the sea, opposite to the Maiden Tower below Drogheda, it measures about seventy miles on the Ordnance Map, and its general direction is from south-west to north-east. While the river pursues its sluggish and circuitous course through the county in which it rises, and also where it borders a small angle of the King's County, it is but an insignificant stream, interesting alone from the remains which still exist upon its banks. Not far from Edenderry it is crossed by Boyne bridge, bearing the road from that town to Clonard. Some gentlemen's seats also diversify the landscape, but, generally speaking, the stream is, in Kildare, very insignificant, and the country through which it passes low and marshy, yet, both in this county, as well as in the upper portion of Meath, the Boyne is remarkably tortuous in its course, and constantly broken with islands, a peculiarity not uncommon to rivers running through so flat and monotonous a country as this. It is to the last stages alone that the description, which we have already attempted, of its scenic beauty, applies. Looking at the course of the river on the map, it will be seen that it forms a segment of a circle, and, taken with the Blackwater, it makes the shape of the letter Y.

Three great natural divisions present themselves to the topographer of the Boyne: first, from its source to Clonard; secondly, Clonard to Navan; and, thirdly, from thence to the sea; each presenting characters peculiar to itself.

Let us now follow its various windings in detail, and, besides

its natural beauty, observe what objects of interest, either for their antiquarian or historic importance, present themselves in our track. In so doing, we shall avail ourselves largely of every possible source of information: books of all sorts, ancient and modern, old records and recent investigations, popular works and old black letter tomes, Irish manuscripts, oral traditions, and scientific researches, dry historical details, and critical dissertations, the Archæological and Celtic Societies' publications, the Ordnance Maps, the public records, ancient ecclesiastical documents, the old Chancery rolls, State Papers, the inquisitions and deeds of forfeiture, the reports of commissioners, parochial and county surveys, the ploughman's song, the Penny Journals, the calliagh's legend, the stories and superstitions of modern shanaghies, ancient ballads, and bardic tales,—each and all shall be here, as they have ever been on such occasions, pressed into the service, and used when opportunity offers.

It cannot be expected, however, that in a popular book of this description, which is chiefly written for tourists, our sources of information should be constantly referred to, after the manner of a strictly archæological work; no more than the materials of which other popular publications have been composed, were stated by their authors to have been derived from sources accessible to all, but only known to a few, learned in Irish history and antiquities. Having prepared ourselves for the subject, we have endeavoured to present our readers with a faithful description of this river, by traversing its banks, or floating down its placid waters, and repeatedly visiting all those scenes of sylvan beauty or rural comfort, all those Pagan relics, feudal remains, and monastic monuments, along its margins, which we have attempted to describe.

The origin and derivation of the word Boyne is involved in the same obscurity as that which surrounds the true meaning of most ancient terms, either in our own or in the early classical literature, and, like them, has occupied the attention and elicited the speculations of the learned, and the unlearned also. By Ptolemy, on whose map of Ireland we find this river figured, it is called Bovinda, or Buvinda; Cambrensis writes it Boandus; and Ware thus speaks of it: "The old name of this river is not quite lost, for it is at present called the Boin; and, by Necham, the Boand in Meath. It takes its name, as some think, from the word Boan, which, both in British and Irish,

signifies *swift*." In Grace's *Annales Hiberniæ* it is written, "Boundi Fluvii."

"Our countryman, Necham," says Camden, "sings thus of it:—

" ' Ecce Boan qui Trim celer influit, istius undas,
Subdere se salsis Drogheda cernit aquis. ' "

Which he thus translates:—

" Swift flows the Boyne to Trim, then makes his way
To join at Drogheda the briny spray."

The Necham here quoted was Abbot of Cirencester, and died in 1217.

As might be expected from the foregoing portion of this sketch, the Irish manuscripts, annals, and poems, are exceedingly rich in references to, and descriptions of, the Boyne; indeed more so than to any other Irish river, of which we might give numerous instances, but shall reserve them till we come to speak of the river in detail. The Boyne, Boinn, or Boan, has several names in our ancient literature, many of which, however, may be referred to the following legend—one which Ovid would have enlarged into a charming metamorphosis—which is preserved both in prose and verse in two of the oldest MSS. in the Library of the Royal Irish Academy, the Books of Lecan and Ballymote; and is copied and repeated in several of the Irish romances. Many of our Irish rivers have their source in holy wells, and there are few, if any of them, without their legends.

The well of the Blessed Trinity, at which the Boyne rises, is at the foot of the hill of Carbury, anciently called Sidh Nechtain, the fairy hill of Nechtain. There was a celebrated poet and king of Leinster, called Nechtain, or Nuada-Neacht, in the first century, who had a secret well in his garden, one of the miraculous virtues of which was, that any one who approached it, except the monarch and his three cup-bearers, Flesg, Lesg, and Luam, was instantly deprived of sight, their eyes bursting, as the manuscripts describe it. Female curiosity, however, was not to be disappointed, and Boan, the queen, was determined to test the mystical powers of its waters; she, therefore, arrogantly, not only approached the well, and defied its powers to mar her beauty, but passed three times round it

to the left, as was customary in several of the ancient incantations.* Upon the completion of the third round the charm was broken, the spring rose, and three enormous waves burst over the hapless lady, mutilating her sadly, and, says the original, "breaking one of her eyes;" she then fled toward the sea, to hide her deformity, but the waters, now loosened from their source, still followed, till she reached the Inbher, or present mouth of the river. This Boan was the mother of Aengus Mac An Daghdha, a celebrated Tuatha De Danaan chieftain, of whom we shall have to speak hereafter, and who is thus referred to in an old Irish poem, enumerating the fairy palaces of Ireland:

"I visited that glorious dome that stands
By the dark rolling waters of the Boyne,
Where Aengus Oge magnificently dwells."

Dabella, the lapdog of Boan, shared, it is said, the fate of its mistress, and was swept out on the rushing waves of the Boyne to the sea, where it was transformed into the rocks since called Da Billian, which rise above the water at the Boyne's mouth. Notwithstanding the watery grave thus assigned by the poet Kenneth O'Hartigan, in the Book of Ballymote, to the wife of Nectain, her monument is recorded by the ancient poets and topographers among those of the great royal cemetery of Brugh na Boinné. Thus in the *Senchas na Relec*, or History of the Irish Cemeteries, we find enumerated: "The grave of Boinne, the wife of Nechtain; it was she took with her the small hound called Dabilla, from which Cnoc Dabilla is called." So many versions of this story have come down to us, that, without attaching any credence to the legend, we are forced to receive the fact of the name of the river having been derived from an Irish princess named Bóinn, Boan, or Boann. Similar legends are related of the origin of Lough Neagh, and several other lakes and rivers.

The well is famed for its medicinal virtues, and there is a *Pattern*, or *Patron*, still held there on Trinity Sunday.

It is said that Bo was the original name of the river, and that where it meets the river Finnabhainn, of Sliabh-Guaire,—

* For a particular account of this "unhallowed round" see Toland's *Druids*, p. 143; and Martin's *Description of the Western Islands of Scotland*, p. 20.

in all probability the Blackwater,—near Navan, is the place properly called Boan. Righ is also one of the ancient names of the Boyne, and means the wrist or fore-arm. It is thus explained. Boan, the wife of Nectain, wore her wrist adorned with bracelets and other ornaments, with which she rewarded poets or rhymers; and in one of the ancient manuscripts of the Brehon laws, still preserved in the library of our University, we find the following notice of this princess: "The righ of the wife of Nuada was covered with rings of gold, for bestowing them on poets:" and this explains how the word Righ came to be applied to the river Boyne, in some of our old poems and metrical romances. This river, probably after Boan was drowned in it, took the name of her *Righ*, or fore-arm, because of the inspiration which its beauties imparted to the poets of after ages.*

Livy says the Tiber was first called the Albuda, and continued to be so till Tiberius was drowned therein. The river Eithne, now the Inny, in Westmeath, is accused of having drowned Eithne, the daughter of King Eochy Feileach, and wife of Conor Mac Nessa, King of Ulster. Many other instances of the names of rivers being derived from distinguished persons might be adduced.

* See also Dr. Petrie's Inquiry into the Origin and Uses of the Round Towers of Ireland, pp. 103, 113.

CHAPTER II.

FROM CARBURY TO CLONARD.

CARBURY; ITS ANCIENT HISTORY, HILL, AND CASTLE.—GENEALOGY OF THE DUKE OF WELLINGTON.—THE BOYNE'S PROGRESS THROUGH THE KING'S COUNTY.—EDENDERRY.—RUINS OF MONASTEROIS.—THE BIRMINGHAMS.—ALTERATION OF ENGLISH INTO IRISH NAMES.—RETURN TO KILDARE.—KINNAFAD CASTLE.—A BATTLE FIELD; THE MEN WHO FOUGHT THERE, AND THEIR WEAPONS.—GRANGE.—THE HILL OF CARRICK; ITS CHURCH, WELL, AND CASTLE.—VIEW OF THE PLAINS OF LEINSTER.—TOBERAULIN.—LADY WELL.—IRISH HOLY WELLS.—BALLYBOGAN; ITS CHURCH AND PRIORY.

THE Hill of Carbury, which rises to a considerable height above the surrounding plains, forms a conspicuous object from all sides; and the ruins of the ancient castle, which still rest upon its north-eastern shoulder, are some of the finest of their kind in Ireland, and form a most imposing object as we approach from Enfield. The elevation, the total want of surrounding wood, and the tall, graceful chimneys and gables of the modern or Elizabethan portion of this edifice, give it an air at once tasteful and commanding.



The accompanying sketch, taken from the south-east, affords a very good idea of the style, magnitude, and general extent of this once noble building, which is now a complete ruin; the length of the line of the southern wall figured above is alone

100 feet, and the general view of the castle, upon our first approach, with its chimneys, narrow pointed gables, and large stone-sashed windows, is that of one of the best specimens of the castellated mansions of about the time of James I., which we know of in this country, combining lightness, taste, and comfort, with strength and durability. The eastern front, which measures sixty feet, still remains with several of its mullioned windows, even yet quite perfect, and upon a gentle slope leading down from its walls on this side may still be traced the vestiges of a garden, with a few of its flowers, now wild and neglected, mingling with the rank florin-grass with which it is surrounded. In fact everything about this ruin bears evidence of ladies fair as well as valiant knights having inhabited it. Such is the impression made by this ruin from a glance at its external face, particularly from the point of view from which the drawing figured on the other side was taken; but upon a closer inspection, and an internal examination, we perceive from the character of the masonry, the massive walls, the deep, stone-roofed donjons, the principal of which runs for eighty-five feet underneath the great keep, from south to north, the manifest antiquity of the entire of the western end, and the general arrangement of the whole, that the present ruin consists of the remains of structures very much older than the early part or middle of the sixteenth century; indeed some of them would appear to be as old as the twelfth century, and there are remains of walls of great thickness, built with rubble masonry, and grouted, extending even beyond the confines of the present ruin to the north-west. The modern additions all exist on the opposite side, and their later date is at once manifest. Four of the chimneys, three of which are in the eastern front, have sixteen sides, and are like some of the chimneys of English castles, built about the year 1530, being beautifully wrought and moulded at top. Owing to the various additions at different ages, the plan of Carbury Castle is very irregular, and its history, which will be found somewhat farther on in this chapter, will in some measure account for the various erections manifested in the ruins. A short distance from the castle we find a modern burial-ground, chiefly occupied with the remains of members of the Pomeroy family.

Toward the summit of this beautifully verdant hill of Carbury, which rises gradually from the surrounding plains, and

leading southward from the castle, we meet with some ancient pagan remains of considerable extent; and still more southwards, towards the Edenderry road, we light upon the old church and graveyard of Temple Doath, or Caille, probably the site of the ancient church of St. Muadnat, Virgin, mentioned by Colgan.* This is a fairy hill, as its Irish name implies, and its Pagan remains seem to have escaped the attention of our modern antiquarians. It appears to have been the Tara of north Leinster, and is well worthy of attention.† Upon its top we find a small sepulchral mound, and to the north-west of this two remarkable military forts or raths, both very perfect, and one of considerable extent; but they are not even marked in the Ordnance Map, accurate as it is in all other respects.

We know of no locality so celebrated as the barony and hill of Carbery or Carbury, about which there has been so much discussion, and concerning which there is still so much discrepancy among Irish writers.‡ There are at least four districts of this name in Ireland, all celebrated in history, ancient and modern. Carbery, in the county of Cork, a scene in which has been commemorated in Dean Swift's poem of "*Carberix Rupes*;" Carbery, in Longford, where we still find *Sliabh Cairbre*, and in which the magnificent moat of Granard stands; Carbery, in Sligo, where Drumcliff is situated; and that now under examination in Kildare. The investigation carried on by Mr. O'Donovan and his assistants in connexion with the Ordnance Survey,§ has, however, thrown new light upon the subject, and settled the question of the topography of that

* *Acta Sanctorum*, p. 339.

† The Tara of ancient Leinster was Dun-Aillinne, near old Kilcullen, where the largest *fort* in that province is still to be seen.

‡ From the difficulty attending the investigation, the same discrepancy has crept into the topographical notes to the earlier volumes of our modern societies, the Archæological and Celtic. See notes to the *Leabhar-na-gCeart*, or Book of Rights; and the references to Carbury in *The Battle of Magh Rath*, pp. 138 and 148. See also *The Tribes and Customs of Hy-Fiachrach*, pp. 276, 474; and also the *Miscellany*, p. 144, n., all translated and annotated by Mr. O'Donovan, and published by the Irish Archæological Society.

§ But for the information acquired during that great national work, the records of which are preserved in the Ordnance Office at Mountjoy Barracks, Phoenix Park, it would have been quite impossible for the editors of the various historic and archæological works which are now being produced in Ireland, to have written those full and critical topographical notes with which these works abound.

Carbury most celebrated in ancient Irish writings, and decided that this barony in Kildare was the *Cairbre Ui Ciardha* of our most trustworthy historians, and that particularly alluded to by the Irish poets, O'Dugan and O'Heerin, of whom the former flourished in the latter part of the fourteenth, and the latter in the beginning of the fifteenth century, and gave topographical and historical descriptions of some of our most memorable localities.* O'Dugan says that O'Kiery (now Keary) was lord of this territory, and the only chief of the descendants of Niall of the Nine Hostages, king of Ireland in the fifth century, located in Leinster. The translation of the passage referred to runs thus:

"O'Kiery o'er Carbury of the Clergy,
Of the tribes of Niall of the Nine Hostages,
There are but themselves (i. e. O'Kierys) there to the east,
Of the descendants of Niall in Leinster."

This locality has many interesting historical recollections connected with it, too long, however, for insertion here. O'Heerin, the topographical historian and poet, contemporary with the celebrated Giolla Isa Mor Mac Firbis, thus alludes to it:

"Over Carbury of Leinster of the plains
Rules O'Keary of the red-bladed swords,
The scion of Almhain, without scarcity in the east,
By whom battles were kindled round Croghan."

The castle of Carbury was originally built by the family of Bermingham, the descendants of Pierce De Bermingham, one of the early English settlers in Ireland, of whom some account is given a little farther on, in the description of Monasteroris. It suffered greatly at the time of the civil wars in Ireland, particularly during the fifteenth century, and was constantly the scene of strife in those forays which took place between the English barons within the Pale and the western Irish chieftains. In 1447 "Castle Carbury was re-edified by the lord ffurnival" (Furnival). In 1466 Meath was the seat of war, and in one of the skirmishes between Teige O'Conor and the Earl of Desmond, the latter was taken prisoner and conveyed

* O'Dugan died in 1372, and O'Heerin in 1420. See also the Abbé Mac Geoghegan's Account of the Rebellion of Carbre, History of Ireland, vol. i. p. 200.

by that chieftain, his captor and kinsman, to Castle Carbury, together with several of the English nobles and ecclesiastics. The celebrated Red Hugh O'Donnell, when laying waste Meath and Leinster in 1475, "demolished and burned Castle Carbury and Ballymeyler." So late as 1546 we read that "the plains of Cairbre and Castle Carbury were plundered and burned" by some of the Irish insurgents, particularly the O'Kellys, the O'Maddens, and O'Conors. The mode in which this outrage was punished by the high legal functionary of the Government is highly characteristic of the time. "When," say the Annals, "the Lord Justice, Anthony St. Ledger, heard of this, he came into Offaly and *plundered and burned* the country as far as the Togher of Cruoghan;" and again, "the Lord Justice came a second time into Offaly, and remained fifteen days in the country, plundering and spoiling it, burning churches and monasteries, and destroying crops and corn." These notices, from authentic history, afford us some idea of the state of this country in the middle of the sixteenth century; of the mode taken by its governors to suppress crime, and to gain the affections of the Irish chiefs and people. The modern part of the present castle must have been erected long since these days, probably in 1548, and appears to have fallen gradually into decay. After the Berminghams it passed into the possession of the Cowleys, an English family, the great ancestors of the Duke of Wellington.* From whatever side we approach, it

* The Hero of Waterloo boasts that he has not a drop of Irish or Milesian blood in his veins, and, so far as the old Irish stock is concerned, he certainly has not (except perhaps a slight collateral rill through the Cusacks of Cushinstown), no more than many other noblemen and gentlemen connected with Ireland, whom the *Times* calls Celts. For the following pedigree we are indebted to our learned friend, John O'Donovan:

"I. *Sir Henry Colley*, or Cowley, son of Walter Cowley, Esq., Surveyor-General of Ireland (patent 5th November, 1548), was evidently the last builder, re-edifier, or modifier of Castlecarbury. He was a captain in the army of Queen Elizabeth, and a Privy Councillor in Ireland. He married Catherine, daughter of Sir Thomas Cusack of Cushinstown, county of Meath, and had by her Sir George Colley of Edenderry, who became extinct in the male line, and,

"II. *Sir Henry Colley of Castlecarbury*, who was Constable of the Fort of Philipstown, Seneschal of the King's County, and Providore of the army, in the year 1561. He married Anne, the daughter of Adam Loftus, Archbishop of Dublin and Lord Chancellor of Ireland, by whom he had,

"III. *Sir Henry Colley of Castlecarbury*, who married Anne, daughter and heiress of Christopher Peyton, Esq. He died in 1637, leaving,

"IV. *Dudley Colley, Esq., of Castlecarbury*, Member of Parliament for

forms a noble picture, and such is its elevation that it can be seen upon a clear day from Poul-a-Phouca, in the county of Wicklow.

From the summit of this hill of Carbury, which is one of a series of gentle elevations that rise out of the extensive plains of Leinster, we gain a most commanding and extensive prospect, extending over the counties of Dublin, Kildare, Meath, Carlow, Westmeath, King's and Queen's Counties, with the hills of Allen, Carrick, Balrennet, Edenderry, and Croghan, standing up

Philipstown, in the first Parliament after the restoration of Charles II. He died in July, 1674. He married Anne, daughter of Henry Warren, Esq., county of Kildare, by whom he had many children, and among others his son and heir,

"V. *Henry Colley, Esq., of Castlecarbury*, who died in 1700; he married Mary, daughter of Sir William Ussher, of Dublin, and had Henry Colley, Esq., whose issue became extinct, and,

"VI. *Richard Colley, Esq.*, who, according to O'Connell, 'used to be picking potatoes after the crows in the county of Meath.' He succeeded in 1728 to the estates of his cousin, Garrett Wellesley, Esq., of Dangan, county of Meath, the head of an Anglo-Irish family of ancient respectability, and assumed the name and arms of Wellesley. He was elevated to the peerage of Ireland the 9th of July, 1746, by the title of Baron Mornington. He married, in 1719, Elizabeth, daughter of John Sale, Esq., Registrar of the diocese of Dublin; and, dying in 1758, left,

"VII. *Garrett*, second Baron of Mornington, who, on the 2nd of October, 1760, was raised to the dignities of Viscount Wellesley of Dangan Castle, and Earl of Mornington. He died in 1781. He married, on the 6th of February, 1759, Anne, daughter of Arthur, first Viscount Dungannon, and had,

"VIII. 1. *Richard, Marquis of Wellesley.*

"2. *William, Baron Maryborough.*

"3. *Arthur, Duke of Wellington.*

"4. *Gerald Valerian, D. D.*, Chaplain to King William IV."

See Dean Butler's notes to Grace's *Annals of Ireland*, p. 47, where it is stated that the Wellesleys were descended from the standard-bearer of Henry II. See also the notice of Laracor, in chapter iv. of this work.

Many distinguished generals and military men of high renown and true Milesian blood have, however, figured in foreign service. Among these may be mentioned the following, taken without selection from a host of other illustrious names:

Trophine Gerard, Comte et Marquis de Lally Tolendal (Tulnadaly, near Tuam), peer of France and minister of state: so illustrious during Napoleon's time. His father and grandfather were equally distinguished in the service of the French kings.

General Charles Count O'Donell, of the Austrian service, who was mortally wounded in the battle of Neresheim, in October, 1805.

Henry O'Donnell, Conde d'Abesbal, general in the Spanish service, who distinguished himself at the famous siege of Gerona in 1809. See Napier's His-

like so many acropoles amidst the deep pasture and meadowlands rich beyond description, and diversified by green hedges and occasional plantations, which stretch along the Boyne as far as the eye can reach; with the ruins of some of the ancient castles of the Anglo-Normans bursting through the surrounding foliage. Towards the north-east, on the approach from Enfield we see the tall tower of Mylerstown castle, another stronghold of the Berminghams* already referred to; and in the parish

tory of the Peninsular War, and *Annals of the Peninsular War*, vol. ii. p. 272.

Marshal Mac Donald, of the Connaught sept, so renowned during Napoleon's wars.

Don Carlos O'Donnel, general in the Spanish service during the Peninsular war. See *Annals of the Peninsular War*, vol. iii. p. 147.

Leopold O'Donnel, Count de Lucena, General Governor of Cuba in 1848.

Maurice Count O'Donnel of Tirconnell, a general in the Austrian service. Now living.

Count Manus O'Donnell, major-general in the Austrian service, who died in 1793.

Connell Count O'Donnell, field marshal in the Austrian service, who commanded the imperial army at the battle of Torgan, after Count Daun was wounded. He died in 1771.

John Count O'Donnell, a general in the same service. He was the brother of the foregoing.

Alexander Count O'Reilly, generalissimo of His Catholic Majesty's forces, captain-general of Andalusia, and civil and military governor of Cadiz, about the year 1786.

Andrew Count O'Reilly, general of cavalry in the Austrian service, who died in 1832.

We have also, in the service of the Autocrat of Russia, two distinguished members of the house of West Breffney, ever ready to crush democracy and republicanism: Joseph Prince O'Rourke, general-in-chief in the Russian empire; and Patrick Count O'Rourke, a colonel in the same service.

There are also in the Austrian service several of the Kavanaghs of Dermot Mac Murrough's race.

Among the descendants of the ancient Irish on the Continent may also be enumerated, fighting on the side of imperialism, Captain Daniel O'Connell O'Connor Kerry, in the Austrian service, who was commandant of Lodi in August, 1848.

See also the *Military History of the Irish Nation*, comprising a *Memoir of the Irish Brigade in the Service of France*. By the late Matthew O'Connor, Esq. Dublin, 1845.

There also some distinguished Irish officers in the Hungarian army at present, and among others Field Marshal Guyon (O'Guihu or Gahan), a native of Rathkeale, in the county of Limerick.

* The tourist should consult the map, and also the itinerary, from time to time, as he follows the various windings of the Boyne. Upon leaving Enfield,

of Ardkill, about a mile from the adjoining village of Carbery, the foundations of another castle, of which not even the name now remains; and the site of another fortress is pointed out near the mill in the parish of Clonkeen, midway to Edenderry: all showing the military importance of this district in former times. Edenderry, and the castles of Kinnafad and Carrick, form prominent objects as the eye sweeps round from south to west. Although the Boyne is said to rise at Trinity Well, a small stream which empties itself into it, and which may be considered the true source of the river, rises in an adjoining bog or marshy ground to the north of Carbury,—a branch of the great bog of Allen which extends towards the east,—and creeping round the base of the hill to the neighbouring demesne of Newberry, passes under a small bridge upon the Enfield road, as we enter the little village of Carbery adjoining.

As it would be impossible (even did it possess sufficient interest) to follow the various windings of the infant Boyne from its source to Clonard, where the stream enlarges sufficiently to permit of navigation for small row-boats, we must take to the road, and avail ourselves of as many way-side points of interest as the ordinary modes of travelling permit.

Our next resting-place is Edenderry, “the height or brow of the oaks,” about midway between which and Carbery we cross the river by a small bridge,* forming the boundary between Kildare and King’s County, which we now enter. It is a neat, well-built, and remarkably clean town, belonging to the Marquis of Downshire; but possesses little worthy of inspection to the antiquarian tourist except the castle of the Blundells, the ancestors of its present noble possessor, which crowns its wooded height, and the remains of a silver-mine adjoining.† As we leave the town, on the road to Monasteroris, the next point of attraction, we pass through a suburb of small cottages, with well-tended gardens in front of them, characterised by a degree of care, neatness, cleanliness, and, above all, by an appearance of industry and thrift quite unusual in Ireland. These cot-

the nearest railroad station to the Boyne’s source, after passing the little village of Johnstown, Mylerstown castle can be seen about a mile to the right of the road to Carbery. It is worth inspection.

* Rather by two bridges, for the stream-way of the Boyne has been lately altered here by the Board of Works.

† For a description of Edenderry, see Fraser’s admirable “Hand Book for Travellers in Ireland.” Dublin, 1849.

tages are given by the Marquis of Downshire to industrious tradesmen and labourers at a shilling a year rent. The general appearance of comfort in this district at once bespeaks the encouraging landlord and the admirable care of the resident agent. The peasantry are a remarkably fine, stalwart race, and the females particularly handsome. A very admirable road, through a well-cultivated country, takes us nearly parallel with the Boyne to our next resting-place; a collection of ecclesiastical ruins, about two miles distant from Edenderry, our route still continuing through the King's County.

Monasteroris, the locality just referred to, consists of the remains of a small church with a double belfry, built, probably, about the fourteenth century, and surrounded by an ancient grave-yard; to the east of this, in one of the adjoining fields, we find the ruins of a castellated monastery, the walls of which are of great strength and thickness; and not far off, placed upon a mound which bears all the evidence of being artificial, and was probably an ancient tumulus, we observe the basement of a square dove-cot or pigeon-house, a usual appendage to the houses of the English ecclesiastics in Ireland. The accompanying sketch, taken from the south, affords a tolerably good idea of this interesting group of ruins.



Monasteroris, in Irish, *Mainister-Feorais*, the Monastery of Mac Forais, or Mac Pierce's Monastery, is celebrated in our mediæval history, and the references to it in the works of that period are numerous and interesting. The manner in which

this name arose is peculiar and worthy of remark. Pierce De Bermingham was one of the early English settlers, and received a large grant of land in Leinster. The surname was dropped by the Irish-speaking people, and the Christian name, Pierce, or Peter, translated into Gaelic, as Horish, or Feorais, a name which the descendants of the Berminghams still bear to the present day. The Clan-Feorais—the tribe-name of the family of Bermingham—applied the Irish appellation to their territory, which was coextensive with the barony of Carbury, and extended along the Boyne, both in Kildare and King's County, as far as the borders of Meath.* In process of time this Anglo-Norman stock became more Irish than the Irish themselves; they joined with the O'Conors of Offaly, and other Irish chieftains, and made fierce war upon the English settlers within the Pale at different times. We have an account of the cause of one of these wars, given us by Dudley Firbisse: "That warr was called the *warr of caimin*, that is, an abuse that was given to the son of the Chiefe of the Berminghams (Hibernice, to Mac Ffeorais, his son), in the great court in the town of Ath-truim, by the Thresurer of Meath, i. e. the Barnwall's sonn, so that he did beate a caimin (i. e. a stroke of his finger) upon the nose of Mac Fforais, or Bermingham's son, which deede he was not worthy of, and he entering on the Earle of Ormond safe guard; so that he stole afterwards out of the town, and went towards O'Conor Ffaly, and joined together; and it is hard to know that ever was such abuse better revenged than the said Caimin; and thence came the notable word (*Cogadh an Caimin*)."[†] During this war the Berminghams and O'Conors "preyed and burnt a greate part of Meath."

Sir John de Bermingham, Earl of Louth, founded an abbey in the year 1325, for conventual Franciscans, at Totmoy, in Offaly, the ancient name of this territory; and from the Irish name of this chieftain it was called Monaster-Feoris. In 1511,


* See the Annals of the Four Masters, A. D. 1151, 1446, &c.; also the Annals of Ireland in the Miscellany of the Irish Archaeological Society, from p. 202 to p. 234; also Archdall's *Monasticon*; see also O'Donovan's Dissertation on Irish Names, in the Irish Penny Journal, 184, edited by Dr. Petrie, and published by Gunn and Cameron, Dublin.

For the possessions of John Bermingham here, in 1625, see the published Inquisitions, *Lagenia*, Kildare, 6 Car. I., and No. 92, Car. I.

[†] *Caimin* (a stroke of the finger), i. e. a fillip on the nose.

Cahir O'Conor, Lord of Offaly, was slain near this Monastery. It was a place of considerable strength, as the remains of the building still testify, and sustained a lengthened siege by the Earl of Surrey, Lord Lieutenant of Ireland, when he marched into Offaly at the time of his expedition against the O'Moores of Leix, who, with other Irish chieftains, had invaded the borders of the Pale.* At the time of the suppression of religious houses it was granted to Nicholas Herbert.

Following the road which leads from Edenderry to Clonard, we again cross the Boyne, and re-enter Kildare, at the little bridge of Kinnafad,—*Ceann-atha-fada*, “the head of the long ford,”—where the river is still inconsiderable, but the streamway has been widened, and its banks straightened, so that it here resembles a small modern canal. On crossing the bridge we get a view of the castle of Kinnafad, another stronghold of the Berminghams, which stands in an adjoining meadow, and of which the accompanying is a faithful sketch.



It is a large, square, block of building, measuring forty-seven feet by thirty-one on the outside, the external walls being still quite perfect. It appears, from its few and narrow windows, as well as its general design, to have belonged to an earlier era than the modern part of the castle of Carbury, when strength influenced the builder more than attention to comfort.


Although the river is but inconsiderable for the first few miles of its course, still, from the difficulty of crossing it except at certain points, these were generally defended with great

* Harris's History of Dublin, p. 290 ; also Archdall's *Monasticon*, p. 403.

care and forethought. Thus at every ford and pass, or bridge, if such existed at the time, some castle was erected. This was in all probability the cause of the position of Kinnafad Castle, which stands beside a shallow in the river, which the local traditions say was often the scene of fierce conflict.

A few months ago, in deepening the bed of the river, and in some places altering its course altogether, so as to cut off the angles and render its stream-way straighter, as we already observed, near Edenderry, the workmen dug up here some human remains, as well as those of a horse, and several weapons of exceeding interest indeed. Through the kindness of a friend, we are enabled to have some of these figured in this work.*

The remains consisted of the skeleton and iron shoes of a horse, several portions of human skeletons, and two very perfect skulls. With these were found divers iron and bronze weapons, — a circumstance of considerable interest, for although it was rumoured that such



had been very frequently found together, no well-authenticated instance of it has been heretofore recorded. These weapons, which are here represented, consist of,—No. 7, a very perfect straight, short sword of iron, the most beautiful of its kind yet discovered; it is twenty-two inches and a half

* Mr. Murray of Edenderry, Lord Downshire's agent.


long; the blade, which measures upwards of seventeen inches, is very narrow in the middle and towards the handle, but, increasing suddenly towards the top, it forms a very obtuse point, an inch and a quarter broad. A sword of the same character, but not so perfect, was found in the excavations lately made in the Shannon. Some swords of the same type, but shorter, and with parallel edges, were a few years ago found at Dunshaughlin. See page 15. Ancient iron swords are much rarer than bronze ones; until very lately there was scarcely one to be found in any of our collections; we have now four distinct forms of them:—that just described, which is the rarest; a shorter, sharp-edged sword, very like the ancient Roman; the heavy, broad-bladed sword, with a narrow and ornamented handle, supposed to be Danish; and the long, straight iron sword, which varies in size in different specimens, and of which a fragment of one found at Kinnafad is figured here, No. 8. This is evidently of later date than any of the others.

The brazen sword-blades found in Ireland may be classed under two heads: the long, narrow, straight one, tapering from the handle to the point, like the modern small sword; and that with a broad belly, swelling towards the end, resembling the ancient Grecian or Phœnician.* With the two iron swords here figured were found two very perfect spear-heads also of iron, Nos. 1 and 6, and with such small sockets that we are at a loss to know what description of wood, except perhaps yew, was used for their handles. The brazen weapons found in connexion with these consist of the blade of a dagger, No. 2, and two bronze hatchets, commonly called *celts*, Nos. 3 and 5, a sort of war-axe, which was fastened on the end of a curved stick. That figured as No. 5 is a particularly fine specimen, and ornamented on the sides. The other is remarkable from its exceeding lightness, showing the great quantity of tin of which the antique metal in this instance is composed. The cut No. 4 shows one of the horse-shoes. It is peculiar in shape, remarkably oval, and

* Specimens of all these antiquities will be found in the Museum of the Royal Irish Academy, which is open to every person desirous of becoming acquainted with these subjects; and the able Curator of which, Mr. Clibborn, the best public officer which any institution ever possessed, takes delight in showing the collection to strangers. Those intending to visit the Boyne, or any other locality of archaeological interest in Ireland, should first visit the great national collection at the Academy.

convex on the under side, as may be learned from the position of the small cocks and the nail groove, showing that it was intended for the field, not the road. That bronze and iron weapons have not been more frequently found together is to us a matter of surprise, for they must have been long in use together, and we have reason to believe bronze weapons were used to a very late period indeed.

It is, we think, a fair inference, to suppose that all these weapons were employed by the belligerents who fell at the pass of Kinnafad: can we form a conjecture as to who they were? Upon the races of men who fell in this encounter we certainly can speculate with some degree of plausibility. In the ethnological inquiry, at chapter ix. of this work, the question of the early races of Irishmen is discussed; there it will be seen that we have strong evidence in support of the idea that two races, totally distinct in feature and form of head, formerly existed in this country, and probably fought for the mastery;—a long-headed people, with thick, narrow crania, low foreheads, projecting noses, deep, square orbits, high cheek-bones, prominent mouths, and narrow chins,—probably the first settlers or original stock, low in intellect, dark-haired, strong-bodied, hardy, and courageous. The other a round or globular-headed race, with features not so marked, but evidently possessing more intellect,



and who were probably the conquerors of the former. Examples of both races, particularly the former, may still be found among some of the modern Irish. Two such heads—well-marked specimens of their kind—were found, along with the

weapons and antiquities described, at Kinnafad. They are represented in the accompanying wood-cuts. The long head is quite perfect, and has a sword-cut on the crown. The base of the skull and face has been broken off the specimen of the globular head. Is it unnatural to suppose that these people fought with the weapons by which their remains were found surrounded?

It is now more than five years since we first drew attention to this subject, and promulgated the idea as to the two races which originally inhabited this country; and it is pleasing to find that every instance of human remains since discovered in Ireland is confirmatory of the views we then put forward.*

Upon the northern side of the river, in the King's County, there is little worthy of inspection, except the ruined castle of Clonmore, not far distant from the Yellow River, a stream which empties itself into the Boyne, about midway between Edenderry and Clonard, and forms the boundary between the King's County and Meath.

We are now upon the right bank of the Boyne, passing, by a smooth and admirably kept road, through deep meadows, bordered by luxuriant hedge-rows, particularly of white thorn, which blooms here in great beauty. About a mile from Kinnafad castle, and half a mile from the Boyne, the road passes by the castle of Grange, a fortalice of a somewhat later age than that just described, and a part of which is still inhabited by one of the Tyrrells, a family of repute in the ancient kingdom of Meath. We have not been able to discover any references to either of these two buildings in the historic annals, and it is probable their history has not been preserved in the rolls of time.

We next ascend the sloping hill of Carrick,—one of those high places in the great plains of Leinster which we already saw from the hill of Carbury. From the top of this elevation we again obtain a most commanding and extensive prospect of the well-wooded and highly-cultivated plains of Meath and King's County, forming one vast undulating sea of green;—a truly glorious land, rich and fair; gazing upon it we wonder not at the tenacity with which our fathers clung to it, nor

* See a Lecture on the Ethnology of the Ancient Irish, delivered at the College of Physicians in 1844, and originally published in the Dublin Literary Journal.

at the efforts made by the invaders to possess it; neither can we wonder at the peasant's love for it;—we are now only astonished how poverty, misery, and starvation even unto death, can exist in any corner of the island with such a garden as this within it.*

This hill, though not mentioned in history, that we have been able to discover, must, not only from its situation, but from the traditions in the neighbourhood,—the rock denominated the Witch's Stone, and some slight vestiges of architectural remains upon its summit (probably those of a hermit's cell),—have been a place of note in very ancient times, antecedent to the date of the ruins which at present exist upon it. It is said that a considerable town once stood at the base of its north-eastern side, where there is now a vast limestone quarry. The extensive woods of Ballindoolan stretch down from its summit towards the north, and upon the south-eastern brow of the hill adjoining, the more direct road to Edenderry, we find another group of ruins, the church and castle figured upon the opposite page.

The hill of Carrick (the Rock), which very much resembles that of Carbury, and commands a similar extent and beauty of prospect, derives its name from a large block of trap rock, called "the Witch's Stone," which stands upon its northern brow, just over the great limestone quarry. It is evidently the same kind of stone as the large mass of trap which is to be found about ten miles off, near Philipstown, to the south-west of this hill; but whether it is a boulder, and was carried to this spot—which is in the general direction of the great current which appears to have transported the beds of limestone gravel throughout Leinster—by natural means; or was transported there by art for some sacred purpose in early Pagan times, as we know was frequently the case, it is difficult to say. Upon the lower Boyne, near the hill of Dowth, we meet masses of compact basalt, fully as large, which must have been transported there by artificial means. The legend is, that a witch cast this stone from the hill of Croghan, at some of our early saints, and that it alighted here. This is a favourite and widely spread legend in the north of Europe; in Scotland we find it preserved

* While we write, we understand there are 1800 paupers in the Workhouse of Edenderry! There must have been something wrong in the system which produced all this misery in the neighbourhood of such a fertile country.

in the story of the Devil throwing the hill of Dumbuck, Dumbarton rock, and Ailsa Craig, after St. Patrick, when he was flying into Ireland.

Some mischievous quarryman split this witch's stone, by blasting it, a few years ago. For this wanton act he was obliged to leave that part of the country.

Near the summit of the hill there is pointed out "the Mule's Leap," when running off with a saint from the Church of Carrick. Eight holes, marking, it is said, the places of the mule's feet, and showing a distance of about ten yards between the place from which it sprung and where it alighted, are still to be seen, and it is said that no grass ever grows upon these footprints. The locality is worth observing, not for the nonsensical story of the mule, but because there is evidence of some masonry—probably the foundation of an ancient oratory—existing between the two sets of footmarks.



As this castle still bears the local name of Carrick-Oris, we have a proof stronger than conjecture that it was erected by the Berminghams. It was originally a tall, oblong square tower or keep, a portion of the southern end of which is yet perfect, measuring about thirty-two feet in length. From the extent of the ruins upon the northern side, it must have been nearly ninety feet long: the walls are upwards of four feet thick. This was the court of Pierce Bermingham in 1305, and consequently the seat of the "treacherous baron," so bitterly

complained of by O'Neill and the Irish chieftains in their Remonstrance to Pope John XXII.*

In the Annals of the Four Masters, A. D. 1305, and also in James Grace's Annals of Ireland,† we learn the circumstance of the massacre which occurred here, and which earned for the inhospitable owner of the castle the opprobrious title bestowed on him by the Irish chieftains in 1315.

Murtagh O'Connor, King of Offaly, and his brother Calwagh, with twenty-nine of their companions, were slain here by Jordan Comin, and Sir Pierce Mac Feorais, the latter of whom had invited them to a feast on Trinity Sunday at his castle, "*apud Carricke in Carberia*." In Mageoghegan's translation of the Annals of Clonmacnoise, the murder is thus alluded to: "A. D. 1305, Murtagh O'Connor of Offallie, Mulmorrey, his brother, and Calvagh O'Connor, with twenty-nine of the choicest of their family, were treacherously killed by Pyers Bermyngham, within the Castle of Carrickffeorus." In the Remonstrance just alluded to it is said: "The instant they stood up from the table he cruelly massacred them, and sold their heads at a dear price to their enemies; and when he was arraigned before the King of England, the present king's father, no justice could be obtained against such a nefarious and treacherous offender." Can we wonder at the Irish people acknowledging the power, and seeking the interference of the Pope, when they could not obtain redress nearer home?

This Pierce Bermingham was the progenitor of the Mac Feoris.‡ These references serve to fix the site of a very memorable locality hitherto unnoticed.

The adjoining Anglo-Irish church appears to be of a date coeval with that still remaining at Monasteroris,—probably the end of the thirteenth century,—one of those long, low buildings, with a belfry in the western gable, and small, narrow, pointed windows in the sides, of which we have so many examples remaining. This church is forty-six feet long and twenty-two broad in the clear. The eastern and southern walls are still standing, and two small, narrow windows, deeply

* See Memoirs of Charles O'Connor, of Belanagare, pp. 59, 74.

† Edited for the Irish Archæological Society, by Dean Butler. See p. 48, n. c.

‡ See, in addition to the remarks on this name, Dean Butler's History of Trim Castle, p. 31.

splayed on the inside (one square and the other circular-headed), and evidently different in date, and the cut stones of which were probably used in some earlier building, as well as a small almary, exist in the latter. The door was in the northern wall of the chancel, and a small, narrow window, now built up, a little to the left of the centre, remains in the eastern gable, which latter rises into a very perfect double belfry.

There are several traditions and some curious remnants of superstitious usages yet remaining attached to this locality. The peasantry used to show a large stone, with some indentations in it resembling the print of the hand, which they said was lifted by St. Columbkille. Not long ago, people were in the habit of carrying away from hence portions of the clay of a priest's grave, and using it as a cure for several diseases, a practice formerly in much repute, particularly in the west of Ireland.*

A few hundred yards below the ruins on the hill of Carrick, in the angle formed by the junction of the roads leading to Edenderry and Carbery, we find the holy well of Tobercro, or *Tober Crogh-neeve*, the Well of the Holy Cross, a beautiful spring shaded with flowering briars and wild white roses. Although it is now totally neglected, and its site scarcely known even by the neighbouring peasantry, it was once highly venerated, and its virtues greatly esteemed. The water runs into the Boyne through the adjacent valley. See page 53.

There are two roads leading along the river towards Clonard, on the Kildare side: the lower sweeps through the valley; the upper, that which we have chosen in our present excursion, on account of the commanding prospect which it affords, winds over the hill of Carrick, which we have just described. Proceeding northward towards the Boyne, we pass through a noble country with enclosed paddocks, fringed with well-grown timber, and exhibiting an admirable state of cul-

* This practice, which may to some of our readers appear as extraordinary as it is disgusting, is nevertheless frequently resorted to up to the present time. We have known persons in a respectable rank of life to boil the clay taken from the grave of Father O'Connor, in the abbey of Roscommon, upon milk, and drink it, for the cure of several diseases; and an account has been given by Dr. Pickells of Cork, of a female who, it was said, became seriously diseased from having swallowed the larvæ of beetles and other insects, in making use of a similar remedy.—See the Transactions of the College of Physicians in Ireland, vols. iv. and v. Also, "Our Fellow Lodgers," by Rev. Robert Walsh, M. D. Dublin, 1847.

tivation. Two objects claim our attention: upon the right hand side of the road, the site of an ancient castle, of which nothing now remains but a cairn of stones; and a little farther on, Toberaulin, or "the Beautiful Well," another sacred spring shaded by graceful thorns, near which we again join the lower road, which runs parallel with the river as we approach it at the bridge of Ballybogan. Here, at a place called Glyn, where three roads meet in an open space shaded by trees,—one of those calm, peaceful, homestead spots, so frequently met with in England,—we find "Lady Well," a fountain dedicated to "the Blessed Virgin," and a very memorable spot in days gone by. It immediately adjoins the road, and is shaded by a splendid sycamore tree, to which a few votive offerings might, in former days, be seen attached. A fair and *Patron* is held here in harvest.

Holy wells abound in this locality, and assist to feed the growing stream, so that the river becomes doubly consecrated, not only by the ruins of sacred edifices which cluster upon its banks, but through the waters which flow into it from so many hallowed springs. Besides the Well of Trinity, and these two just mentioned, we have Tobercro, and also Carbury Well, and not far from the point where the Yellow River pours its waters into the Boyne we have upon the Kildare side the Well of Tobernakill;—six in all, baptizing the infant Boyne.

The peasants' faith in the *Blessed Well* has ceased; the last remnant of it, at least in the midland counties of Ireland, was obliterated by the famine.

"Old times are changed, old manners gone."

The days of rounds and penance, of vows and votive offerings, of charm and miracle, of pilgrim and boccagh, of fun and frolic, faction fight and whiskey, which took place at the *Patron* (i. e. the patron saint's day) at our holy wells, are past and gone; and, once omitted, these rites, ceremonials, and pastimes of the people, are seldom or never restored. There is scarcely a holy well in Ireland, the waters of which, independent of the general efficiency of the *station* performed there, either as a penance or in redemption of a vow, but is celebrated for its cures of particular diseases; and this at which we rest, with the other wells upon the Upper Boyne, were famed far and wide for their sanitive efficacy. Most of our holy wells were objects of veneration, perhaps of worship,

long prior to the spread of Christianity in Ireland, when the Pagan altar, the sacred grove, and Druid priest, were their general accompaniments; and, therefore, it cannot be wondered that so many unchristian rites and ceremonies should still attend the practices observed there by the uneducated.

——— “ This may be superstition,
But even the faintest relics of a shrine,
Of any worship, wake some thoughts divine.”

Each holy well generally bears the name of some saint, upon whose festival day the *Patron* is celebrated; and each has its legend, often of great interest both in a historical and topographical point of view. Ancient thorns, or gnarled ash trees, clad with the propitiatory offerings of the pious, bend over their clear waters; a certain number of oval or circular stones, used as a sort of beads, generally surround their margins, and a quantity of white pebbles are scattered over the bottom of each; while in many instances a pair, or more, of sacred trout are allowed to remain unmolested in these still pools. Like other shrines of religious veneration, the virtues of our holy wells are subject to variation, remaining for years inert, and then breaking out afresh, upon the recital of a recently performed miracle by some cunning boccagh, or neighbouring publican: when, in defiance of the threatenings of the Church, the exhortation from the altar, and frequently of the personal influence of the Roman Catholic clergyman on the spot, scenes of superstition, riot, and debauchery ensued, which would now be scarcely believed if we ventured to relate them. These wells were often not only chary of their powers, but very fickle in their dispositions, frequently changing their localities, from their waters having been profaned by the irreligious or diseased, and springing up next morning in a different spot; or, like the Boyne in more miraculous times, bursting forth from their rocky prisons, and overwhelming in their waters their sacrilegious polluters. The pilgrim was allowed to drink at the well itself, but he was not permitted to wash, except in the stream which flowed from it; and most of the instances of the change of locality among our holy wells is attributed to some diseased person having been bathed in their waters, and for which offence the saint's displeasure has been generally manifested.

We require a book upon the holy wells of Ireland. Such

a work would be instructive, amusing, and popular. If illustrated by a good artist, capable of feeling such subjects, and drawing them with fidelity,—a Petrie or a Burton,—it would greatly assist the study of the antiquary, and such embellishments would afford the fireside reader a series of some of the most charming scenes which this country possesses. Amidst the wildest glens, among the most savage rocks, on bare mountain tops, surrounded by savage grandeur, or located by the quiet homestead in the cultivated plain; embosomed among aged trees in the sequestered valley; o'ershadowed by the ruined church or abbey wall, or guarded by the ancient sculptured cross; with the drooping thorn, or the ragged ash, hung with the offerings of the pilgrim, stretching its arms over the crystal fountain;—these venerated spots may be found in abundance; and with some "Blind Girl" or burly boccagh kneeling by their waters, the artist will find subjects for his pencil of surpassing interest. And the author in his description of these ancient and romantic sites of religious veneration or medical superstition,—by inquiring into their Pagan origin, recounting the legends attached to each, so illustrative of ancient manners, and elucidating popular traditions which are becoming hourly obscured; in telling something about the saint to whom each is dedicated, and of the rites and ceremonies, the *rounds*, prayers, and all the formulæ (generally self-imposed) which are there gone through, by the pious pilgrim, the devout penitent, the faithful valetudinarian, or the paid representative, together with some notices of the humours, fights, and frolic of the *Patron*, its tents and pipers, beggars, rogues, and gamblers,—could not fail to interest his readers.*

* A little work was produced some years ago, called "The Holy Wells of Ireland," from which title the reader might suppose that some, if not all, the subjects alluded to in the foregoing passages were treated of. Such, however, is not the fact. It is a mere tirade against Popery, for which purpose alone it appears to have been compiled. Its descriptions are almost entirely made up of extracts from the works of Inglis, Cæsar Otway, Carleton, Crofton Croker, and other modern Irish writers.

The Annals of the Four Masters, now in process of translation and annotation by O'Donovan, and which, when complete, will form the great groundwork for all future Irish histories, contain numerous descriptions and accurate references to the origin and names of our Irish wells; and the great local and topographical knowledge of the learned commentator renders these accounts of immense value. Cambrensis and his commentators, Holinshed and Richard

The materials for a work of this description abound in such quantities that the only difficulty is in selection. Almost every barony possesses several holy wells. The Lives of the Saints, and the Irish Annals and early histories, are profuse in their references to our "blessed wells;" but it is only by visiting these spots upon *patron* days, by culloguing with the neighbouring shanaghies, and by appearing to give credence, in addition to tobacco, to the priestess of the well, that the legendary lore of such can be acquired, or their traditional romance preserved.

In the Irish ballad poetry of the last few years we find several charming songs upon our holy wells; in particular we would instance those by our friend, Samuel Ferguson, Esq.,

Stanihurst, may be consulted, particularly with reference to the legendary tales and mode of performing stations at Patrick's Purgatory and other holy wells and places of religious resort in their day; as also Camden, Hammer, and other writers of that time; but it must always be borne in mind with what prejudices these writers were possessed, for what end and under what influence they wrote, as well as the exceeding ignorance of the Irish language which they exhibit. Dr. Lynch's *Cambrensis Eversus*, lately translated and commented on by the Rev. Matthew Kelly, and published by the Celtic Society, should be carefully consulted. All the publications of our Archæological Society abound with materials which might be made use of with effect, particularly the translation of Nennius, by the Rev. Dr. Todd and the Hon. Algernon Herbert, especially that portion of it upon the "Wonders of Ireland, according to the Book of Glendalough." Dr. O'Connor's third letter, published in his *Columbanus ad Hibernos*, contains many interesting particulars on the subject of Irish well-worship, and will show our English readers what the opinions of an educated and intelligent Irish Roman Catholic priest were on the subject. Richardson's "Great Folly, Superstition, and Idolatry of Pilgrimages in Ireland," published in 1727, should be read; and also Barnaby Rhyche's very scarce "Description of Ireland, 1624," where the reader will find many curious matters connected with our vulgar superstitions generally, and the holy wells of Dublin in particular. The manuscript letters preserved in the Library of the Ordnance Survey, contain much valuable information. The Dublin and Irish Penny Journals afford notices of many blessed wells; and in the last volume will be found a most charming paper on the subject, by Petrie, under the head of "St. Senan's Well." We have to express our great obligation to Mr. Hackett of Middleton, and to Mr. Windele of Cork, for having furnished us with several interesting topographical descriptions and a quantity of legendary lore connected with this subject.

We have written this note in the hope of eliciting further information, as well as directing attention to this curious subject; and should we find leisure and inclination to continue the "Irish Popular Superstitions," two parts of which have already appeared in the Dublin University Magazine (Nos. for May and June, 1849), we will devote a chapter to our blessed wells.

and also ones by Mr. Fraser and Mr. Teeling;* but most of the poems upon these our sacred fountains assign to them a fairy origin, an idea not by any means popular among the people, who are generally acquainted with the saintly legends attached to them; by what patriarch of the Irish Church they were blessed or cursed; what miracles they have wrought; on what days they are to be resorted to; and what prayers are to be repeated at them;—circumstances never connected with the fort or rath, the cave, or hill, or glen,—the true fairy ground.

The following lines, characteristic of the Irish people's religious belief in blessed wells, have been forwarded to us by a lady, while these pages were passing through the press:

“Thou chosen spring of sacred gift!—
 By prayer and penance blest!—
 Here, on thy knee-worn margin, let
 My wand'rings find a rest.
 I would not pass thee heedlessly,
 Or deem, with scoffing thought,
 That God hath, thro' thy hallow'd drops,
 No healing wonders wrought.
 With solemn pause I gaze upon
 Thy surface calm and pure,
 Recalling days when simple souls
 In faith found simplest cure!


“Who knows thou art unsanctified,
 And hast no salving pow'r?
 Let me, at least, revere thee now,
 In thy deserted hour.
 Perchance, when angry justice frown'd
 On sinning sons of earth,
 The Virgin's interposing tears
 First gave thee heav'nly birth?
 Or were thy waters angel-stirr'd,
 For humble suff'rers' weal?
 Be blessed still!—and may I too
 In thee my sorrows heal!”

To return to the stream of our discourse. The sedgy, sluggish river is here crossed by the first bridge of any note which we meet with upon the Boyne, and leads to Ballybogan, “the

* See *The Spirit of the Nation*; the *Book of Irish Ballads*, by D. F. M'Carthy; *The Ballad Poetry of Ireland*, by C. G. Duffy; the *Poems of Thomas Davis*, &c.

town of O'Bogan," an insignificant village upon the northern side of the river.

Upon this, the Meath side, and a little to the north-west of the bridge, are the ruins of one of the largest churches and monasteries, except those of Trim, Slane, Bective, or Drogheda, which we meet with in our downward course; and if indeed the domiciliary buildings (of which nothing but the foundations now exist) were in proportion to the church, the former must have been very extensive, for the latter is of great magnitude. The accompanying engraving, taken from the south-east, shows all that now remains of the church or priory of Ballybogan, which is pleasingly situated in a rich meadow, surrounded by trees, on the river's bank. The church was originally cruciform, but the transept has been entirely destroyed on both sides. The nave and choir measure 193 feet in the clear, and are twenty-six feet broad. So very little architectural decoration is to be



found, either in the walls which are still standing, or among the surrounding rubbish, that we cannot believe it was ever highly decorated. Over the western entrance there was a tall, narrow window, without mullions or cross-bars, the arch of which, as well as those of the east window, exhibit the transition from the circular to the pointed style. In the northern wall of the choir three sedilia, with trefoil arches, yet remain; and attached to the outer wall of the chancel, upon the same side, there is a very curious little building, apparently a vestry or robing-room.

This priory was almost exclusively English. It is mentioned

only twice by the Four Masters ; once, in the year 1446, in recording the interment of Tany, son of Maolín, who was interred in the monastery of *Baile-úí Bhogain*; and again, the year following, when we read of a great plague which raged in Meath, Leinster, and Munster; and by which it is related that several hundred priests died; among the rest the Prior of Ballybogan.*

Archdall has collected with great care some curious notices of this monastic edifice, which was founded in the twelfth century by Jordan Comin,† under the invocation of the Holy Trinity, for canons of the order of St. Augustine, and was originally called "The Priory de Laude Dei." By an inquisition taken in the year 1399, "it was found that John O'Mayller, a mere Irishman, and of the Irish sept of the O'Mayllers, enemies to our Lord the King, was instituted to the priory of the Blessed Virgin of Ballybogan; but Richard Cuthbert did on the same day make due proof that the said priory was not under the invocation of the Virgin Mary, but dedicated to the Holy Trinity, and that he was the lawful prior thereof. Cuthbert was accordingly restored to the temporalities."‡ From the well of Ballybogan, or Lady Well, being dedicated to the Virgin, it is not improbable that there may have been some earlier monastic buildings here under the same invocation, and that hence arose the dispute just referred to.

In 1404 King Henry IV. granted certain lands belonging to the prior of Ballybogan, in the county of Dublin, to one William Stokynbrygge. Dudley Furbisse records the burning to the ground of this priory about the middle of the fifteenth century. The last prior was Thomas Bermingham, and the following inventory of his possessions has been preserved upon the surrender of his church property to Henry VIII., in 1537.

* We might add here some notice of the different plagues, famines, and pestilences, from which this country has suffered during the last 1000 years, and show that the very same misery under which we have so lately laboured is but a repetition of similar calamities which existed in early years, but that we fear to extend this little work to too great a length. A history of our Irish plagues and famines would be useful in a medical, a sanitary, and an historical point of view. The materials are most abundant.

† Was this the Jordan Comin who assisted at the massacre of the Irish chieftains at Carrick, in 1805? If so, this priory must have been founded in the thirteenth century.

‡ *Monasticum Hibernicum*, p. 514.

Besides the cloister, kitchen, &c., there were attached to the priory "twenty-four messuages, four gardens, one orchard, one curtilage and an haggard within the precincts of the said priory; also the manor of Ballyboggan, containing one hundred and sixty messuages, one hundred and sixty gardens, a water-mill, six eel-wiers, eighty acres of arable land, one hundred and forty of meadow, one thousand of pasture, forty of wood, forty of underwood, and six hundred of moor in Ballyboggan, of the annual value, besides all reprises, of 8*l.* 6*s.* 8*d.*; sixty messuages, forty gardens, three hundred and twenty acres of arable, two hundred and forty of pasture, forty of meadow, eighty of underwood, and three hundred of moor, in Herreyeston alias Ballykill, of the annual value, besides all reprises, of 40*s.*; one hundred messuages, sixty gardens, forty acres of arable land, ninety-six of meadow, six hundred and forty of pasture, one hundred and sixty of wood, and three hundred and sixteen of moor, in Knockangoll, Ballykesty, and Cardoneston, of the annual value, besides all reprises, of 50*s.*; and sixty messuages, forty gardens, two hundred and forty acres of arable, three hundred of pasture, two hundred and forty of moor, and two hundred of underwood, in Kyllnedobbragh and Kyllaskelyin, of the annual value, besides all reprises, of 50*s.*"* From this recital we learn somewhat of the vast possessions held by the Church in Ireland before the Reformation. The greater portion of the lands of this monastery, together with those of Clonard, were granted by Henry VIII. to Sir William Bermingham, afterwards created Lord Carbery; and the reversion of the monastery, with certain of the estates, were bestowed on Edward Fitzgerald in the latter part of the reign of Elizabeth.

Ware's Annals inform us that in 1538 a crucifix which was held in great veneration was here publicly burned; and *Tober-Crogh-neeve*, or the Well of the Holy Cross, at the foot of the hill of Carrick, mentioned at page 45, may, perhaps, have derived its name from some connexion therewith. At the same time the reformers burned the celebrated image of the Virgin Mary at Trim, and St. Patrick's Staff (crozier) at Dublin.

The abbey and surrounding lands at present belong to Lord Lansdowne, who has most creditably placed several buttresses

* *Monasticon Hibernicum*, p. 515.

against the northern wall, which was in a falling condition some years ago. The prospect from the abbey, though tame, is particularly pleasing. Looking up the Boyne upon the Kildare side, the planting of Rahin demesne stretches along a gentle elevation which slopes gradually from the river's edge, and the country rises in successive undulations to the woods of Ballindoolin and the hill of Carrick, while toward the west we get a glimpse of the hill of Croghan, in the King's County.

Our next point of interest is Clonard, to which two roads, one on each side of the Boyne, lead from the bridge of Ballybogan. The southern will be found most interesting to the tourist, as it passes through a pleasingly-diversified country, not remarkable either for its cultivation or its amount of population,—which is here, indeed, particularly thin,—but for the number, variety, and graceful form of the swelling undulations through which we pass. To this part of the country may be applied the simile which has been elsewhere used with respect to Tipperary, that it resembles a swollen sea which had become suddenly consolidated. A circular earthen fort, of the military class, belonging to the times before stone buildings were much in use, may be seen upon the south-eastern shore of the Boyne, in the townland of Ballycowan, not far from the high road, and can be visited by those who feel particularly interested in the examination of such remains; but as we shall direct attention to other similar structures, of greater magnitude and more accessible, upon the lower portions of the river, it is here unnecessary to do more than point out its site.

CHAPTER III.

CLONARD, AND THE BOYNE TO TRIM.

CLONARD.—DESCRIPTIONS OF CÆSAR OTWAY.—THE BATTLE OF 1798.—ANCIENT SEAT OF LEARNING.—HISTORY OF ST. FINIAN.—THE ABBEY, MONASTERY, AND ROUND TOWER.—DISASTERS AND DEDICATIONS, ANCIENT AND MODERN.—ANTIQUE FORT AND LAVATORY.—RECOVERY OF AN ECCLESIASTICAL STOUT.—THE PAGAN REMAINS AT CLONARD.—THE MOAT AND FORT; SPECULATIONS ON THEIR ORIGIN AND USES.—THE BATTLE-FIELD OF RATHCORE.—THE BATTLE OF BOLD-BOYNE.—TICROGHAN.—DONORE CASTLE.—THE BOYNE TO TRIM.—TRIMBLESTOWN.

CLONARD, at which we have now arrived, is the first spot of great and undoubted historic and ecclesiastical celebrity which we meet with on the Boyne, and deserves a more lengthened notice than any of the foregoing. The great western road here crosses the river by Leinster bridge, a remarkably flat, well-built structure.

Our lamented friend, Cæsar Otway,—a most graphic describer of Irish scenery, the most charming of companions, and one of the most genuine, true-hearted Irishmen that ever lived, and whose powers of description were such that, to use the expression of an Edinburgh reviewer, "Give C. O. an old stone, a green field, and a gossoon, and he will make a book out of it,"—noticed this spot in his "Tour in Connaught" in 1832, and, as we affect to be little more than gleaners in this work, we hesitate not to transcribe some of his impressions of the place at that period.

"The Boyne water flows lazily here, amidst sedge and reeds, —appearing but the dark drain of an immense morass—the discharge of the waste waters of the bog of Allen. A strong position in time of war—Lord Wellington knows it well: he has often had his soldier eye upon it, his paternal mansion Dangan being not far off to the right, near Trim. How different was the young, fun-loving, comical, quizzing, gallanting Captain Arthur Wellesley, when residing in his shooting-lodge between Summerhill [Trim] and Dangan, from the stern, cautious, careworn Fabius of the Peninsular war; the trifling, provoking, capricious sprig of nobility, half-dreaded, half-doated on by the women, hated by the men,—the dry joker, the practical wit, &c.,—from the redoubtable warrior of Waterloo

—the great prime minister of England. He who achieved a greater moral victory than that of Mount St. Jean, when, neutralizing and overcoming political and religious animosities, he set at rest a question that had vexed the world for nearly three centuries.* The Boyne, then, is not here that lovely, picturesque water which it becomes when it sweeps under the wood-crowned banks of Beau-parc, winds under the limestone bluffs of Slane, washes the castle of the Marquis of Conyngham, or meets the tide

“ ‘ At Oldbridge town,
Where was a glorious battle :
When James and William staked a crown,
And cannons they did rattle.’ ”

But there was a battle at Clonard also; unhappily, however, in it both sides were our own countrymen. To the right of Leinster-bridge, on the old road, are the ivy-mantled remains of a massive wall, a porch, and a portion of a turret, all that now exist of the memorable dwelling where the brave yeomen under Lieut. Tyrrell, in 1798, made so gallant a stand against a large force of insurgents, some hundred and fifty of whose bodies are buried beneath a small mound in one of the adjoining fields.† The defence of this little Hougomont was, perhaps, one of the most striking instances of determined courage on the part of the loyalists that has been recorded during the whole of that ill-starred, most unmeaning, and most ill-conceived rebellion. At the time of this engagement,—the 11th of July,—the peasantry who took part in the “rising” had become tolerably well organized and accustomed to arms, and had then unfortunately seen too much blood spilled, so that they did not, at that time, present the unguided rabble mass which they appeared some six weeks earlier, at the commencement of that disastrous campaign. After the defeat at Whiteheaps, a large portion of the insurgents, under Parry, Kearns, Holt, and the two Byrnes, fled into Kildare, and in their progress attacked the little garrison of yeomanry at Clonard, con-

* This description of Clonard appeared originally in the Dublin Penny Journal. See vol. i. p. 150. The sentence immediately preceding the reference to this note was omitted in the published “Tour in Connaught.” Why?

† This little mound, which lies between the Ballybogan road and the river, has never been tilled since, and is now covered with gooseberry bushes.

sisting at the time of but twenty-seven persons, two of whom, sons of Mr. Tyrrell, were mere boys. The place to be defended resembled, in a remarkable manner, that portion of the field of Waterloo to which we have already likened it, consisting of a dwelling-house, then occupied as a barrack, and surrounded by a court-yard and garden, enclosed by a high wall, on one side of which there was a turret commanding the bridge and great western road; in front was the river, on the left a mill-race, and behind it some wooded rising ground. The advance of the besiegers was so rapid that the gate of the court-yard was closed with considerable difficulty. After several hours' hard fighting, during which the slaughter of the rebels was immense, and the courage, both of the besiegers and besieged, severely tested, the garden was lost; and thus the Tyrrell yeomanry became divided. The insurgents then turned their chief attention to the turret, from which they had sustained the hottest fire. The six men whom it contained, thus cut off from their fellows, drew up the ladder and ascended to its top-most story, and fought so determinedly, and fired so effectually, that it is stated twenty-seven of the assailants were killed within and about the ground floor of it during this portion of the contest. The attacking force, finding it impossible to gain access through the floor, at last lighted a quantity of straw within and around the turret, and literally smoked out its occupants. While it was enveloped in smoke and flames, two of the band attempted to rush through the crowd of assailants, but were instantly shot; yet the other four, leaping from one of the upper windows, escaped to their comrades in safety. Still the conflict raged for six hours without intermission; the valour of the handful of determined spirits within the barracks continuing unsubdued, the vengeance of the attacking party remaining unsatiated; till at five o'clock in the evening the siege was raised by the arrival of twenty-one additional men from Kinnegad, when Mr. Tyrrell and his party sallied forth, and drove the insurgents from the garden with great loss. God avert such fearful scenes from being again enacted in our land! and—shall we not add?—forgive the rulers who could, by misgovernment, drive, or the selfish leaders who could seduce, the people into a similar condition!*

* See Sir Richard Musgrave's History of the Irish Rebellion, and the Me-

Within the enclosure of Tyrrell's mansion may be seen a very perfect ancient tumulus.

The name of this celebrated spot, Clonard, or Cluain Ioraird, has been translated by Ware, Vallancey, and other topographers, "the Retirement on the Western Heights:" but this meaning is very questionable, for there are no heights, or even hills, in this locality, to which such could refer. Cluain, which is the general prefix to the names of our churches and bishops' sees, means a lawn, an insulated meadow, or level, fertile plain, surrounded by a bog or marsh; in fact a kind of oasis, as we know is the general appearance of such localities in Ireland; and Ioraird is a proper name: we have examples of this in Cluain Mac Nois, Cluain Coner, Cluain Dolcain, &c.* Clonard was once the most distinguished bishop's see in Meath, perhaps it would not be exaggeration to say in the kingdom; and its cathedral may be conjectured to have been one of the very first erected in Ireland, and was probably coeval with Clonmacnoise, and the original buildings at Armagh. It is well known to have been one of the most distinguished seats of learning of which the Irish historians can boast. Ware informs us that St. Finnian, Finen, or Finbar, who must have been one of the immediate successors of St. Patrick, was created first Bishop of Clonard in 520, "where he also opened a school, which, by his care and industry, produced many men of eminent sanctity and learning, among whom were the two Kierans, the two Brendans, the two Columbs (namely, Columb Kill, and Columb, the son of Crimthan), Laserian,

moirs of Joseph Holt, General of the Irish rebels in 1798, edited by T. Crofton Corker, Esq., 1838, who adds in a note: "The Kinnegad infantry [Tyrrell's corps] received for their conduct, in cutting down the rebels on this occasion, the *soubriquet* of 'the Slashers;' and a lively melody, still popular in Ireland, was named 'The Kinnegad Slashers,' in complimentary commemoration of the achievements of that corps at Clonard." Three celebrated ladies in that neighbourhood were also called "The Kinnegad Slashers." Holt acknowledges that he commanded 3000 men at Clonard, and that number was only a portion of those engaged. The rebel loss was upwards of 150. The leaders at Ballingarry should have studied the history of Irish rebellions more attentively.

* See Petrie's Essay on the Round Towers, and O'Brien's Irish Dictionary. But it is stated by Archdall that the original name of Cluain Ioraird was *Ross-Finnchuill*, "the Wood or Shrubbery of the White Hazel," an appellation which we can readily suppose was highly characteristic of this spot in early times.

the son of Nathfrach, Caineac, Moveus, and Ruadan. And as St. Finian's school was not 'improperly a sacred repository of all wisdom,' as the writer of his life tells us, so he himself got the surname of 'Finian the Wise.'"^{*} To this ancient seat of learning resorted students, not only from all parts of the British isles, but also from Armorica and Germany; so that at one time it is said they numbered about 3000. The venerable Bede, it is said, bears testimony, not only to the instruction delivered at Clonard, but to its fame for hospitality towards the students of the many nations who resorted there; and Colgan, Ussher, Sir James Ware, and the learned Dr. Lanigan, have collected materials, and inserted in their writings the life of this distinguished philosopher and divine, who was also one of the most celebrated commentators on the Holy Scriptures of his age. One of the hymns anciently sung at his festival begins thus:

"Regressus in Clonardiam,
Ad Cathedram Lecturæ,
Apponit diligentiam
Ad studium Scripturæ."†

There is some discrepancy as to the date of his decease, but the best authorities acknowledge that it occurred between the years 548 and 563.

After the establishment of Christianity in Ireland, several bishoprics were created in Meath, namely, Clonard, Damliag or Duleek, Ceananus now Kells, Trim, Ardbracken, Dunshaughlin, Foure, Slane, and others; but in the beginning of the twelfth century, all these, except Duleek and Kells, were united to form the see of Clonard.

It appears from our monastic annals, that St. Kieran the younger, commonly styled the son of the carpenter, the founder of Clonmacnois, and who was born in 506, bestowed the territory of Clonard, which was his patrimony, on St. Finian, whose character and descent is thus recorded by Mac Geoghegan, who has paraphrased Colgan and Ussher: "St. Finian, or Finan, sometimes also called Finbar, son of Fintan, a subtle philosopher, and profound theologian, was first Bishop of Clonard: he was of the noble race of the Clanna Rorys, and his

^{*} Ware's Irish Bishops, p. 136.

† Ware's Writers of Ireland, p. 13.

piety added new lustre to his birth. Having been baptized by St. Abban, he was placed under the guidance of St. Fortkern, Bishop of Trim, where he remained till the age of thirty years, continually profiting by the instructions of this holy bishop. He afterwards went into Britain, and became attached to St. David, Bishop of Menevia in Wales, by whom he was particularly beloved for his piety and learning. He remained thirty years in Britain, where he founded three churches. Having returned to his own country, and being consecrated bishop in 520, he established his see at Clonard, on the river Boyne, in Meath, where he founded a school, or university, celebrated for the great concourse of students, amounting sometimes to 3000, amongst whom were a great number of subjects celebrated for their sanctity and learning.”*

Dr. Lanigan writes,—his parents were Christians, “and sent him towards the Church of Roscor, to be there baptized by Bishop Fortkern. The women who were carrying him were, it is said, met on the way by the priest, St. Abban, who, having inquired whither they were going, and what was their errand, undertook to baptize him, which he did at a place where two rivers unite into one.” From this and other passages bearing a like interpretation, we are inclined to think the early Irish Christians employed *immersion* as their mode of baptism, and some of our very oldest fonts, particularly one still remaining in the churchyard of Tallaght, in the county of Dublin, would appear to have been constructed for that purpose.

At a later period the abbey was dedicated to St. Peter, but what the original buildings were we can now but conjecture, probably a missionary chapel, a few monastic cells, and a cloitheach, or round tower. There was also a derthech, or penitentiary, the burning of which, in the eleventh century, has been recorded. We have constantly wondered that no trace of a round tower had been discovered in this sacred spot; but we learn from the Annals of Clonmacnoise and the Four Masters, that the cloitheach, or steeple of Cluain Ioraird, fell to the ground in the year 1039. Archdall understands this to be the steeple of the church, and so indeed it was, though a separate building from it. For upwards of a thousand years the annals of Clonard have come down to us;

* Mac Geoghegan's History of Ireland, vol. i. p. 402.

and, although scattered through various works, they are now well known, and the majority of them have been collected with great industry by Archdall, in his *Monasticon Hibernicum*, in which work he also relates the nobleness of birth, distinguished philosophy, and eminent piety and learning of the founder. The library was burned in the year 1143. Is it too great a stretch of the imagination to suppose that that very copy of the psalms, in the handwriting of St. Columbkille, contained in the splendid silver shrine called the *Cathach* of the O'Donnells, now in the Museum of the Royal Irish Academy, was written in this very library? So early as 665, we read of regular professorships having existed there. Besides those who resorted thither as students, it seems that several pious laymen retired to this secluded spot, to spend the remainder of their days in contemplation and repose. From this sanctuary and abode of wisdom, undoubtedly, sprang much of the learning both of Britain and the continent. The far-famed Iona, from whence arose

“ That fire which lit creation in her youth,
That turned the wandering savage into man,
And showed him the omnipotence of truth,”

derived its religion and its architecture from Clonard.*

Numerous disasters befell this place. It was pillaged and in part destroyed no less than twelve times, on five of these occasions by the Danes. The church and adjoining buildings were fourteen times consumed by fire; indeed, this destructive element appears to have marked these structures for its particular fury, for we read that, in 1045, “ the town of Clonard, together with its churches, was wholly consumed, being thrice set on fire within one week.” In 1136, “ the inhabitants of the Breney (Brefney) plundered and sacked Clonard, and behaved in so shameless a manner, as to strip O'Daly, then chief poet of

* In that most meagre and incorrect historical account of Iona, by Mr. Maclean,—the only guide-book, we are sorry to say, with which travellers visiting that sacred isle are furnished,—he has the ignorance and bad taste to say: “ In the year 563, one Colum M'Felim M'Fergus, latinized Columba, a *Scotsman*, set out from Ireland in a currah, and landed at Kebudæ,” &c. Now, the birth-place and parentage of St. Colum are both well known, and are mentioned in all the lives of this saint; nay, the very passage in Adamnanus, to which he refers, is quoted incorrectly; but we need not wonder at this in an author who embellishes his title-page with a veritable *Gaelic* quotation from Ossian!

Ireland, even to his skin, and leave him in that situation; and amongst other outrages, they sacrilegiously took from the vestry of this abbey a sword, which had belonged to St. Finian, the founder." It was sacked and plundered by Dermot Mac Murrough, and his English allies, in 1170. The English settlers appear, however, subsequently to have located themselves in the town of Clonard, which must then have been considerable, and they are even mentioned as having rebuilt some of the edifices. Besides the abbey of Regular Canons, there was also a nunnery, endowed by O'Melaghlin,* to which, in after times, immense revenues and very extensive lands were attached.

In 1206, Simon Rochford, an Englishman,—for English ecclesiastics ruled in Ireland then, as well as now,—who assumed the title of Bishop of Meath, removed the episcopal chair from Clonard to Newtown, near Trim, where he founded the celebrated abbey of Augustinian Monks. Clonard is frequently mentioned in the Annals of the Four Masters, and all the ecclesiastical histories of Ireland, and some of the most distinguished Irish prelates are said to have been buried there.† There was also a castle at Clonard, erected by Hugh de Lacy, but, unless Ticroghan be the spot, even its foundations have long since been obliterated.

Amongst the legendary lore attached to this abbey, is a tale of Columba, the son of Crimthan, having been seen late one night in his cell, when his lamp had expired, reading the sacred volume by a light which emanated from the tips of his fingers, as he passed them over the leaves before him.

At the beginning of this century, and indeed till a very modern date, the ruins of some of the many buildings which once adorned this memorable locality were in existence. Archdall thus describes them: "The entrance into this abbey, on the west side, was through a small building, with a lodge

* This name, which is written in half-a-dozen ways by the Irish, Latin, and English annalists, means Mael-Sechnal, the attendant or servant of Sechnal, the patron saint of Meath.

† We would direct the attention of any of our Irish antiquaries who may be travelling in the Highlands of Scotland to the churchyard of St. Finian, at Otter, in which will be found some exceedingly curious and highly sculptured tomb-stones, the workmanship of which is evidently of Irish origin.

over it, which led into a small court ; to the right of this court stands the kitchen and cellar, and over them the dormitory, ranging with the river, and overlooking the garden, which sloped from thence to the water's edge ; opposite the entrance was another small apartment, and adjoining it, the refectory, which was carried for some length beyond the square, and joined the choir, a large and elegant building, most part of which still remains, and the windows are finished in a light Gothic style. On the south side of the altar, fixed in the wall, is a small double arch, in the old Saxon manner, and divided by a pillar through which iron bars were fixed. This is supposed to have been the founder's tomb. There are many remains of walls adjoining the other parts of the abbey, but in so ruinous a state that little information can be gleaned from them. At a little distance from the east window, in the burial ground, stands a small chapel, in which is a table monument, ornamented with the effigies of a man and a woman, in a praying posture, and dressed in the ruff of Queen Elizabeth's time ; the sides are adorned with many coats of arms,—that of the family of Dillon is most conspicuous.”*

We have thus described Clonard from whatever research we have been able to devote to the subject ; but of all the magnificence of all these buildings not even a trace now remains. It is with difficulty their former situation can be made out. The Christians have, after numberless burnings, sackings, and plunderings, for upwards of a thousand years, at last succeeded in completely obliterating every vestige of these Christian edifices, the tombs and temples of their ancestors, while some pagan remains, erected centuries before the introduction of Christianity into Ireland, attract our attention from the Boyne's banks, and point out the locality sought for. Here, upon the Trim road, the village of Clonard stands, and in connexion with it the modern church and graveyard. This latter, and the fields adjoining, were the site of the ecclesiastical remains, but it would appear from the ancient references that the monastical and scholastic buildings extended down towards the western bank of the river for some distance. Three stones are all that can at present be discovered of the vast range

* Archdall's *Monasticon* ; also Gough's additions to Camden, and Seward's *Topography*, &c., &c.

of buildings, and the numerous decorations and ornaments which so lately existed here. One of these is a head, probably a fragment of a corbel or bracket, inserted into the wall of the present church tower, over the door. The second is a baptismal font, that figured in the annexed cut, which was probably too heavy to be carried away, or useless in the erection of the modern ugly structure adjacent, and too massive to



be broken with facility. It is still preserved, and has been placed in the parochial church. It is one of the finest, and perhaps, of its kind, one of the oldest in Ireland, and, being of very hard, compact, grey limestone, or marble, it is still in most wonderful preservation. It is three feet high, and stands on a square pedestal, the upper portion of which is highly ornamented with floral decorations, in eight compartments, and divided by a moulding from the basin, which is formed out of a separate stone, the lower part of which corresponds in the number of its sides with the upper part of the shaft; but four of the panels contain figures of angels, the remaining ones being filled with the representations of trees or shrubs. The basin is octagonal in shape, two feet one inch in diameter, and highly

sculptured externally, with figures in relief, representing the Flight into Egypt, the Baptism in the Jordan, St. Finian, St. Peter, and various grotesque figures of monks of the Augustinian order; which latter show that it was carved since the days of Walter De Lacy, on the rebuilding of the monastery in 1175. The principal figure in the foregoing engraving, that of a bishop with a crozier, is supposed to be that of the founder, St. Finian. As may be seen by referring to the cut, some of the panels are divided per pale, and each small compartment contains a figure. The carvings on this curious relic are well worthy of inspection, and are a rude pictorial representation of scriptural and Irish monastic history and hagiology. The bowl of this font is very deep, and measures about twenty inches across, a sufficient size to permit of immersion, which, it is more than probable, was the form of baptism employed by the early Irish Church. There is an aperture in the bottom of it.

The third stone to which we alluded is a square trough, probably the lavatory of the ancient monastery. It is rude and undecorated, with a cavity two feet two inches long, by twenty-one inches wide, and about fifteen inches in depth. It remained, until we had it taken up, very lately, almost completely buried in the grave-yard, near the present church tower. Like several other hallowed stones, such as piscinas, bolt-holes, and steps or bases of crosses, which are met with on the sites of many of our old churches and religious houses, peculiar superstitious reverence attached to this ancient washing basin as long as it remained over ground. Like the "Deer-stone" at Glendalough, it was said to have contained water at all times, and to this water peculiar properties were attributed by the peasantry; it was believed to cause the illness and death of geese and all animals which drank it, and it was sought for as an infallible remedy—one of the hundred infallible cures—for warts.*

At what precise period during the present century those time-honoured ruins at Clonard were completely effaced, or to what base uses they were applied, it is now difficult to say. The chief dilapidation certainly occurred within the last five-and-twenty years. Ruins such as these are the landmarks of

* See the Author's articles on Irish popular superstitions, in the Dublin University Magazine, already referred to, and in the London and Edinburgh Monthly Medical Journal for June, 1849.

our history, transmitted to us through "ages of sorrow and shame," from a brighter and more glorious era, and are fully as interesting and as valuable to the Irish people as the stately edifices of Westminster or St. Paul's are to the English. Whatever government, political or ecclesiastical, rules this country, should be taught, by the voice of public opinion, to preserve our architectural remains and antiquities; and neither vestry clerk, parish bumpkin, itinerant architect, nor titled commissioner, should be permitted to remove one stone of those sacred piles, which are not the property, and do not belong to this parish or that proprietor, but appertain by right to the country at large.

We had a lamentable instance of the desecration of monuments, the dilapidation of ancient structures, and the complete obliteration of the records of several well-marked historic eras, in the spoliation of the church of Lusk, not far from this city, a few years ago; and not many months past a similar attempt was made to destroy the monuments in the old church of St. Audoen's, in Dublin. Where will paternal love, or filial piety, the adoration of a husband, the mourning of a friend, or the grateful homage of a country, erect the tomb or carve the tablet, to the memory of the hallowed, though not forgotten dead, if such memorials are, within the lapse of a few years, by the vote of a vestry, or the dictate of a commission, to be hurled from their niches, broken, scattered through the surrounding grave-yard, or turned into sharpening-stones by the masons and artisans employed in erecting modern ungainly buildings, in the construction of which the materials of a church some five or six centuries old are often "thrown into" the contractor's agreement?

But, above all, the people themselves should be taught to reverence and respect these remains, and not (as we have frequently observed), destroy them, by removing some of their beautifully carved stones to form lintels and cornices for their wretched cabins, the surrounding filth and misery of which contrast but too mournfully with the relics of ancient grandeur in their vicinity.

Among the remnants of ecclesiastical remains belonging to the cathedral of Clonard, which have been discovered or preserved, one unique object of interest deserves our especial notice. The Kinnegad river winds by this spot, and in some

improvements lately made for the purpose of deepening the bed of that stream, a nest of curious antiquities was discovered. They consisted of a bucket, composed of small oaken staves, in which were packed some thin brazen culinary vessels; one of those long brass Dutch boxes, well known to the curious in such matters, containing some silver coins of the reign of Elizabeth; some of the "brass money" of James II., and several copper coins of the reign of William and Mary, dated as late as 1694, which latter serve to mark the time of the interment of these relics. But the object of most interest is a small bucket or Stoup, of oak, about six inches high, and beautifully hooped or bound with a thin filagree of brass; the handle, which is also brass, is affixed by loops and clasps, which contained precious stones, and were decorated in the form of some of those carvings, so characteristic of early Irish art, both in the engraving and adorning of ornaments, and the embellishment and illumination of manuscripts. It is altogether an exceedingly light, chaste, and elegant fabric, and was, in all probability, used in the service of the cathedral, perhaps for carrying round the holy water.* Utensils of this kind, both household and ecclesiastical, are alluded to in the Brehon laws. Were we to offer a conjecture, we would say that after the battle of the Boyne, when Dutch boxes were common in Ireland, these relics were removed from the Abbey, and hidden, or dropped by accident, in the locality where they were found.



* See a picture, by Shoreel, in 1520, in Shaw's *Dresses and Decorations of the Middle Ages*, vol. ii., given in the *Glossary of Gothic Architecture*. This interesting relic figured above belongs to Dr. Barker, of Gardiner's-row, in this city, in the vicinity of whose family estate it was found, and to whom we are indebted for permission to publish the accompanying engraving. With laudable zeal he has deposited it, with the other objects of interest found in the same locality, in the great national collection of the Academy, where the public have an opportunity of seeing them, and where they are carefully preserved. The public generally, and even our fellow-citizens, do not seem to appreciate this noble collection, where, besides the articles intrinsically the property of the Academy, several interesting family relics have been deposited for safety and the purposes of exhibition.

We now turn to those Pagan remains which already attracted our attention, and to which we lately directed our steps from the Boyne's banks. About half a mile beyond the bridge of Clonard, near the church, and consequently on the left bank of the river, rises one of the most picturesque green moats of the many that border this noble stream. On its summit a most picturesque ash flourishes in great luxuriance. That tree has a particular charm for us; we remember it some fifteen years ago, when its commanding position attracted our attention, as we first wended our way from the far west towards Alma Mater; and season after season as we passed it, returning to the home of friends, and the glens and mountains in the sterner and more romantic, but less historic lands washed by the wide Atlantic, we watched the growth of its graceful, wide-spreading boughs with no common interest.



This large tumulus, the great bulk of which is probably formed of small stones, but the surface of which is now a verdant greensward, rises in steps caused by the gradual slipping of the alluvial soil. In circumference it measures 433 feet round the base, and at the top, which is flat and truncated, 168 feet. Its perpendicular height is upwards of fifty feet. Some excavations were made both at top and bottom upon its northern aspect, by treasure-seekers, some years ago.

Circular mounds of this description are of two kinds, mili-

tary and sepulchral, and it is often difficult, without an examination of the interior, to distinguish to which class some of them belong; but this point we shall discuss as we advance among the larger and more numerous collection of these monuments on the lower Boyne. This at Clonard appears to be a barrow, or tumulus, and probably covers a stone chamber, or a cromlech, containing the remains of some distinguished Irish chieftain. In numberless instances we find architectural remains of more recent date, and coming within the historic period, occurring in the immediate neighbourhood of these mounds; and not far from this moat once stood the celebrated school, abbey, and cathedral, which we have already described. It would appear that the odour of sanctity still lingered round the spot hallowed by the dust of the noble dead, or commemorated by the battle-field of heroic times, and that on the national acceptance of a new religion and another system of Government, of policy, or warfare, Christian edifices, civil and ecclesiastical, arose round their Pagan predecessors.

Independent of this great mound beside the town of old Clonard, the entire of the vicinity is studded over with mounds, forts, and raths, of various shapes and sizes; there is one, however, in particular, a short distance to the north-west of the great tumulus, to which we would especially direct the attention of the tourist, on account of its importance, and the peculiarity of its structure, as distinguished from the sepulchral mounds in its neighbourhood. This rath or dun, which is evidently one of the military class, formed an ancient fort or encampment, and was capable of containing as many as 200 men; it consists of an external fosse, encircling a raised ditch, or circular earthen wall, within which we find a level platform, elevated somewhat above the surrounding plain, but not so high as the earthen circle which encloses it. A broad entrance, through which a modern carriage might enter, exists upon its eastern side.

In some instances there is a double wall of circumvallation; and cases might be enumerated, in which sepulchral mounds, cromlechs, and tumuli, exist in the centre of these military enclosures. Several of these ancient forts contain a central subterranean chamber, and circular passages, in all probability for the purposes of security, and to serve as granaries; and beside the rude weapons and ornaments occasionally discovered in their

vicinity, quantities of animal remains, particularly of goats and oxen, have been found within and around these enclosures.

Between this ancient camp and the great mound, in the low ground through which the Kinnegad or Blind River flows, have been dug up, from time to time, numerous Irish antiquities, brazen celts, spears, fibulæ, and also quantities of charcoal, slag, and such material as would indicate the previous existence of some foundry or smelting establishment. But looking down from the tumulus upon the surrounding flat country, and examining the situation and appearance of this great rath, we are strongly inclined to believe that the ancient name of the place is derived from it. It fully answers the meaning of the term Cluain, an insulated meadow, a sort of oasis rising out of a bog or morass, and, as we already remarked, bore the name of a man, probably some early Irish warrior;—is it too speculative to suppose that of the person buried in the great sepulchral moat, figured at page 68? Sometimes these raths or cashels are formed of stone, and in some rare instances they enclose Christian churches and monastic remains; but, besides the difference in material and contents, these circumstances in no wise prove their Christian origin, for it is acknowledged that Christian edifices have been erected, within these enclosures, within the historic era.

There has long existed an opinion among the reading and middle classes in this country, that these raths are of Danish origin; but, though still described as such by some of the peasantry, no person of any antiquarian knowledge now believes them to be any other than Pagan structures, erected by the Firbolg, Tuatha De Danaan, Scotie, or Milesian population, and constructed long prior to the first Danish invasion of Ireland. Conversing with an old man at Bective lately, we asked his opinion of these remains: "Ough," says he, "sure it's well known they were med by the Danes, who, when they were nearly bet all out, and grown mighty wake entirely in the counthry, lived under ground in thim same forths."

Besides the very general belief that exists even among the upper classes of society—an opinion, by the way, chiefly ascribable to the writings of Sir Thomas Molyneux—of the Danish origin of these raths, a certain degree of superstitious reverence attaches to them in the minds of the peasantry, by whom they are often styled "fairy raths" and fairy circles, and are believed

to be now inhabited by, if not originally the handiwork of the "gentry" or "good people," whose music is said to be often heard within their enchanted precincts, in the calm summer evenings; and this superstition is strong against their Danish origin.* Although by no means inclined to foster these rude and early prejudices of our people, still we respect them, inasmuch as they have for centuries thrown a magic spell around these enchanted halls, which few were hardy enough to attempt to break. Until very lately, scarcely a peasant in the land would put his spade into one of these mounds or circles; and we have known blood spilled in attempting to force the people to demolish an ancient rath. Sometimes this spoliation arises from ignorance, or want of patriotism, in our farmers and gentry, but often from mere curiosity, or in order to manure or level the land, and frequently, to our own knowledge, for the mere purpose of "breaking down prejudices," and showing the people that no ill-luck or misfortune could possibly occur from their destruction. So much for the veneration for our national monuments; so much for the reverence for the dust of our ancestors! It does not bespeak either education, taste, or patriotism, thus wantonly to obliterate these footprints of our early history.

While we speculate upon the construction, the uses, and the

* Giraldu Cambrensis calls some of them Danish; but, after the publication of Sir T. Molyneux's Discourse on "Danish Mounts, Forts, and Towers," this idea was chiefly propagated by Hugh Boy M'Curtin, whose dissertation was widely circulated among the native Irish.

In no place in the Irish histories do we read of the remains at Tara, Emania, Tailte, or Croghan, &c., being attributed to the Danes, or called Danes' forts. In the autograph letter of Thady O'Roddy, published in the Irish Archaeological Society's Miscellany, p. 124, we have the following common sense view of the case, written by an intelligent Irish antiquary in 1517:

"For the Carnes, or heaps of stones, in several parts of Ireland, some of them were heaped as monuments in memory of battles fought in such a place, some made in memory of some eminent persons buried in such a place, some of them layed over some corps, as the Romans did: *Aggere cinctus*.

"For the forts called the Danes forts, its a mere vulgar error. For these forts (called Rathes) were entrenchments made by the Irish about their houses. For we never had any stone worke in Ireland till after St. Patricke's coming, a° Christi 432, the 5th yeare of the reign of Laogary Mac Neill. And then we began to build churches, &c., of stone. So that all our kings, gentry, &c., had such raths or forts about their houses, witnes Tara forts, where the kings of Ireland lived, Rathcroghan in Connaught, etc."

By "stone worke," Dr. Todd, the learned editor of this Tract, very justly remarks in a note, that the author must mean that "we had no buildings of

historic era of these raths, duns, lises, or ancient fortresses and encampments, which have given names to so many places in Ireland, we must carry the mind back to a very early period in the colonization of this island, when a great portion of the country was thick wood and impassable morass; when the population did not exceed, if indeed it even amounted to two millions; when the warfare of the country consisted in the desultory incursions of some neighbouring chief; and the weapons of the belligerents were flint arrows, sling-stones, and stone and bronze hatchets and celts, with, in a little later period, short brazen swords, like those found on the field of Cannæ. We should then, in all probability, have found a half-civilized tribe or clan, or portion of a clan, intrenched within one of these raths,—which was further strengthened by a strong wooden palisade, erected on the outer embankment,—with their flocks grazing on the neighbouring plain, and their habitations constructed of timber, within the circle of the great enclosure.

As several other military forts, and one in particular, the great ring fort on the lands of Dowth, will claim our attention as we descend towards the sea, we shall refer to these structures in another locality.

It is very remarkable, as we already observed, how frequently we find some of the earliest Christian remains in the vicinity of Pagan mounds, tumuli, and other similar ancient structures, as if the feeling of veneration remained round the spot; and, though the grove of the Druid was replaced by the cashel of the Christian, still the place continued to be respected, and the followers of the early missionaries raised their churches and laid their bones in those localities hallowed by the dust or renowned by the prowess of their ancestors. Until within the last three centuries, which may be styled the dark ages of Ireland, each succeeding generation appeared to vie with its predecessor in the elegance and the beauty of its architecture. The pillar-stone, enlarged and decorated, grew into the sculptured cross; the hermit's cell became the cloistered monastery; the small belfry within the rude cashel

stone cemented with lime and sand mortar before the introduction of Christianity; for the Cahers or Cyclopean stone forts, built without cement, are as old as any of the earthen raths."

rose into the stately tower; the simple missionary church of early times grew into the florid cathedral; and individuals, as well as nations, strove to show their piety in the religious edifices which they erected, and their patriotism and ancestral veneration in the tombs and monuments which they adorned. These holy feelings continued alive and warm in the breasts of the nobles, churchmen, and chieftains of Ireland, even through ages of wild misrule; in the days of foreign invasion, when the plundering Northmen pillaged, burned, and destroyed, and a conquering neighbour fomented civil disagreements and domestic strife; when might, not right, was law; when the soldier's stalwart arm, and the churchman's moral power,—the bannered or the mitred tyrant,—swayed in turn the destinies of our people; before peace, with its accompaniments of security, wealth, and commerce, flourished in the land; e'er national schools offered education to the peasantry,—centuries antecedent to the creation of Art Unions and national Architectural Institutes, and long prior to the date of modern commissions,—church architecture obtained an eminence in Ireland which it has never since equalled. These reflections were forcibly impressed upon us in some of our excursions along the Boyne, where, beside the ruin of some light and elegant early church, with its leaning door-posts, its round chancel arch, and triangular-headed windows, its carved imposts, and sculptured piscinæ, and all those details which, though simple and inexpensive, preserve the rules of taste and architecture, we find some ugly, inarchitectural, modern, white-washed or yellow-washed structure, with its sentry-box for a belfry, and cold, damp, unpainted interior, erected at an expense far exceeding that which the construction of a building, similar to the original, would have cost. The church at Clonard affords a lamentable instance of our position. We neither belong to the schools of Rome nor Oxford, but we do hope to see the day when an Irish parish church, for a congregation of some fifty persons, will be constructed on the model of some of the early churches, the creed of the occupants of which was, perhaps, as pure and as free from the middle age corruptions as that now believed by the portion of the population professing the reformed faith.

A new era has taken place in the vicinity of this memorable locality, an event which the wildest visionary of that far-famed school of philosophy, who sauntered along "The Boyne

of Science," could not by any possibility have even speculated upon. An aqueduct carries the Royal Canal over the stream a short distance below this; and at the same point the river is crossed by the Midland Great Western Railway, by which our readers, instead of being, as of old, tugged along in a dirty tub through a muddy ditch, at a rate little exceeding two miles and a half an hour, can spin over the Boyne with comfort and security at a rate of twenty miles an hour at least.

In the cuttings that were made along the banks of the canal, between Enfield and Clonard, for the progress of the railway, a most interesting battle-field was opened at Rathcore, in the townland of Newcastle, county of Meath, and such a quantity of human bones exposed, that the entire bank was literally white with them. They were found in every possible position, but had evidently been thrown into a large pit, without order, and not surrounded by any form of sepulchral monument. The most superficial part of this ossific stratum was scarcely two feet beneath the surface: and along with these bones were found some iron spear-heads, hatchets, and other weapons, which incline us to believe that these remains may be those of the gallowglasses, or heavy Irish soldiery employed in this country from the tenth to the end of the fifteenth century. Such, however, may be the speculations which men will yet form when similar exhumations occur on the fields of Cressy, Poitiers, or Agincourt, or, in a few centuries to come, perhaps even Waterloo. Some of these weapons have been placed in the national collection of the Academy.

The Annals of the Four Masters have afforded us the following references to this locality:

"A.D.799.—Hugh Oirnidhe (monarch of Ireland) collected a large army, and marched into Leinster; and he devastated Leinster twice in one month. He again raised the whole of the men of Ireland, except those of Leinster, both lay and clerical, and marched to Dun-Cuair, on the confines of Meath and Leinster; Connmach, the Coarb of Patrick, accompanied by the clergy of the northern, or Conn's half of Ireland. The clergy were displeased at being called on expeditions at all. They complained of their grievance to the King; and the King, Hugh, said that he would abide by the decision of Fothadh-na-Canoine [Fathadh of the Canon] in the matter. And it was on that occasion that he [Fathadh] gave the judgment

which relieved or exempted the clergy from expeditions or hostings ever after." Dun-Cuair is the same as Rath-Cuair, the modern Rath-Core.

"A. D. 800.—Hugh Oirdnidhe went to Cuar, and divided Leinster between the two Muireadhachs, viz., Muireadhach, son of Ruadhrach, and Muireadhach, son of Brian."

"A. D. 815.—Hugh Oirdnidhe, King of Ireland, went out with a great army to Dun Cuar again, and divided Leinster between the two grandsons of Bran."

There is in this locality a remarkable winding of the river, styled in ancient writings "the sweep of the Boyne," where it spreads out into a considerable expanse, and the spot is memorable in Irish history. In the year 765, the seventh of Niall, the Annals of the Four Masters, in recording the various battles which took place in the east of Ireland, give us an account of "the battle of Bolg-Boinne" (the belly of the Boyne), "against the men of south Breagh," in which certain Irish chieftains were slain. The hostile belligerents appear to have been the Leinstermen.

About a mile beyond the bridge of Clonard, towards the west, we find the ruins of the old fortress of Ticroghan, or Queen Mary's Castle, as it is sometimes styled; it can be seen from the Ballybogan road, upon the left bank of the river, and may be visited in that route. We cannot, however, stop to record the annals of every feudal or monastic pile that attracts our attention in this passage down the Boyne; but we may here remark, that Lord Ormonde retired to this castle from Trim, in 1649, shortly before the siege of Drogheda, and that, "after a well-regulated defence," it was surrendered by Lady Fitzgarret, in 1650, to Colonel Reynolds and Colonel Huetson.* In its vicinity some remains of the walls of an ancient church and a burial ground, which formerly contained an antique font, also exist; but even within our own memory portions of the walls of the castle have been torn down to supply building materials. De Lacy built a castle at Clonard, but, if this was not it, we cannot find any trace of it.

* The peasants in the neighbourhood relate a story that the siege was about to be abandoned when the besiegers discovered that the soldiers in the fortress were firing silver bullets; encouraged by this proof of the extremity in which the beleaguered were, the Parliamentary forces continued the attack with renewed energy, and soon succeeded in reducing the castle.

We now commence the second great division of the Boyne, extending from Clonard to Navan. In the first portion of this division, from Clonard to Trim, a distance of about ten miles, the characteristics of the river vary little from those which we have described; slow, deep, and tortuous, it winds on its placid course, through deep, alluvial meadows, to the bridge of Stonyford, over which the road from Mullingar to Trim crosses to the southern bank. For the next four miles of its course there is little to attract attention; the banks are low, and the country exceedingly flat, and liable to yearly inundations from the overflow of the river, several of which have been recorded by the Annalists. This stream has not been made any use of, either for the improvement of the country or commercial purposes. There is scarcely one boat upon it for many miles of its course, and the only fish it affords here are pike, perch, and eels. The fish of the Boyne have been celebrated in ancient story; but these were, we have reason to believe, salmon, which now at least are seldom caught so high up. On the original proposal of making a canal along the Boyne, it was intended to have rendered the river navigable as far as Clonard, but the canal never was completed further than Navan, although it remains half finished as far as Trim. A river of such magnitude, and with such facilities, running from the very heart of the kingdom, and through the granary of the island, to a good sea-port, and remaining, for such a length of time, in the upper portion of its course, nearly as when the first migrations of the human family passed up it, certainly speaks badly either for the government of the country or for the native enterprise or industry of the people: perhaps both are to blame. The bed of the river is being now deepened, and some interesting relics have been discovered in it; among the rest, a most beautiful and most perfect gallows-glass axe, the finest of the kind ever found; it is in the Museum of the Royal Irish Academy.

In the demesne of Killyon, on the northern bank of the river, about midway between Clonard and Trim, are the ruins of an old church and friary, originally founded by St. Liadhan or Liedania, the mother of St. Kieran of Saighir, who is still the patroness of this parish. From some of the Inquisitions and Burke's *Hibernia Dominicana* we learn that the Dominican monks of Trim retired to the Friary of Donore, as it is

sometimes called. The two walls which now remain are picturesquely situated on a sloping ground, surrounded by some patriarchal ash trees; and nearly opposite these, on the southern bank, at Lion's Den, in the townland of Castle Ricard, we find the crumbling walls of an old battlemented house. Two very perfect tumuli, one near the church of Castle Ricard, also occur in this locality.

Below the friary, on the northern bank, the square border castle of Donore, here represented, forms a conspicuous object,



as its ruins are in better preservation than most of the other castles of the Pale, particularly those on the northern side of the river. We have not been able to collect any accurate information with reference to this building, which does not appear to be older than the fifteenth century. It was probably built by some of the Anglo-Norman soldiers, who spread themselves over the fertile valley of the Boyne for two or three centuries after the English invasion. There are several Donores, both in Meath, Westmeath, and Kildare; and two of these—McGeoghegan's castle, in Westmeath, and Donore Hill, from whence James beheld his defeat at the Boyne—are memorable localities.

The next bridge we meet is that of Inchmore, near which the Kildare Blackwater empties itself, and beyond it that of Scariff, below which latter the river is broken into a great number of islands, and intersected by weirs. The road approaches to within a few yards of the stream at this

point; and here the true sylvan beauty of the Boyne commences, a circumstance of which the neighbouring proprietors seem to be aware, for now every mansion, lodge, or cottage, seems proud of its locality, and we find the elevated, sloping, wooded banks here, studded with Boyne views, Boyne banks, and Boyne lodges, one of the latter of which is located at the next bridge we meet with, Derrinydaly. The country through which the river passes to this point is light in soil, very thinly populated, and chiefly used as meadow or pasture land, a circumstance owing partly to the yearly inundations. Below Derrinydaly the stream passes the demesnes of Newhaggard and Trimblestown, still preserving the same tortuous course, slow in progress, and constantly broken into islands, some of which are planted with considerable taste. On the right bank of the river, in a bold sweep, with which it encloses the ground of Roristown and Newhaggard, we find a large oval military fort, with a small souterrain in its western face; and a similar description of fort may be observed about a mile from the Boyne, on its northern side, near the coach road from Trim to Athboy.

The castle and chapel of Trimblestown, the residence of the Barnewall family, and which gives title to the present baron, are about a mile from the Boyne, in a direct line. Trimblestown castle was fortified during the war of 1641, and for the ten following years. General Jones attacked it in 1647, when it surrendered to the Parliamentary forces. This is the first demesne of any magnitude, and the first noble residence, which we meet with on the Boyne's bank; and we regret to say, that it is too true a picture, and too well-marked a type of many similar residences in the country, forsaken and neglected, a perfect ruin, yet still imposing even in its decay; its high embattled walls and massive towers, which formerly rose above the surrounding woods, exhibit one of the finest specimens of domestic architecture of the fifteenth century in the kingdom. The family cemetery, in the small ruined chapel in the neighbourhood, is worthy of inspection.*

* For some notices of the late Lord Trimblestown see *Memoirs of Richard Lovell Edgeworth*. A drawing of Trimblestown Castle, by Petrie, forms the frontispiece to the second volume of the "*Excursions through Ireland*."

CHAPTER IV.

TRIM.

TRIM; FIRST IMPRESSIONS; HISTORY, ANCIENT AND MODERN; ACCOMMODATION; ORIGIN AND FOUNDATION.—ST. MARY'S ABBEY AND YELLOW TOWER.—GEOFFREY DE GENEVILLE.—MILITARY BUILDINGS.—THE EARLY IRISH CASTLES.—THE SAXON, WHO?—DEATH OF HUGH DE LACY.—THE PRESENT CASTLE OF TRIM; ITS CHAPEL AND MINT.—TALBOT'S CASTLE.—THE EARLY RESIDENCE OF THE DUKE OF WELLINGTON.—LALACOB, SWIFT, AND STELLA.—NEWTOWN; ITS ABBEY, TOMBS, AND RUINS.—MONASTIC CASTLE AND PRIORY OF ST. JOHN.

WE now approach Trim from the west, but the views of its ruined towers, its steeples, and its abbeys, are, from this side, far inferior to those gained on every other approach. To see Trim aright the tourist must approach it by the Blackbull road from Dublin, when all the glorious ruins which crowd this historic locality, and which extend over a space of above a mile, burst suddenly upon him: the remains of St. John's Friary and castellated buildings at the bridge of Newtown; the stately abbey of St. Peter and St. Paul a little further on, raising aloft its tall, light, and ivy-mantled windows, the neighbouring chapel, with its sculptured tombs and monumental tablets; the broad green lawns, through which the Boyne winds, between that and Trim; the silver stream itself, gliding smoothly onward with unbroken surface; the grey massive towers of King John's castle, with its outward walls and barbican, the gates, and towers, and bastions, the fosse, and moat, and chapel; the Sheep-gate and portions of the town-wall; and, towering above all, the tall, commanding form of the Yellow Steeple, which seems the guardian genius of the surrounding ruins. All these beauteous objects, with the ancient church tower, the town itself, the Wellington testimonial, and the modern public buildings, form a combination of scenery and an architectural diorama such as we have rarely witnessed. We have also this additional charm in the views of Trim, that, look at this place as we may, its noble ruins are ever forming new combinations, fresh groups of beauty and of interest, singly or collectively: in all the varying aspects caused by atmospheric changes; in glaring sunshine playing upon their massive walls; with the heavens overcast, and the drifting shower half revealing some of their turrets and gables;

with the calm subdued light of evening softening every object in the landscape; or the silver moontide throwing into shadow every dark recess and deep cathedral niche; with the stream that winds among them now burnished as a golden mirror, now dark and gloomy, with scarce light upon it to reflect the ruins that are usually mirrored in its calm waters. In each and all of these we have ever found new sources of admiration, new themes for the painter's art, the poet's feeling:

—————" Here you stand,
Adore and worship when you know it not;
Pious beyond the intention of your thought,
Devout above the meaning of your will."

Among the other beauties of the ruins of Trim are the tableaux which each group form when seen from one of the others; thus appear the castle and the Yellow Steeple with the town of Trim, when framed in the beautiful Gothic window of Newtown Abbey; thus may Newtown or the Yellow Steeple be seen from the interior of the castle; and other views of a like character, and formed in a similar manner by some surrounding arch or window, might be cited.

But we rave of scenes that we have admired, instead of conducting our readers through the town of Trim, and over these ruins in detail. Well, then,—of all the modern towns in Ireland, of our acquaintance, we know few to vie with Trim in dirt, laziness, and apathy; and of all the ruins in the country, we cannot call to mind any more carefully kept or better preserved from decay than these. This preservation of the ruins of Trim is chiefly to be ascribed to the energy and zeal of Dean Butler, the vicar, who has taken immense pains not only to collect a great body of information on the subject of Trim, but also to bring to light and preserve many of its antiquities. The Dean possesses a fine collection of coins, found among these ruins, and has printed and published some notices of the castle and church at Trim, collected from various authorities. These little publications, which, we confess, we would rather have seen in a less dry and more popular form, contain, we believe, the greatest amount of information, in the fewest possible words, of any works we ever read. They are chiefly composed of annals, collected from various ancient records, and arranged in a chronological form, extending—the

ecclesiastical notices from 433 to the present century, and the military from 1128 to 1689. We have availed ourselves largely of these researches in the present notice, particularly in the description of the military remains of Trim.

It would seem as if the modern inhabitants—perhaps degenerated by the causes which have ever acted in demoralizing small corporations, and owing in part to the unfortunate circumstances of a plurality of landlords, or wanting the stimulus of the warder's bugle, and the exciting scenes when De Lacy's lancers and mailed warriors careered through their narrow streets, when the standard of royalty proudly waved from the tall towers of their castle, and the mitred abbot and stole-girt priest, with all the gorgeous paraphernalia of the Church, paraded their dull town—have sunk down into apathy and listless indifference. According to the last Census, the population of Trim amounted to 2269 persons, 1124 males, and 1145 females. It has the honour of being the county town, and possesses a gaol, a fever hospital, a poor-house, barrack, court-house, and a school under the Incorporated Society endowed by Richard first Baron Mornington; and it has been ornamented with a testimonial pillar, erected by the gentry of Meath to the honour of the Hero of Waterloo, who spent some of his early days at Dangan, in this neighbourhood, and who represented this borough the first time he sat in Parliament.

We cannot say much for the accommodation of Trim; but we are bound to acknowledge every possible desire to afford comfort and civility. A little more care, and a little more cleanliness, added to the civility which it at present affords, would make the Trim hotel a very desirable residence during a tourist's stay. A coach passes between this town and Dublin twice in the day, and the Navan Railway on the one side, and Midland Great Western on the other, bring the tourist within little more than an hour's drive of the scene we are describing. The immediate suburbs, like all those surrounding ancient monastic remains, exhibit great richness and fertility. Before it enters the town the Boyne widens considerably, but becomes exceedingly contracted while passing beneath the ancient castle. It is crossed by a narrow bridge not unlike that of Drogheda.

The ancient name of that place was *Ath-Truim*, "the Pass or Ford of the Elder Trees;" and a ford, or shallow in the river, a short distance above the bridge, and within the extent of the

old fortifications, was probably the site of this pass, for above, and particularly below it, the river is very deep.

Although we have no evidence of the military importance of Trim before the arrival of the English in the twelfth century, there is high authority for believing it to be "one of the oldest, if not the very oldest, of the Irish episcopal sees;" and consequently it had an abbey or conventual church, which, it appears, was used, like the round towers of old, as an occasional place of refuge and defence to the small Christian community which had collected around it. "Colgan informs us that so early as the year 432, St. Patrick founded here an abbey of canons regular, dedicated to the Virgin Mary, built on a piece of ground given for that purpose by Fethlemid, the son of Laoghaire [Felimy, or Phelimy, son of Leary], and grandson of Niall."* The first bishop of this see was St. Loman, the nephew of Patrick, who was succeeded by Forcherne, the grandson of King Laoghaire, who was said to have been baptized by Patrick himself.

"A. D. 433. When Patrick, in his holy navigation, came to Ireland, he left St. Loman at the mouth of the Boyne, to take care of his boat forty days and forty nights; and then he (Loman) waited another forty, out of obedience to Patrick. Then, according to the order of his Master (the Lord being his pilot), he came in his boat against the stream, as far as the ford of Trim, near the fort of Feidlimid [Felimy], son of Loiguire [Leary]. And when it was morning, Foircbern, son of Feidlimid, found him reciting the Gospel; and, admiring the Gospel and his doctrine, immediately believed: and, a well being opened in that place, he was baptized by Loman, in Christ; and remained with him until his mother came to look for him; and she was made glad at his sight, because she was a British woman. But she likewise believed, and again returned to her house and told to her husband all that had happened to her and her son. And then Feidlimid was glad at the coming of the priest, because he had his mother from the Britons,—the daughter of the King

* Archdall, *Monasticon Hibernicum*.

We have been asked why we have not reduced our terrible, unpronounceable Irish names into something English, that people can read. This has, we feel, in a great part arisen from the Irish people being totally unacquainted with their history; and until they become familiar with their country's history, those Irish names must, indeed, sound harsh and grating in their ears.

of the Britons,—namely, Scothnoesa. And Feidlimid saluted Loman in the British tongue, asking him, in order, of his faith and kindred, and he answered, ‘I am Loman, a Briton, a Christian, a disciple of Bishop Patrick, who is sent from the Lord to baptize the people of the Irish, and to convert them to the faith of Christ; who sent me here according to the will of God.’ And immediately Feidlimid believed, with all his family, and dedicated (*immolavit*) to him and St. Patrick his country, with his possessions, and with all his family; all these he dedicated to Patrick and Loman, with his son Foirchern, till the day of judgment. But Feidlimid crossed the Boyne, and Loman remained with Foirchern in Trim, until Patrick came to them, and built a church with them, twenty-two years before the foundation of the Church of Armagh.”—*Tircehan*, as quoted by *Ussher, Primordia*, 853.*

It must be remembered, that the Britons had Christianity preached to them two centuries previously. The Church of Armagh here referred to stood on the north side of the river, and belonged to the see of Armagh.

The original abbey, which was dedicated to the Virgin Mary, stood, in all probability, upon the picturesque site of the Yellow Tower which in after ages was erected here, and is stated to be “the most lofty remnant of the Anglo-Norman architecture now existing in Ireland.” It was originally a square steeple, or abbey tower, of gothic architecture; it is now upwards of 125 feet high, and consists of one perfect and two partial walls, which, thus leaving it open on the west, exhibit a series of stories in its interior. It was, in all probability, like many of the other early monastic remains, and the round towers in particular, used as a place of security and defence; and its great height and commanding position may have caused it to be employed as a watch-tower over the surrounding country. Although the buildings of St. Mary’s Abbey adjoining have been removed, a considerable portion of their site can be traced. There is a tradition that Cromwell battered down a portion of this tower; but we do not find any further authority for this assertion than mere local history; and there is scarcely a ruin along the Boyne, from this to Drogheda,

* See some notices of the Church of St. Patrick, Trim, by the Rev. Richard Butler, Dean of Clonmacnoise.

which is not said to bear evidence of his cannon. Gough, indeed, in his additions to Camden, on the authority of the *Gentleman's Magazine* for 1784 (where there is a figure of this tower), asserts that one half of the Yellow Steeple "was demolished by Oliver Cromwell, against whom it held out a considerable time, as a garrison; a quarter of it being blown up by Cromwell, the top overhangs several feet;" but considerable dilapidations have occurred in it since then. The accompanying illustration represents the Sheep-gate of Trim, and the Yellow Steeple in the distance.



This abbey of St. Mary's, to which the "Yellow Steeple" was attached, together with the other abbeys of Trim, always maintained the most friendly intercourse with the Court of England, and particularly favoured the house of York.* The De Lacys are said to have re-edified and endowed it.

* The abbots of Trim, and the barons in its neighbourhood, particularly favoured the impostor, Lambert Simmel, who was ridiculously crowned in Christ Church, Dublin, as Edward the Sixth of England.

A cloictheach, or round tower, formerly existed at Trim, the burning of which by Conor O'Melaghlín, in 1108, and by Conor Feargal O'Lochlinn, in 1127, is mentioned in several of the Irish Annals. Like Clonard, the ecclesiastical buildings at Trim suffered various conflagrations; but neither our space, nor the character of this work, permit us to follow out the well-recorded annals of this or the other abbeys and monastic remains along our track,—consisting of notices of the celebrated persons who flourished or were interred in them, poets, priests, and warriors, mail-clad barons and palmer knights, holy nuns and pious monks; the various miracles wrought in these monasteries; the plunderings, seizures, and dilapidations they sustained; the records of the privileges which they enjoyed, and the broad lands they occupied; together with the offerings of the devotional, and the various plagues (from which Meath suffered so frequently and so severely);—which form the records of these establishments,—highly interesting, no doubt, in their way, but merely valuable to us for the epochs which they mark, and the historic facts which they attest.

The Grey Friary of Observantines stood by the water's edge, near the site of the present court-house, but all trace of it has been long since completely effaced.

The Black Friary of the Dominicans was founded by Geoffrey de Geneville, Lord of Meath, in 1263, to which he subsequently retired on the accession of Roger de Mortimer, his heir in right of his wife in that territory. Several Parliaments were held here, in one of which, in 1446, it was enacted that the Irish should cut their beards according to the English fashion, and not wear yellow shirts. Some meagre remains of this friary still exist near the site of the abbey-gate, on the northern side of the town, and without the ancient wall. It is much to be regretted that more of the history of the illustrious founder of this abbey has not come down to modern times. Geoffrey de Geneville, or De Joinville, was of noble birth, a native of Champagne, and brother to the celebrated Jean de Joinville, the companion and historian of St. Louis. Geoffrey was a most distinguished statesman, and the confidential friend of Edward I., by whom he was employed in most of the great diplomatic affairs of England at that time, both at home and abroad. About the middle of the thirteenth century he joined the Crusaders, and remained for some time in the Holy Land. After his return in

1273, he was appointed Lord Justice of Ireland; and in virtue of his wife, Maude, sister to Gilbert de Lacy, he became possessed of a large portion of the great Palatinate of Meath. After a most eventful history, he died on the 19th of October, 1314, in the Black Friary, which he had founded. Dean Butler, the historian of Trim, thus graphically alludes to this distinguished character:—"It is to be lamented that our notices of the varied life of this great man are so meagre that we cannot fill up the outline of the young noble of Champagne wooing his wealthy bride in the court of England, retiring with her to her great seignories in Ireland, and joining with her in founding a religious house;—joining in a crusade to the Holy Land; administering for a short time the government of his adopted country; busy for years in the councils and campaigns of the bold and politic Edward I.; and closing his career by the resignation of his lordship of Meath to his youthful granddaughter and her ambitious husband, and ending his days in the habit of a Dominican, in the cloister which he and his wife had built fifty years before. The following verses are quoted from I know not what monkish author, in the *British Magazine*, x. 670. The person to whom they relate had, like Geoffry, been a Crusader; and they give a beautiful picture of such a life as Geoffry de Geneville may have led in our Black Abbey:

" Ipse post militæ bursum temporalis,
Illustratus gratia doni spiritualis,
Esse Christi cupiens miles specialis,
In hac domo monachus factus est claustralis.

" Ultra modum placidus, dulcis et benignus,
Ob ætatis senium candidus ut cygnus,
Blandus et affabilis, ac amari dignus,
In se Sancti Spiritus possidebat pignus.

" Nam sanctam ecclesiam sæpe frequentabat,
Missarum mysteria lætus auscultabat,
Et quas scire poterat laudes personabat,
Ac cælestem gloriam mente ruminabat.

" Ejus conversatio dulcis et jocosa,
Valde commendabilis et religiosa,
Ita cunctis fratribus fuit gratiosa.
Quod nec gravis exstitit nec fastidiosa.'

"We may easily suppose that the old Crusader, who had been employed in the wars and embassies of the time, had tales

of travel and of danger which would make him a very acceptable companion in a monastery; and we may imagine, as he roamed about it,—

“ ‘ Hic per claustrum quotiens transiens meavit,
Hinc et hinc ad monachos caput inclinavit,
Et sic nutu capitis eos salutavit,
Quos affectu intimo plurimum amavit.’ ”

There were also a nunnery and a Greek church at Trim, which latter has been supposed to afford some evidence of a Grecian people settling in Ireland. Sir James Ware says: “ I confess, indeed, that there remain some small traces of the ancient Grecians having been in this country, in a church at Trim, in Meath, called *Græcorum Ecclesia*,” but as the only foundation for this supposition merely consists in the name, it may as likely have been given from some peculiarity in the doctrines or form of worship of those who frequented it, or from some similarity in its architecture to the Grecian or Pelasgic type, as we now speak of Grecian, Cyclopean, Roman, Saxon, or Norman masonry in some of our early churches. The question is still an open one.

The military buildings of Trim next claim our attention.

We have neither space nor inclination to enter into the much-mooted question as to whether the Irish possessed castles and military fortifications of that nature, prior to the arrival of the English, in the twelfth century. Besides the raths to which we have already alluded, they certainly had several very ancient fortresses, or circular duns of Cyclopean masonry, with walls of immense thickness, containing circular passages within them, and erected on highly defensible and commanding situations,—on rocks, islands, promontories, and isolated blocks of massive rock, on the level plains, like the ancient acropolises of the Greeks and Orientals, or on natural mounds in the midst of swamps and morasses; but these were constructed without mortar or cement. Several such acropolises are already well known, and their sites determined. The use of lime cement, and the accurate adjustment of the stones according to certain rules of masonry, were, however, well known to, and extensively employed by the Irish, centuries before the arrival of the English in this country, of which we have innumerable examples in the round towers, missionary

churches, and early ecclesiastical buildings, centuries before the conquest; and we may well suppose that, with such a knowledge of architecture, the Irish chieftains and their architects and artisans would have erected castles of defence and security for life and property, against the inroads of the neighbouring tribes, during those centuries of civil war with which this country was distracted, as well as against the descents of the plundering Dane and fierce Northman, during the ninth, tenth, and eleventh centuries at least. But, besides these speculations, we have positive historic assurances of the use of lime cement in the ancient Irish palaces; and we have authentic records of castles after this fashion having been built, particularly by the O'Conors of Connaught, antecedent to the English invasion of Henry II. The castles of Galway, Dunlo (now Balinasloe), and Colooney, in Sligo, were built in 1125. Turlough More O'Connor, monarch of Ireland, built the castle and bridge of Athlone in the summer of 1129, called the dry summer. The castle of Tuam, called "*Castellum Mirificum*," built by Roderic O'Connor, was also long prior to the date of the Invasion.* The castle of Cullinragh in Meath, the stronghold of O'Melaghlin, was demolished by Roderick, son of Turlough O'Connor, in 1155, and in the same year O'Melaghlin in retaliation destroyed the fortress and bridge of Athlone. That such buildings bore no comparison in strength, skill, or extent to those erected by the English here, there can be also little doubt. One can easily account for the almost total obliteration of these remains, while the relics of ecclesiastical architecture, many of which were constructed without lime or mortar, still remain. With regard to the first, every circumstance combined to dilapidate them, and the great superiority of the fortresses and castellated mansions of the English, in a short time rendered the Irish strongholds useless; while the most powerful of all feelings,—religious veneration,—a feeling common to the conquerors and the conquered, continued to preserve the latter, if not from desecration, at least from total annihilation; and the more distant from the theatre of war, and the scene of the early Anglo-Norman colonization, the more perfect have these sacred relics been preserved, and the longer have the

* See also note at page 12.

ancient manners, habits, and customs of our people been retained.*

We do not think the term "Saxon," so frequently employed in modern Irish writings referring to this period, is correct. The colonization was Anglo-Norman. We find that the families who became Anglo-Irish clans here were chiefly Norman, viz. : Butlers, Burkes, Barrys, Fitzgeralds, De Lacys, De Courcys. Many Welsh families settled here also, as Joyce,

* We cannot forbear mentioning the following circumstance as corroborative of this opinion. Shortly after the British Association met in Dublin, in 1835, we spent a week in the island of Achill, and there witnessed some scenes and modes of life which it could scarcely be credited were passing at one end of this small kingdom, while at the other the savans of Europe and America were met to discourse on science. There are several villages in Achill, particularly those of Keeme and Keele, where the huts of the inhabitants are all circular or oval, and built for the most part of round, water-washed stones, collected from the beech, and arranged, without lime or any other cement, exactly as we have good reason to suppose the habitations of the ancient Fírbolgs were constructed; and very similar to many of the ancient monastic cells and oratories of the fifth and sixth centuries, which religious veneration and the wild, untrodden situations where they are located, have still preserved in this country. Those of our readers who have ever passed the Minaune or Goat's Track, on the towering cliff that rises above the village of Keele, with the glorious prospect of Clew Bay and the broad swell of the western Atlantic before them, and have looked down upon the pigmy dwellings, resembling an Indian wigwam, scattered over the beach beneath, may call to mind the scene we describe. During the spring, the entire population of several of the villages we allude to in Achill, close their winter dwellings, tie their infant children on their backs, carry with them their loys, and some corn and potatoes, with a few pots and cooking utensils, drive their cattle before them, and migrate into the hills, where they find fresh pasture for their flocks; and there they build rude huts, or summer-houses, of sods and wattles, called booleys, and then cultivate and sow with corn a few fertile spots in the neighbouring valleys. They thus remain for about two months of the spring and early summer, till the corn is sown; their stock of provisions being exhausted, and the pasture consumed by their cattle, they return to the shore, and eke out a miserable and precarious existence, by fishing, &c. No further care is ever taken of the crops; indeed they seldom even visit them, but return in autumn, in a manner similar to the spring migration, to reap the corn and afford sustenance to their half-starved cattle. With these people it need scarcely be wondered that there is annually a partial famine.

Spencer relates that the Irish, like the ancient Scythians, "kept their cattle and lived themselves the most part of the year in *Boothies* [cow-houses], pasturing upon the mountain and waste wild places, and removing still to fresh land as they have depastured the former." Several laws were made to prevent this indiscriminate grazing on the borders of the Pale. See also the Statute of Kilkenny in the Archæological publications, p. 41.

Barretts, Walshes; but we had no early chieftain of the "Saxon race," which appears to have been less warlike than the Normans. The Saxons had no castles of stone at any time, and they had few laws. The truth is, they were an inferior *buddagh* race, and their history has been made too much of by modern writers. We had no Saxons here till the reign of Elizabeth, except some farmers in Forth and Bargie, and a few *villani* or buddaghs who followed the fortunes of the great Anglo-Norman warriors, and settled in Meath and elsewhere; but these were mere *serfs*. It was Cromwell who poured the great flood of Saxon blood into Ireland.

There is no evidence of the existence of a castle, or any military building, at Trim, anterior to the date of the English invasion. If the O'Melaghlin, the original monarchs of Meath, possessed a stronghold here, no record of it has come down to modern time. As we have already stated, Henry II. bestowed, for the service of fifty knights, the fertile territory of Meath upon the celebrated Hugh de Lacy; who fixed on Trim as his residence, and built there, about the year 1173, a strong castle, surrounded by a deep moat, into which it is most likely the water of the Boyne was conducted. Having established his power and authority in this part of the kingdom, the Norman baron departed for England, leaving his stronghold at Trim in the custody of Hugh Tyrrell.

"To destroy this castle, Roderick O'Connor, King of Connaught, assembled a large army; and Tyrrell, having despatched messengers to Earl Strongbow, beseeching him to come to his aid, and finding himself too weak to resist the multitudes brought against him, he abandoned the castle and burned it. The Irish king, having thus obtained his object, returned to his own country; and Earl Strongbow, who was advancing to the relief of Trim, meeting on his way with intelligence that the castle was burned, marched on, and when he came there he found neither castle nor house to lodge in; wherefore he made no stay, but pursued the enemy, and fell upon their rear, of whom 150 were slain; which done, he returned to Dublin, and Hugh Tyrrell to the ruined castle of Trim, to re-edify the same before Hugh De Lacy's return out of England.

"Giraldus Cambrensis says, that, 'on hearing of this inroad of Roderick into Meath, Raymond le Gros, although the news reached him at Wexford the day of his marriage with Basilia,

sister of Earl Strongbow, marched the next day to oppose him, not being overcome either by love or by wine; that Roderick, who had had previous experience of his valour, retreated at his approach; and that Raymond repaired the castles of Meath, that is to say, of Trym and of Duleek, which had been wasted by Hugh Tyrell.' "

The tragical end of the first English lord of Meath is already well known: he is said to have been murdered by an Irish labourer, while directing some work at the castle which he was building at Durrow, in the King's County. De Lacy having stooped forward at the moment, the man nearly severed his head from his body, at a single blow, with a sharp axe, which he had concealed for the purpose beneath his clothes.

Such is the version of this affair pawned upon the world by the Jesuit Campion, and copied by Hanmer, Harris, and has even been repeated by Moore; passing, like any story of the present day, from hand to hand, till it is now generally received as authentic history. Keating, it is true, endeavoured to rectify the error, but he was not attended to. The fruitful source of this, like innumerable other false statements in the works of writers upon the history of Ireland, has been their total ignorance of the language in which these statements were written, and their trusting (even if honest) to incorrect translations or garbled extracts.

In the Archæological and Celtic publications we perceive the dawn of a clearer, if not a brighter day for true Irish history; but the morning of that day has been ushered in by the publication, by Mr. O'Donovan, of the great work of Irish history, generally known as the "Annals of the Four Masters," so often referred to in this little work.

The true story is this. About the middle of the sixth century, Columbkille having obtained a grant of land from a chieftain named Brendan, in the King's County, at a place called Dair-Mahg, or the "plain of the oaks" (now Durrow), erected there a monastery, which subsequently became very celebrated. Well, some centuries after, comes the English baron, Hugh De Lacy, — the acknowledged destroyer of churches, — and erects his castle beside it, and even with some of the very materials, it is said, of the ancient abbey, which he destroyed. This naturally excited the wrath of the rightful heirs, the descendants of the ancient lord of Dair-Mahg, the renowned Brendan.

These were, the O'Caharney, chief of Teffia, well known under the soubriquet of Sinnach, or "The Fox," and O'Brien, chief of Brawney. Now, as may be shown from *unquestionable* authorities, the man who slew De Lacy was no Irish labourer, but a young soldier of the household of O'Caharney, who was remarkably swift of foot. The fact is recorded in the "Annals of Ulster," the "Annals of the Four Masters," and also more fully in the "Annals of Kilronan," from which latter we quote the following account:

"A. D. 1186.—Hugo de Lacy went to Durrow, to make a castle there, having a countless number of the English with him, for he was King of Meath, Brefny, and Oriel, and it was to him the tribute of Connaught was paid, and he it was that won all Ireland for the English. Meath, from the Shannon to the sea, was full of his castles and English followers. After the completion of this work by him, that is, the erection of the castle of Durrow, he came out to look at the castle, having three Englishmen along with him. Then came there one youth of the men of Meath up to him, having his battle-axe concealed, namely, Gilla-gan-innaheir O'Meyey, the foster-son of the Fox (O'Caharney) himself, and gave him one blow, so that he cut off his head, and he fell, both head and body, into the ditch of the castle."—*Annals of Kilronan, T. C. D.*"*

And the Four Masters take up the narration of this event, and inform us that Gilla-gan-innaheir escaped by flight into the neighbouring wood of Kilclare, where the Irish chieftains were awaiting him.

What a prolific theme for the novelist the stirring dramatic events of this period of Irish history would prove,—what a romance a Sir Walter Scott would have made of the whole story of the English invasion, and this incident in particular; and until some great historical novelist arises, Irish history and Irish scenery and manners will not be known, and consequently not valued, by the educated classes, either here or in England.

* See also the Annals of the Four Masters, A. D. 1186, with O'Donovan's note thereon.

It is a remarkable circumstance, that almost on the very spot on which Hugh de Lacy was slain, Lord Norbury, the late possessor of Castle Durrow, or Durrow Abbey, as he styled his new mansion, was murdered a few years ago; and it is said that he also interfered with the rights appertaining to the adjoining abbey.

De Lacy's body was detained for several years by the Irish, who then attacked the castle, but it was at last restored, and buried with great solemnity at Bective Abbey, while his head was carried to Dublin, and interred in the Abbey of St. Thomas, in the tomb of his wife, Rosa de Monmouth. This division of the remains of the unfortunate De Lacy gave rise to a fierce dispute between the two abbeys, as to which should possess both, and the controversy arose to such a pitch that the matter was referred to the supreme Pontiff at Rome. It was finally decided that the body should go along with the head; and it is supposed to have been removed to Dublin about the year 1205. Gerald of Cambria thus described this remarkable man:

"If you will know what manner of man Hugh de Lacie was, you shall understand his eies were blacke and deepe, and his nose somewhat flat, like that of an ape; and the right side of his face, from the chin upwards, by a mischance, was schrewolie skalled; his neck was short, and his bodie hairie, as also not fleshie, but sinewish and strong compact; his stature was but small, and his proportion deformed; but in construction he was verie sober, trustie, and modest. He was verie carefull in his own private matters, but in causes of government and in all public affairs he was most vigilant and carefull: and albeit he were a verie good souldier, and one of great experience in martial affairs; yet in his sundrie adventures, wherein he was sometimes rash and verie hastie, he sped not alwaies best, nor has the best success. He was verie greedie and covetous of wealth and possessions, but over much ambitious of honours and reputation."

In 1210 King John arrived in Ireland, and spent the second and third days of July at Trim; but although the present castle is called after him, it does not appear that he lodged at any castle at Trim,—if there was one at that time fit for his reception; and his writs are dated "*apud Pratum subtus, Trim*,"—the field now called the King's Park. What a volume might be written on *royal visits to Ireland*;—by whom made, under what circumstances, with what objects or inducements; what was the condition of the country, what the mode of reception, what the state of manners at the time of each;—from the days of Henry II. to those of Queen Victoria in this present year, 1849.

The present castle of Trim, which has been justly styled the finest specimen of Anglo-Norman military architecture in Ireland, is generally believed to have been re-erected by Richard Peppard or Pipard, who, according to the Registry of Clogher, also built the castle of Donaghmoye, in Farney.* It occupies within its walls about two acres of ground, and stands on a sloping mound on the right bank of the Boyne, from the banks of which it presents a noble and commanding appearance. The



great keep or donjon in the centre is a rectangular building, with massive square towers abutting from each side, and rising to a height of nearly eighty feet ; some parts of the wall are twelve feet in thickness. By the arrangement of its ground plan, it presented, when perfect, a figure of twenty sides, and the external face is still in very excellent preservation, with the exception of the tower facing the town gate, which is said to have been destroyed by the cannon of Cromwell. Some of the winding staircases, by which the topmost turrets were reached, still enable the visitor to gain the highest pinnacle, from whence a view of immense extent and great interest is obtained. Standing here, the eye ranges over many miles of the vast and fertile plains of Meath, with the Boyne sweeping through them, the various groups of ruins immediately beneath and around,

* See some account of the Territory or Dominion of Farney, &c. By Evelyn Philip Shirley. 4to. London : Pickering. 1845. p. 17.

the hills of Skreen and Tara, the mountains of Kildare and Dublin, the tower of Kells, and, in a word, a territory of which the lords of Trim may well have felt proud. The outer wall, which was surrounded by a deep fosse, through which the waters of the Boyne were originally admitted (thus completely insulating the fortress), is 486 yards in length, and defended by ten flanking towers at nearly equal distances. The gate towards the town, and the barbican, with the remains of their portcullisses, draw-bridges, and all the most approved military inventions of the day, are still in wonderful preservation. On the whole, we know of no castle in Ireland which affords the same scope for the study of the military architecture of the thirteenth century as this, which may justly be classed with those of Conway and Caernarvon. Within the wall, on the river side, we find the remains of a chapel, perhaps that used by the common soldiery; while two niches, resembling piscinæ, in the interior of one of the castle towers, mark the site of a small private chapel within. Adjoining the large chapel near the external wall are the remains of a tower supposed to have been the mint.

Our space, however, will not permit our entering at any length into the details of this noble structure, connected with which we find so many historic occurrences and classic associations. Besides those already enumerated, we cannot forget the pageants and tournaments of the celebrated Earl of Ulster; the imprisonment of the families of the Dukes of Gloucester and Lancaster, during the time of Richard of England's sojourn in this country; the confinement here of the royal hero of Agincourt; its occupation by the De Lacys, the Mortimers, the Verdons, and Cootes; its parliaments and its sieges;—all which throw a degree of splendour over the ruins of Trim.

But, great as these names and circumstances are, they pass into insignificance when compared with the celebrity which this place has acquired by its connexion with the greatest warrior and statesman of the day. It is generally, but erroneously, believed that the Duke of Wellington was born in or near Trim; but the evidence at present is altogether in favour of Dublin, and the honour of his birth-place is now awarded to the Royal Irish Academy House, originally Chichester House, where the Irish estates were forfeited after the Battle of the Boyne. The Registry of St. Peter's parish, in this city,

contains the following entry: "Arthur, son of the Earl and Countess Mornington, born 30th April, 1769." The house where "The Duke" resided for some time at Trim still stands at the corner of Dublin-Gate-street.

The borough of Trim has the honour of having returned the Duke of Wellington, on his twenty-first birth-day, to represent it in the Irish Parliament; and, in 1817, the gentry of Meath erected a Corinthian column on the fair-green of this town, to commemorate the military achievements of our distinguished countryman, whose early life and history is so intimately connected with this ancient town.

There were two other castles at Trim besides that just described, the castle of the Nangles and the castle of the Talbots, both of which stand behind the modern town upon the north side of the river and in the neighbourhood of the Yellow Steeple. The latter was built by the celebrated Sir John Talbot, Lord Lieutenant of Ireland in 1415, "The Scourge of France."

"So much feared abroad
That with his name the mothers still their babes."

This building was until lately the Diocesan School of Meath, when it acquired an additional celebrity from the Duke of Wellington having been for some time at school there. In it also was educated another distinguished Irishman, Sir William Hamilton, our Astronomer Royal. At present the building possesses little to attract attention except a tablet in the northern wall bearing the Talbot arms, quartered with those of Furnival.

Dangan, one of the seats of the Wellesley family, and where the Duke spent many of his boyish days, is distant about five miles from Trim, but is now completely dilapidated, and has long since passed out of the hands of the Wellesley family.

A locality, however, of still greater interest than that of Dangan, presents itself within two miles of Trim, and one which, like the former (with which it is in a certain degree connected), has been permitted to fall into utter ruin and neglect. We allude to Laracor, the early residence of Dean Swift.

It is a dark, secluded locality, into which one would suppose a breath of the busy world without never entered; a spot more uncongenial to the anxious thoughts and high ambition

of the Irish patriot can scarcely be imagined; but he had here other charms and more endearing associations, to which even the votaries of politics and philosophy are not inaccessible. Here Stella and Mrs. Dingley lived, and here they sauntered through the quiet roads with Dr. Raymond, the Vicar of Trim, and with the future author of "Gulliver" and the "Drapier's Letters." Here, on this very bridge which spans the noiseless streamlet, with its sedgy margins of willows and alders, must Swift have often mused; (for who is there that has not mused upon a bridge's battlements when gazing on the current beneath?) Beside this bridge, on the right-hand side of the road, once stood the residence, and around it the well-stocked garden, of the Dean, but the whole is now (or was when we last visited it) an ill-tilled potato garden; yet, without guide or cicerone, we were able to trace, from the recollection of the scene as described in the journal to Stella, the pond and bath which existed in this garden, the boundary of its ancient walls, the site of the very willows, some of whose posterity still exist, which hung over the stream, and beneath which the Dean and Esther Johnson so often walked. Some remnants of the brick wall which enclosed the garden, and the stands on which some bee-hives stood, were discovered a few years ago; but briars and thorns, rank sedge, and luxuriant weeds, are yearly obliterating even the faint traces we refer to. Of the house, a small portion of one of its gable ends is all that now exists; even this, thick and massive as it is, will soon have crumbled away, for, to the disgrace of those connected with the rectory, two wretched cabins have been erected within the site of the walls of Swift's glebe at Laracor.

In front of this residence stands a very perfect sepulchral mound, similar to that which we described already at Clonard, but very much smaller; and beyond this we find the old parish church, to which Swift ran the race with Delany, and where "my dearly beloved Roger" officiated as clerk. Within this Church we find a handsome monument erected to the last Wesley, or Wellesley, who bequeathed his name and his estate to the ancestor of the present Duke of Wellington.

About a mile nearer Trim is pointed out the cottage which Stella and Mrs. Dingley occupied; but this is somewhat apocryphal.

We might now conduct our readers over the numerous other interesting remains which still hallow and adorn Ath-Truim,—the ancient steeple of its parish church, erected in 1449 by Richard Duke of York,—the remnants of the town wall, which mark the ancient boundary, with its Sheep and Water-gates, still wonderfully perfect. We might visit the site of the meeting of its last parliament, speculate upon the locality of its mint, or enumerate the various coinages struck there; we might occupy pages with its annals; the miracles said to be wrought in its abbeys; the sieges which it sustained; the plagues with which it was visited; and the conflagrations which it suffered;—but neither our space nor the object of this book admit of this.


Somewhat less than a mile below Trim, within a magnificent sweep of the river, and beside the bridge of Newtown, on both sides of which they extend, we find a group of monastic remains which, with the exception of the Yellow Steeple, far surpass any of those now existing at Trim; the abbey of St. Peter and St. Paul, with the remains of the ancient cloister; and the broad parterre, or terrace, which stretched down to the water's edge, and where the good monks of old quaffed their wine by the banks of the Boyne, in the calm summer evenings, before the vesper bell summoned the community to worship. Unlike the military and ecclesiastical ruins of many other localities in Ireland, choked by the dilapidated buildings of some wretched dirty town, like the rank weeds of a neglected garden obscuring its urns and statues, those of Newtown-Trim stand alone and distinct on a swelling bank of the river, whose stream seems here to linger by them, as if in memory of their by-gone splendour, and stretch, without even a wall or fence to break the foreground, over nearly an acre of the richest turf, and surrounded by the greenest verdure in the broad plains of Meath.

In 1206 the English prelate, Simon de Rochfort, already mentioned, founded here an abbey of Canons Regular, of the order of St. Victor, and removed the episcopal see of Clonard to this spot. This haughty churchman, who appears to have enjoyed the confidence and support of the powerful De Lacys, seems to have possessed almost unbounded sway in the province of Meath at this period. He abolished several of the minor bishoprics, and had himself created sole Bishop of Meath,

under which title his successors* sat next in rank to the archbishops, as lords spiritual in the Irish Parliament; and he appears to have assumed an authority over the Irish clergy in this part of the kingdom, little inferior to that which the newly-imported Norman barons did over the laity. His settlement here, under the very walls of the time-honoured chapels and priories of Trim, the foundations of Patrick and his immediate successors, must have been no small cause of offence to the jealous churchmen of that ancient town; but, like the dust of their founders, both are now

“Mingled in peace.”

The principal ruins consist of the monastery, with its usual appendages, and the remains of the ancient cathedral of St. Peter and St. Paul, which is one of the most elegant structures, and perhaps one of the very earliest specimens of the light pointed Gothic, in the kingdom. Portions of the southern wall, and of the eastern and western ends, still remain. Ivies,



centuries old, of enormous size, yet still of the freshest green, cluster round and mantle over these ruins, particularly about the eastern window, which now lies open to the ground, and is

* Dr. Lanigan, however, states that, in or “about 1194, died Eugene, Bishop of Clonard, who, a little before his death, assumed the title of Bishop of Meath, which his successors have since used;” the same authority believed that this title was used by Bishop Idunan, as far back as the year 1096.

some fifty feet in height, affording, in several points of view, those beauteous framings to the neighbouring landscapes to which we already alluded.

“ Where the ivy hangs in masses,
Like a clustering mantle thrown,
And the many-feathered grasses
Quiver o’er the sculptured stone.

On the desolation stealing,
With a step of mournful grace,
All the harsher tints concealing
Of each ruin’s blanching face.”

In the walls of a small parish church adjoining are seen the sculptured tomb of one of the mitred ecclesiastics, besides several portions of beautifully carved imposts, flowery capitals, highly decorated mouldings, and other fragments of the abbey, several of which have been, within the last few years, erected there by the same friendly hand which has done so much to preserve the ruins of Trim.

In front of this chapel we find the noble monument of the Dillons, which, with its fine bas reliefs, and its numerous armorial bearings, would take pages to describe. It is the “ remains of a tomb erected to the memory of Sir Lucas Dillon, Chief Baron of the Exchequer in the reign of Queen Elizabeth, and the trusted friend of Sir Henry Sidney. It is an altar tomb, with the recumbent figures of Sir Lucas and his lady, Jane Bath, and adorned with the arms of the Dillons, Baths, and Barnewalls, and with a shield bearing two bends.



“ Sir Robert Dillon, father of Sir Lucas, was Attorney-General to Henry VIII.; and, at the dissolution of the monasteries, received from that king a grant of the lands of Newtown, where his brother Thomas was prior in 1511. Sir Lucas, in 1568, had a grant of the abbey of the Virgin Mary of Trim, and of the towns of Ladyrath, Grange of Trim, Canonstown, and Rathnally. He was the builder of the

house of Moymett, and was the father of the first Earl of Roscommon."

The inscription, which is now defaced, is thus given by Lodge (Roscommon):

"*Militis hic Lucæ Dillonis ossa quiescunt,
Conciliis Regni summus, Buroq. supremus
Mense Februarii decimus cum septimus instat,
Tempora lustrali profusus flumine clausit,
Terrenos linquens cælestes sumpsit honores.*"

Much of the adjoining ground is still used as a graveyard, and we regret to see throughout several fragments of the ancient sculpture used as head-stones by the people. This destruction, which has proceeded for so many years in all similar localities in the country, has in no small degree conduced to the dilapidation of several of our finest monasteries. Scarcely a day passes but several of the carved stones, and portions of doors and windows, are rudely torn from their situations, to be placed as head-stones; and some means, though late, should even now be taken to rescue these remains from further demolition. Even the ancient tombstones, many of which contained valuable Irish inscriptions, have been removed, defaced, or broken.* The graveyard of Clonmacnoise affords a true and lamentable intance of what we assert; and many of the jambs and window-sills to the wretched cabins in the village of Cong, in the county of Mayo, are formed of portions of the beautifully carved pillars and cut stones of the neighbouring abbey.

Archdall, on the authority of King, relates the history of a desperate murder committed at Newtown in 1307, when several of the friars, rebelling against the prior, killed two or three of their brethren, who endeavoured to oppose their entrance to the cellar. A synod was held here in 1216; and in 1486 one of its priors, Thomas Scurlock, was made Treasurer of Ireland. In

* On a small tablet in the little church at Newtown we find the following inscription, which, in honour to the learned author, and because some barbarian has recently endeavoured to deface it, we here insert:

"*HAS ANTIQUÆ PIETATIS ET ARTIS RELIQUIAS
VICINI MONASTERII SS. PETRO ET PAULO DEDICATI
OLIM ORNAMENTA
PROSTRATAS DIU ET PENE DETRITAS
PARIETIBUS HUIUS ECCLÆSIÆ
INFIGENDAS CURAVIT R. B. VICAR DE TRIM.
A. D. M.DCCC.XLII.*"



1488 its prior received the royal pardon, like those of his brethren, at Trim, for being concerned in the rebellion of Lambert Simnel. Its last prior was Laurence White, who surrendered this priory and its possessions in June, 1533; and three years afterwards this house was suppressed by Parliament, and granted to King Henry VIII., when the establishment was found to consist of "a church, two towers, an hall, storehouse, kitchen, brewhouse, two granaries, a pigeon-house and haggart; also of four messuages, twenty acres of arable land, being part of their demesne on the south side of the river Boyne; seventy acres of arable land, twelve of pasture, being part of the said demesne on the north side of the Boyne; and the close, containing an acre of pasture; with three gardens in Newtown: annual value, besides reprisals, one hundred and one shillings and four pence;" besides above 550 acres of some of the finest land in Meath, a castle, several villages, gardens, and messuages, in different parts of the adjoining country. So that this must have been one of the richest monastic establishments in Ireland.*

A few hundred yards further on, beyond the old bridge, on the southern side of the river, are the castle-like remains, consisting of a large square keep, immediately adjoining the bridge, with square towers at two of its angles; and somewhat lower down the river, but connected with it by a range of buildings, we meet a second smaller tower. Besides these, the walls of this extensive enclosure contain the ruins of a small chapel, with a beautiful triple window; and also a light circular turret by the roadside, which probably commanded the gate. This must have been always an important post, as it commanded one of the approaches to Trim; and the church militant here could have afforded every necessary protection to the extensive ecclesiastical establishments adjoining. The Hospital or Priory of St. John the Baptist stood here, and some of the remains which still exist within the general enclosure were erected in the thirteenth century for friars of the order of Cross-bearers, or Crouched Friars, a fraternity who wore a cross embroidered on their habit, and devoted themselves to the redemption of Christian captives.

* The ruins of Newtown form fruitful subjects for the painter. In the exhibition of paintings, at present open in Dublin, may be seen a very charming little sketch of these ruins by Mr. Connolly.

CHAPTER V.

FROM TRIM TO NAVAN.

SCURLOGSTOWN; ITS TUMULUS, CHURCH, AND CASTLE.—TRUBLY.—BECTIVE ABBEY.—INTERMENT OF HUGH DE LACY.—CLADY; ITS SUBTERRANEAN CHAMBERS, CHURCH, AND ANCIENT FOOT-BRIDGE.—THE HOUSE OF CLETTY.—RIVERSTOWN CASTLE.—TARA; ITS HISTORY AND ASSOCIATIONS; ITS TOPOGRAPHY.—BATHS.—THE LIA-FAIL.—SKREEN.—HYMN OF ST. PATRICK.—ARD-SALLAGH.—ST. BRIDGET'S WELL.—KILCAEN FORT.—ATHLUMNEY CASTLE; ITS LAST OCCUPANT.—NAVAN; RECENT DISCOVERIES THERE.

PASSING down the river from Newtown-Trim, its banks assume a more elevated and broken appearance,—now swelling gradually into long, undulating mounds, some of which have been lately planted, and now depressing into broad meadows, while the stream itself quickens its course, and its waters assume a brighter and more limpid character, but still dotted with islands, as in the previous portions of its course. Crowning the hill occupied by Newpark demesne, upon the northern bank, which will be found the most convenient route for the tourist, we find a very perfect circular military fort; and a little further down, upon its southern side, another group of ruins and ancient remains claims our attention,—the old castle, church, and mills of Scurlogstown, which here present from the river's bank an exceedingly picturesque appearance.

In connexion with the neighbouring streamlet and mills, below the latter, in a deep, sequestered nook, formed by one of the niches in the river's bank, we find one of those sepulchral mounds or barrows, so common along the Boyne, and beside it the site from which another was a few years ago removed for the purpose of manuring the adjoining fields. Some of the large flag-stones, which, no doubt, assisted to form the kistvaen, or central chamber, are still resting on the spot.*

A little above the mill may be seen the ancient church,—one of those small early chapels with a circular chancel arch, and a trefoil east window, not uncommon in this part of the king-

* This tumulus, the well-marked and extensive remains on the hill of Carbury, the military rath at Clonard, the ancient Pagan remains at Clady, below Bective, the remains of the great rath at Teltown, and that at Donaghpatrick, are the only structures of that nature which we have not found marked on the Ordnance Maps.

dom; and in the adjoining graveyard we lately observed a considerable portion of an ancient stone cross used as a headstone;—a relic in all probability older than the church itself. This was one of the smallest of our early churches, not being much above thirty feet in length. It is very likely as old as the twelfth century, and was granted to the Abbey of St. Thomas, in Dublin, in the beginning of the thirteenth century, by Walter de Lacy.

The castle of Scurlogstown, here figured, stands by the roadside, and commands a most extensive prospect around; and though possessing but little architectural adornment, its outline is particularly pleasing. It was one of the strongest-built watch-towers of the Pale, and its having so few external apertures, its massive and gloomy walls, its tall towers, and unbroken battlements, give it such a stern appearance that on passing it one still expects to hear the warder's challenge from its gate.



It was built in 1180, by William de Scarlog, one of the Anglo-Norman fiefs of Meath. Its outward wall is still quite perfect, as are also some of its stone floors; it may be considered the type of several other English castles in this part of the country, as, for instance, at Asigh and Trubly, &c.; consisting of a square keep or donjon, with round towers at the diagonal corners; these turrets, having circular stairs in them, were entered by small doors from each of the floors, and they rise somewhat above the height of the square portion of the castle. A perpendicular crack traverses the entire extent of the eastern wall of this building, said to have been caused by the balls of Cromwell, whose progress up the Boyne from Trubly, where he slept the night after the siege of Drogheda, the constable of Scurlog's castle was hardy enough to challenge; but, like many similar recitals of Cromwell's

“crowning mercies” in Ireland, this rests for its authority more upon tradition than written history. Indeed we know nothing more required than an essay upon Cromwell’s Irish campaign. Materials there are in abundance, but scattered throughout several works, and contained in State Papers, and other materials, to which, we are quite sure, an author could have ready access; and yet it is one of the most defective portions of modern Irish history.*

We have here another example of the connexion and combination of ancient and modern remains to which we have already alluded:—a pass upon the Boyne, memorable, no doubt, in some ancient Irish saga, as the scene of hostile fray by its banks; a tumulus covering the sepulchre of the slain; a Christian era antecedent to the Church, marked by the rude cross we spoke of; the early Church itself telling of the simple purity and religion of our forefathers; the gaunt, warlike form of the ancient castle pointing out the epoch of the great English invasion, and its walls bearing evidence of the Protector’s rule.

The next point of beauty is Rathnally, where the banks rise on both sides to a considerable elevation; and here some noble trees in the surrounding demesne, clad in the livery of summer, with the highly cultivated state of the grounds,—the deep, sullen waters of the river,—the calm, Sabbath stillness of the scene, broken only by the cawing of the rooks, and the interrupted craik of the meadow rail,—the long, dark vistas through which the stream winds,—and the picturesque view of the adjoining mills and mansion, form one out of the many charming landscapes which now adorn the Boyne, not here alone, but almost throughout the entire of the remainder of its course.

“ Oh! so green is the grass, so clear is the stream,
So mild is the mist, and so rich is the beam,
That beauty should ne’er to other lands roam,
But make on the banks of *this* river its home.”†

Not only is the transition in the scenery of this,—the second division of the Boyne,—well marked, and totally distinct from

* Our learned friend Mr. Hardiman has made a collection of all the documents relating to Cromwell in Ireland, and it is hoped that the Irish Archaeological Society will have funds sufficient to publish them.

† The Banks of the Lee, by Thomas Davis.

the previously described portion of the river, but the whole appearance of the country changes, and an air of healthy prosperity, marked by the high state of cultivation, prevails, which is in vain sought for between Clonard and Trim.

Mr. and Mrs. Hall, in their charming book on Ireland, speaking of this district, remark : " The hedges are remarkably luxuriant; the trees (of which there is an unusual abundance) are of extraordinary growth; and the fields have at all times and seasons that brilliant green so refreshing to the eye, and so cheering to the mind, when associated with ideas of comfort and prosperity. There is indeed no part of Ireland where the Englishman will find himself so completely at home; for, added to great natural beauty, he sees on all sides the beneficial results of careful cultivation, and marks, in every direction, the ordinary consequences of industry directed by science; while the poverty and wretchedness that are elsewhere forced upon his attention is here so seldom perceptible, and the clamorous voice of woe 'rarely intruded upon the ear.' "*

Such, in particular, is the character of the scenery at the next point of interest as well as beauty—Trubly,—the river being here also completely shut out by its towering, wooded banks, from the roadside view. On a high, commanding knoll, on the southern bank of the Boyne, we still find in the haggard of its proprietor some remnant of the castle of Trubly, or Tubberville, the ancient seat of the Cusacks, who possessed it as early as the time of Richard II. This originally consisted of a square keep, with circular corner towers, like that of Scurlogstown; the foundations of the former can still be traced, and about twenty feet of one of the latter is yet standing, looking, at some distance, and in some points of view, very like the butt or lower portion of a round tower. This is the castle which Cromwell is reported to have slept in on his march up the Boyne. Adjoining it is another isolated circular tower, erected for a dove-cote, or pigeon-house; it is one of the most ancient and best built structures of that description in the kingdom, and resembles very much the dove-cote in one of the towers in the outer wall of Trim castle.

By an inquisition of 1663, the possessor of Trubly was found

* Ireland; its Scenery, Character, &c. By Mr. and Mrs. S. C. Hall. Vol. ii. p. 373.

guilty of high treason; and in the charter of James the Second, Nicholas Cusack, one of Tyrconnell's captains, who owned this castle at that period, was nominated Portrieve of Trim; but at what period this border fortress was destroyed, whether from storm or by gradual dilapidation, does not appear.

Stanihurst says that in his time the Irish, by which term he must mean the retainers, servants, and villagers in the vicinity, "merely passed the night in these castles; the day was spent in mud walls covered with thatch, adjoining the castle and the bawn, which was surrounded with a hedge and ditch, and into which the cattle were driven in time of alarm. At night there was always a watchman on the top of the castle."

Trubly is three miles from Trim, and about a mile further down the river we again cross the stream, by the bridge of Bective, to visit the noble ruin beside it, which gives name to this locality and title to an Earl. As we approach from Trubly, the southern road cuts through a very fine mound of the sepulchral kind,—indeed one of the largest, though not the highest, on this part of the Boyne,—although diminutive in comparison with those which shall engage our attention lower down. Partly for the gravel and small stones, of which it is for the most part composed, and partly from excavations made by the peasantry seeking for treasure, at various times, the top of this mound has been removed. There exist many legends in the country about this ancient cemetery, kept up by the idle dreams of an imaginative people, and these, coupled with the fact of some antique articles of value having been occasionally discovered there, have conduced, in no small degree, to cause these excavations, and thus to lessen its size. But we have heard of the doings of road contractors,—and the intentions of grand juries also!—with regard to the employment of the stones which form similar structures in other parts of Meath, which should awaken the attention of those whose patriotism (for this really is one of the instances to which that term may at present be applied) is greater than their agricultural or macadamizing speculations. From this mound we obtain a charming prospect of the yellow battlemented walls and lichen-clad cloisters of the abbey; and at a point nearly equidistant from the river, on the opposite bank, may be seen a fine specimen of the military raths or duns of the ancient colony who first passed up and settled upon this river's borders.

From the bridge of Bective, or Begty, situate midway between Trim and Navan, we obtain a pleasing view of the adjoining abbey, upon the left bank of the river. From this point the ruins present an imposing and picturesque appearance of a noble castellated mansion, rearing high its turrets, gables, and chimneys, and showing that its architect had both comfort and security in view. The tints which usually play upon the walls of Bective are of a richer and more varying hue than we have ever seen elsewhere. The square grey towers, gables, and chimneys, rendered in some parts perfectly golden by the most brilliant orange and yellow lichens, and in parts festooned with the dark-green drapery of the Irish ivy, rising out of the light feathery foliage of a plantation of young larch, and standing in the midst of a field of corn, which stretches between the ruins and the blue waters of the Boyne, form, upon a summer's evening, one of the most lovely objects in nature.



The ruins of this great Cistercian monastery are among the most perfect in Meath, and enough still remains to enable the tourist to decide, with a tolerable degree of certainty, upon the original use of each compartment, and every room and cell in the building; and as the present proprietor has enclosed them with a wall, they are less desecrated than most of the ecclesiastical remains in Ireland. It is a fact, strange but true, that

the peasant, who will not (or rather who heretofore would not), for love or money, touch a stone, or remove a mound believed to be of Pagan origin, will wantonly pollute, or, for ordinary building purposes, dilapidate the noblest monastic structure, or the most sacred Christian edifice !

Around the ruins of Bective Abbey a young plantation is yearly obscuring its fair proportions. The dark, wide-spreading yew, the gnarled oak, the stunted elder, or the blasted ash, form fit companions for the crumbling wall and falling arch ; but those young trees are anything but suited to the locality, and will, in a short time, completely hide the lower portions of this noble pile. Whether domestic comforts, more than piety and self-mortification, influenced the founders and early tenants of this monastery, or that the condition of the country at the time required a castellated mansion for defence, rather than an edifice erected for the service of religion, it is difficult to say ; but certain it is that while we are able satisfactorily to trace the various halls, corridors, kitchens, galleries, courts, dormitories, and cloisters, it is with great difficulty we can decide upon the situation of the church. Two tall, lancet-shaped arches outside the enclosure on the north-eastern side, and the remains of a handsome window, which splays outward from the great court of the building, would lead us to conjecture that it must have been situate adjoining that point. Some have, however, supposed that it stood over the gallery which formed the southern enclosure of the courtyard.

This abbey, called in Irish *Sendrede*, or “ the Old Bridge,” was founded from Mellifont, in the middle of the twelfth century, by Murchard O’Melaghlin, King of Meath, for monks of the great Cistercian order,* under the title of the Abbey de Beatitudine, and dedicated to the Virgin. The endowment was remarkably rich, the demesne consisting of 245 acres, besides a mill and fishing weir on the Boyne. The lord abbot of Bective sat as a spiritual peer in Parliament, one of the fifteen abbots then entitled to that dignity in Ireland.

There is a remarkable historic incident attached to this ancient house. After the murder of Hugh de Lacy at Durrow, in 1186, an account of which we gave at page 91, the body was

* It is the only Cistercian building in Meath. See *Grace’s Annals*, p. 107.

not recovered till 1195, when "the Archbishop of Cashel, Legate of Ireland, and John Archbishop of Dublin, brought from the Irish country the body of Hugh Lacy (who had conquered Meath), and buried it in the Abbey Beatitudine, that is, of Bective; his head they buried in the church of St. Thomas, Dublin."* Now, as this latter establishment had been founded by one of the Anglo-Norman barons, William Fitz-Adelm, a companion of the great Palatine, by whom also it was largely endowed, the brotherhood of St. Thomas claimed the rest of the remains from the monks at Bective. As we already remarked at page 93, a fierce controversy ensued amongst the rival churchmen on this subject, as to which abbey should possess both the relics; and, as in all Irish ecclesiastical disputes, then, as now, the Pope was appealed to for his decision. Innocent III. appointed the celebrated Simon Rochfort, then Bishop of Meath, and his archdeacon, together with Gilebert, the prior of Duleek, to arbitrate between the belligerents, and they awarded the corpse to the monks of St. Thomas, to which place it was accordingly removed. Such was the estimation in which the remains of a viceroy were held in Ireland in the twelfth century!

An arcade of pointed cinquefoil arches, supported by light clustered pillars, decorated with elegantly carved capitals, separates the cloister from the court-yard or quadrangle, on the southern side; and beneath one of these tradition says that the great Lord Palatine was buried. The carving of this colonnade is, from the hardness of the Ardbraccan stone, of which it is built, and the sharpness of the cutting, in fine preservation, and well worthy the attention of the archæological and antiquarian student. On the extreme western pilaster

* See Grace's Annals of Ireland. A portion of this abbey of St. Thomas, now Thomas's Court, was remaining within the memory of man. In the incident related above, we have quoted the circumstances as they are set forth in records acknowledged to be authentic; but, at the same time, we are inclined to question the chronology of the documents relied on by Irish historians, for if the body and head of De Lacy were thrown into the ditch, and endeavoured to be concealed by the Irish, it is not likely that they could have been identified nine years after; and the very fact of the head having been removed to Dublin, while the body was carried elsewhere, induces us to believe that the interment of both took place immediately after the murder. It is possible, however, that the body may have been originally interred at the cemetery at Durrow.

we find a figure, cut in relief, of an abbot, and above it a shield enclosing three fleur-de-lis, probably the arms of the prelate interred beneath, for we know that underneath these arcades the ecclesiastics of olden time were wont to place their most venerated dead.



The great tower at the entrance above the porch is still very perfect, and by its loop-holes and battlements shows that the inmates were, occasionally at least, entitled to be considered a part of the church militant. It has been said that a portion of this abbey was erected prior to the date of the English invasion, and that Grecian architects were employed in its construction, but upon what authority we have not been able to discover.

The annals of Bective present us with nearly the same amount of history as those preserved of similar establishments of the same era along the Boyne and elsewhere; and their detail, though highly valuable in eking out the history of the country, would be uninteresting to the general reader; charters, grants of lands, endowments, and forfeitures; bulls of Popes, and letters of kings; excommunications and interdictions; pillagings; disputes with neighbouring powers, rival ecclesiastical establishments, exacting chieftains, or rude military commanders; observances of festivals; solemn interments; the preservation of relics, and the records of the accession and deaths of superiors, forming the great bulk of such materials.

There is a small hamlet near the bridge to which the name of Bective is given; and the family of Taylor derive the title of Earl from this locality.

From Bective to Navan the Boyne sweeps gracefully through a highly cultivated country; and its banks are adorned, throughout the entire length of this portion of its course, by the grounds and plantations of noble parks and demesnes, as those of Balsoon, Bective, Bellinter, Dowdstown, and Ardsallagh. The banks are not high or abrupt, but form pleasing

slopes and gentle undulations of surface; here stretching out into broad lawns, and there fringed with aged trees, which, with the handsome mansions of the neighbouring proprietors, give the whole very much the appearance of the inland scenery of England. It is not the peculiar feature of any one of these seats that engenders this idea, but it is the general continuity of style, and the effect which the demesne on one side lends to that on the other, together combining to shut out the surrounding country, which produces this beauty, and that keeps the stream still flowing onward for several miles of its course through a succession of picturesque landscapes in this charming valley.

Near the Navan road, upon the northern bank of the river, not far from the abbey, we find one of those early military raths, so common throughout Meath; and about three-quarters of a mile below Bective bridge, on the same side, upon a small tongue of land which runs out between a tributary streamlet and the river, some very interesting and hitherto almost unnoticed remains, both Pagan and Christian, claim our attention. These consist of the old church and bridge of Clady, and some subterranean structures lately discovered in the immediate vicinity. The church, which is now a complete ruin, was originally a parallelogram, with a projection at the south-eastern side—a sort of transept—and a bell-turret upon the western gable; but although we are able to trace the outline of this building throughout, the only portion of much interest spared by the hand of time is a very beautiful window, in the south chapel, the stone frame-work of which is still very perfect. It consists of two cinquefoiled arches, in the “early English” style, separated by a light shaft. The carvings on the round capitals are rich and tasteful. An aged elder-bush overshadowing and partly protruding through these lights, serves to heighten the effect of the picture, while a patriarchal ash, of gigantic dimensions, spreads its rugged arms over the adjoining graveyard. That many such windows as that we have described must have existed in this church originally, may be learned from the quantity of fragments, exhibiting the same form of mouldings and carving, which are scattered around, or partly sunk in the ground, as head-stones. A hollow stone, apparently an ancient lavatory or a piscina, is still remaining in the enclosure, on the northern side. Mr. Bolton, in whose demesne

the church stands, has lately, with laudable zeal, removed the font to his garden, to preserve it from utter demolition, and being literally ground away; for it had been used by the adjoining peasantry for years as a rub or whetstone, as all loiterers in ancient churchyards must be aware has been the fate of many a similar sacred vessel. It is perfectly plain, octagon in shape, and measures two feet five inches in diameter. It is evidently of great antiquity; and the size of its basin rather favours the idea which we already stated when alluding to the font at Clonard, that immersion was, in all probability, the form of baptism employed by the early Irish Christians. Now that Mr. Bolton has enclosed his demesne, and that the same means of access for mere knife-grinding purposes have ceased to exist, we confess we should like to see this relic restored to its ancient and original site.



The accompanying graphic and faithful sketch, will afford the reader a tolerable idea of this interesting group of ruins.

The adjoining stream is crossed by an ancient stone foot-bridge, about thirty yards in length, and supported by two arches of different shapes. It is about five feet in breadth, and does not appear to have ever had a parapet. It is one of the very few foot-bridges which we have ever seen or heard of in this country; and if it is coeval with the church to which it leads, and which in all probability it is, it cannot be denied that this is the most ancient stone bridge now existing in Ireland.

In an adjoining plantation, and not above a stone's throw from the church, were lately discovered two subterranean chambers. Each of these crypts is formed entirely of unhewn stones, arranged in the shape of a bee-hive dome, but without mortar or cement, the arch being formed by each tier of stones projecting somewhat within or beyond that beneath, and the summit completed by a large flag, the whole structure being preserved by the pressure and weight of the surrounding earth, for these chambers are quite below the surface; and it was owing to the accidental circumstance of a cow having pressed in one of the top stones, that a knowledge of their existence was obtained. The first chamber is nine feet broad, and the walls are not indented by either niches or minor crypts. From the floor to the summit measures upwards of nine feet; but owing to the drifting of some fine sand into the interior of these chambers and passages, their apparent altitude is at present much less. A small quadrangular passage, nine feet in length, two and a half high, and three broad, and roofed with large flag-stones laid upon the flat, runs in a northerly direction to another chamber, exactly similar in every respect, but without any other passage leading from it. From the first chamber, a second gallery branches off in a westerly direction, to a distance of about fifteen feet, where its dimensions increase considerably; but from the roof having fallen in, it is not possible at present to investigate it much further. We understand that these chambers were found in this condition when first opened, a few years ago, and did not contain either weapons, ornaments, or any animal remains, which could in any way assist us in pronouncing upon their probable use. Still the antiquary will speculate upon the purposes for which such structures were erected, their ages, and the people by whom they were built. They differ from the sepulchral caves in that the dome springs directly from the floor, and not from a course of upright pillars, such as we find at New Grange, Dowth, and elsewhere; and in not possessing niches, or minor chambers, which some of the smallest of these latter do, as that in Netterville Park, to which we shall presently allude. The stones are also much smaller, and totally devoid of carvings; and the existence of passages from one to the other, as well as these chambers being sunk in the earth, and not surrounded by a distinct mound of clay or stones, serve to distinguish them from

those of the sepulchral class. There can be little doubt that they are to be referred to Pagan times, before the use of the arch, or the advantages of mortar, were known, and were probably employed by some of the very early people of this island as places of security, temporary habitations, and granaries, for which latter purpose their dryness well fitted them. The two chambers and the passages just described are, in all probability, but portions of a large collection of other souterrains adjoining; and some elevations of the ground in the neighbouring plantation, which have a remarkably hollow sound, lend probability to this conjecture. It is not unlikely to have been a troglodyte village, used as a granary as well as a hiding-place, by some of our Firbolg or Tuatha De Danaan aborigines. The place is well worthy of further investigation in these days of scientific antiquarian research; and we are sure the proprietor would willingly aid such an undertaking.

Several subterranean chambers and passages, some of them similarly constructed, exist in Connaught and Munster; they are generally formed in the raised embankment, or within the precincts of an ancient fort or rath, and are by the peasants invariably attributed to the Danes, although we have no authority whatever for such a supposition. Within some of these have been found quantities of animal remains, those of goats and oxen in particular, besides quantities of charcoal, and very often small tobacco-pipes. Sir Thomas Molyneux gave a very accurate description of these caves and galleries, upwards of 120 years ago, in his "Discourses concerning the Danish Mounds, Forts, and Towers in Ireland."* Most probably a rath existed here in former times, but the planting and the very great alteration of the surface at present prevents its being discerned. A somewhat similar chamber may be seen in the vicinity of Navan, somewhat lower down upon the Boyne. It is figured in Mr. Wakeman's *Archæologia Hibernica*,† and

* Dublin: printed by and for George Grierson, at the Two Bibles, in Essex-street, 1725; and reprinted in Boate and Molyneux's *Natural History of Ireland*. See also the Author's *Memoirs of Sir Thomas Molyneux*, in the *Dublin University Magazine* for 1841, vol. xviii.

† *Archæologia Hibernica*: A Hand-Book of Irish Antiquities, Pagan and Christian, especially of such as are easy of access from the Irish Metropolis. By William F. Wakeman. With numerous Illustrations. Dublin: M^cGlashan. 1848.

Mr. T. Crofton Croker has given an interesting account of several in the county of Cork.*

Two of the most celebrated Irishmen of early times died on the Boyne's bank: Finn Mac Cumhaill, the renowned warrior, popularly known as Fin-ma-Cool, who was killed with a dart or gaff by a fisherman named Athlach, at Ath-Brea or Rath-Breagha,† and also his father-in-law, King Cormac Mac Art, the grandson of Con of the Hundred Battles, who died from a fish-bone having stuck in his throat. The circumstances attending the death of the latter are here worth recording. He was one of the most renowned, just, and wise of the monarchs of Tara, and is said to have been the third person who accepted Christianity in Erin before the time of Patrick. One of his eyes having been destroyed by the warrior Engus Gaibh-uaihnech, he afterwards generally resided at Acaill (now Skreen), at Kells, or at the *House of Cletty* (Cletigh, Cleiteach, or Cletech), as "it was not lawful that a king with a personal blemish should reside at Tara."‡ Two years after the loss of his eye, he was suffocated, from the bone of a salmon having stuck in his throat, at this House of Cletty, the site of which has not yet been determined by topographers. The name, the situation, and the remains at Clady, afford us, however, some clue to it. In several Irish manuscripts, both in prose and verse, this house is alluded to as being over or above the Boyne ("Cletig supra Boin"), and in the vicinity of Tara, to both of which circumstances this place accurately answers; but furthermore we learn something of its precise locality from the account given of the death of King Muirheartach Mac Earca, nearly two centuries and a half after the time of Cormac. He was burned to death in the House of Cletty, by his mistress Sheen, after the battle of Kirb,—a spot believed to be Assey, upon the opposite side of the Boyne. St. Cairneach, of Tuilen (now Dulane, near Kells), cursed the place, and it was soon after deserted. His prophecy is recorded in the *Annals of Tighernach*. King Cormac's death took place, according to the *Four Masters*, A. D. 266, "at Cleiteach, the bone

* See the *Dublin Penny Journal*, vol. iii. p. 350.

† See the *Annals of the Four Masters*, A. D. 284; and the *Annals of Innisfallen*, quoted by O'Donovan, in a note to the above.

‡ See *History of the Cemeteries in the Leabhar na h-Uidhre*, a translation of which is given in *Petrie's Round Towers*.

of a salmon sticking in his throat, on account of the Sibhradh [Genii], which Malgeen, the Druid, had incited at him, after Cormac had turned against the Druids, on account of his adoration of God in preference to them."

The situation of Cletty is described in the historical tale entitled *Oighidh Muirheartaigh Mhoir mhic Earca*, thus: "Good indeed was the situation of that house over the margin of the salmon-full, ever-beautiful Boyne, and over the verge of the green-topped Brugh." This latter place, is, however, against our theory, but so is it against the situation of Cletty assigned by others to the vicinity of Stackallan Bridge,* and there may have been, and no doubt were, more Brughs or forts than one. This inquiry is well worthy of further investigation.

Below Clady, some high, precipitous banks arise, upon the northern side of the river, near Bective House; and upon the opposite hill, two sites, of considerable interest, claim our attention,—Balsoon and Asigh or Assey. The former was once the residence of Archbishop Ussher, and its ruined church and ancient graveyard are still worthy of a visit. The latter, called in Irish *Ath-Sighe*, consists of the ruins of a castle, originally constructed upon the type of those at Scurlogstown and Trubly, a square keep, with circular flanking towers at the eastern and western angles.† Like other castles of the Pale, its summit commands a most extended view, including a long reach of the river both above and below this point. On the slope leading down to the river we meet with a small group of ecclesiastical ruins, portions of the walls of one of the early missionary churches: the middle wall, with a square doorway, occupying the place of a choir arch; and some broken fragments of stone mouldings, with a surrounding graveyard. Several noble ash trees, which seem the peculiar growth of the valley of the Boyne, shelter this ruined chapel; and the luxuriant crop of white lichens, which have crept over the walls and adjacent tombstones, give this place an air of great antiquity.

As the Boyne passes through the noble demense of Bellinter, it is again broken into islands, a group of which, nearly oppo-

* See O'Donovan's Note on Cleiteach in the Annals; and also the Banquet of Dun na nGedh, and the Battle of Magh Rath, pp. 19, 20.

† The plan of these Boyne fortresses consisting of square keeps, with circular turrets at the corners, is well shown in the ruins adjoining the Church of Lusk, where an ancient Round Tower is used as one of the flanking towers.

site Mr. Preston's house, are planted with considerable taste. This residence, which was once the seat of the lords of Tara, was designed by Mr. Cassells, and is one of the finest specimens of domestic architecture in this part of Meath. It consists of a large square central building, with a projecting wing on each side, connected to it by a colonnade. The southern road to Navan presents the traveller with a fine view of this mansion and the intervening park.

Turning southward from Bellinter Bridge, as we begin to ascend the hill towards Tara, the castle of Riverstown, about a mile and a half from the Boyne's brink, will be found well worthy of inspection. This was one of the best built castles upon the Boyne; and the remains which still exist, in the perfection of their masonry, and the sharpness and beauty of their lines, still bear witness to the fact. The ruins of this beautiful building show it to have been of the same type as most other castles of the Pale which we have examined, consisting of two portions, an ancient and a modern. The former is a massive square tower, entirely built of cut or hammered stone, with three square turrets at the corners, which batter very much toward the foundation, and at top rise several feet above the principal part of the building. The eastern turret was originally a pigeon-house, and that on the west side contained a spiral staircase which led to a parapet at top. These turrets were lighted by small square windows and loop-holes, and were, as well as the central tower, divided into four floors and an attic. In the wall of each of these turrets we find one of these chimney-like, concealed flues, or upright passages, common in some of the ancient castles, and popularly known among the people as "murder-holes." This part of the castle was inhabited within the last eighty years, and portions of the plaster still remain upon the interior of the walls. The more modern portion abutted against the western wall of the tower, and shows, by the two gable-grooves, which are still visible in the latter, that it was erected or re-edified at different periods; and this conjecture is further supported by the fact of the existence of a large stone-arched keep, still remaining on the north-western side. Portions of the wall of the bawn can still be traced in the surrounding farm-yard.

By whom, or at what precise time, the original castle of Riverstown was built, we have no means of ascertaining, but

we know that in the sixteenth century it was in the possession of the Dillons. In the churchyard of Tara may be seen the monument of Robert Dillon of Riverstown, who died in 1595.

In our passage down the river we have heretofore confined our observations and researches to the scenery in its immediate vicinity, and the objects which presented themselves within view of its banks ; for were we to extend the field of our inquiry beyond this limit, we would have to enlarge this work much beyond the dimensions of a guide-book to the Boyne. In fact, it would become, had we sufficient knowledge of the subject, an antiquarian history of Ireland ; and yet, as we stated at the beginning of this work, such might be written from the ruins still remaining in these localities. Thus, were we inclined to draw upon the sources of early Irish history, from documents of undoubted authenticity, referring to Pagan and early Christian times, and to point with certainty to the evidences which existing remains afford of the truth of the topography, at least, set forth in those early records, the bardic histories, which were written in the few first centuries of the Christian era, we might lead our readers from Bellinter Bridge up a gradual ascent which rises on the right bank of the river, about two miles beyond this spot, and, standing on a commanding eminence, point to the grassy mounds of Tara in proof of our assertion. A full description of this celebrated locality would, however, occupy several chapters. Aroused by the enthusiasm which the very name inspires, we might describe at length the royal residences which once crowned this sacred spot, and still point out the foundations of these very structures. We might recount the monarchs who reigned here, Belgic, Scotie, and Milesian, from the days of Slaigne and Dagda, through the royal line of Temur, to the subversion of Paganism, and the introduction of Christianity into Ireland. We might describe the great *Feis Teamhrach*, or assembly of the chieftains ; and while we hold not with superstitious reverence by all the bardic tales and poetic legends handed down to us for some fifteen centuries, except so far as they accord with common sense, or are borne out by collateral evidence, we could point with pride to the just and wise laws which emanated from the house of Ollamh Fodhla ; we could tell of Con, the warrior of the hundred battles ; of the Druid famed for sorcery ; the Brehon wise in judgments ; the Bard who chronicled in

wild and imaginative song the half fabulous events of a semi-barbarous age; the Kings renowned in story,—the Cormacs and Nialls, and Dathis: but now

“No more to chiefs and ladies bright
The harp of Tara swells;
The chord alone that breaks at night
Its tale of ruin tells.”

We might, by merely paraphrasing the translations of authentic Irish history, occupy pages in recounting the deeds of Patrick, when he converted the Irish monarch and the whole court at Tara. We might, even now, preach with the sermons, and enliven modern Christianity with the hymns of our patron saint. We could tell of the cursing of Temur by St. Ruadhan, and its subsequent desertion. Or again, we might trace the various raths, and descant upon the wells and pillar-stones which consecrate this spot. The Lia Fail, or stone of destiny, supposed to have been removed to Scone, and from Scone to Westminster, but which is still, it appears, undoubtedly at Tara, would in itself form a text for an entire chapter upon the civil history of this kingdom; while the name of St. Adamnan is a fitting proem for an hour's dissertation on our early ecclesiastical writings, and the colonies which sprung from this Isle of Saints, even to the far-famed Iona. Or, to come down to later years, the graves of the croppies, the lyrics of Tom Moore, and the monster meetings, would lead us far beyond the limits of this little work. Were we to allow ourselves the latitude we should desire, or, perhaps, the subject deserves, we would carry our readers to the opposite hill of Skreen, the ancient Acaill, and while we pointed out, from that elevated situation, the extensive prospect of the broad lands and fair mansions, the castles, churches, and monasteries, so full of interest in themselves, and such embellishments to the extended landscape within view, with the “Pleasant Boyne” gliding smoothly by them, we could also tell of the wonders of the locality whereon we stood, and call to our readers' recollection the legends about the shrine of Columba, and the history of the battles fought here by the Ostmen of old, and also refer to its occupation, in more modern times, by the Feypoos, and Cusacks, and Verdons.

For all that is known, or can, in all probability, be known,

of the antiquarian lore, historic records, and topographical details, connected with Tara, we must refer our readers to Dr. Petrie's essay upon the history and antiquities of that ancient seat of learning, wealth, and power, which has been published in the eighteenth volume of the Transactions of the Royal Irish Academy. This essay, while it stamped its author as a most profound scholar, acute observer, and a most honest and laborious searcher after truth, with a mind unbiassed by theory, uninfluenced by the dogma of the schools, or the authority of names, has been of immense value to Irish history, not only on account of the sources of learning which it discloses, but for the lesson it teaches to all future gleaners in this field of patient investigation and judicious critical research. If Dr. Petrie had never written another line, or established another truth, this memoir upon Tara would have established his fame, and formed the model from which the history of Ireland may hereafter be framed or worked out.

Strangers, and foreigners speaking the English language, and Irishmen also, visit the site of this regal city; and some carry with them the quarto volume of the Academy's Transactions, as they would one of "Murray's Hand-books," and expect that it will point out at once, and with but little trouble, all the ancient halls and courts, so poetically described in some of the fanciful histories of Ireland. On the one, however, they find nothing but a collection of earthen mounds and grassy undulations, a few time-worn stones, and an old churchyard, crowning the top of rather an unpicturesque hill; and in the text of the other a mass of what is, to them, dry, unintelligible, documentary evidence, partly written in a language the very characters of which they are unacquainted with, and interspersed with quaint old poems, containing names of men and things quite unpronounceable by their vocal organs. Such casual visitors spend an hour at Tara, and some read the commentary upon it, and acknowledge that they are none the wiser; and this we can fully conceive. To understand the one, and effectually to observe the other, requires a certain amount of schooling in the investigation of the sources of history, an eye practised to the forms of ancient remains, and an ear attuned to the language of archæology; but, even with all or any of these acquirements, there is a feeling, an innate feeling, necessary, which no art can teach, no schooling generate; for

there *are* hundreds whose valour or patriotism would *not* be aroused on the field of Marathon, nor their piety awakened amidst the ruins of Iona.

The following brief notice of Tara, intended chiefly as an itinerary, may, however, serve to direct the tourist's attention to the objects best worthy of attention in this celebrated locality.

Retracing our steps for a short way from Riverstown, we meet another ruined fortress at the cross-roads of Castletown, and now we commence the ascent of Tara by the ancient road leading to the north, the *Slighe Fan na g-Carbad*, or Slope of the Chariots, which has been mentioned in the old topographical descriptions of this renowned locality. The first object which demands attention is the *Teach Miodhchuarta*, or great Banqueting Hall, the chief monument of all, which runs north and south, a deep excavation, with parallel sides, rising up a gentle ascent of the hill, 360 feet long, and 40 wide, the sides being formed by a raised *mur*, or earth embankment, in which a number of excavations or gaps may be observed, corresponding to the doors which led into the great hall, "the house of the thousand soldiers," the locality where the Feis Teamhrach, or solemn assembly of Tara, was held. Standing at the top or southern extremity of this remain, and bearing in mind the various prose and bardic histories of the Irish annalists, one cannot help reverting to ancient heroic times, and again, in imagination, peopling it with its early occupants. Here sat in days of yore kings with golden crowns upon their heads; warriors with brazen swords in their hands; bards and minstrels with their harps; grey-bearded ollamhs; druids with their oak-leaf crowns; learned historians; wise brehons and subtle lawyers; the physicians; the smiths, artificers, charioteers, huntsmen, architects; the chess-players and cup-bearers, together with crowds of servants and retainers, whose places are all specified in the ancient annals relating to Tara.* Sneer not at the Irishman's veneration for this spot; the history of its "long-faded glories" is still preserved; the memories of Tara have remained a silver thread in the garment of sackcloth he has worn for centuries.

* We wish our space permitted of our introducing here some of the poems of the Book of Rights, describing the feasts at Teamhair, lately published by the Irish Celtic Society. It should be consulted by every visitor to Tara.

Most probably a wooden building covered in at top extended along the earthen elevations still remaining at the sides of this great banqueting-hall. The prospect from this site now is one of the most extensive and beautiful in Meath, and fully as awakening as that wherewith Demosthenes, standing on the Areopagus, aroused the valour of the ancient Athenians.

In the adjoining field is *Rath Caelchon*, and beyond it are the remains of two circular duns, but greatly obliterated by plantations; one of these is *Rath-Grainne*, and the other, together with the small well of Tober Finn, are now scarcely perceptible; none of these, however, are of sufficient importance to require particular notice in a popular description like the present.

Ascending the slope towards the south we gain the top of the hill, crowned by the *Rath-na-Seanadh*, the Rath of the Synods, or the King's Chair, where it is said the tent of Adamnan was pitched, presenting a double wall of circumvallation, the eastern side of which has been cut off by the adjoining churchyard. Upon this rath in particular, it is more than probable, some of the synods at Tara, in Christian times, were held. It is the highest spot upon the hill, being 512 feet above the level of the sea. The two beautiful gold torques, preserved in the collection of the Royal Irish Academy, were found by a boy in the side of this hill some years ago. Immediately adjoining this elevation stands the modern church, the decorated western window of which was removed from the ruins of an ancient ecclesiastical building which existed here within the present century.* Within the enclosure of the surrounding churchyard we find some objects of antiquarian interest, especially a flat pillar-stone about six feet high, supposed to be the shaft of the cross of St. Adamnan, on the eastern face of which is carved, in relief, a rude human figure, about eighteen inches high.† In its vicinity we find a short


* There is a view of this church given in Grose's *Antiquities*, vol. ii. p. 88.

† This small naked figure, with something like horns upon the head, is from its position evidently one of those curious pieces of ancient sculpture, popularly known in some places as *Sheelah Ny Giggs*, frequently found inserted into the walls of some early Christian buildings, and of which there are one or two specimens in the Museum of the Royal Irish Academy. There is one to be seen built into the side wall of the ruined Church at Dowth facing the Boyne. See the description of that building.

pillar-stone, not unlike some of those at New Grange. This is supposed to be one of the two druidical stones called *Bloc* and *Bluicni*, which used to open out to admit the chariot of the king at his coronation.

Proceeding still southward we pass into the great oval enclosure of the *Rath na Riogh*, the King's Rath or the Cathair of Crofinn, the most extensive of all the earthen circles at Tara, measuring upwards of 280 yards in length in its longest dimensions. It is obliterated in several places, but a sufficiency still remains to point out its site. Immediately within its northern boundary we find the mound of the hostages, *Dumha-na-Ngiall*, a small circular moat, so named in memory of the hostages which King Cormac took from the different provinces, and on which formerly lay the obelistic monolith, believed to be the Lia Fail, or Stone of Destiny. Nearly in the centre we meet the triple enclosure of the *Forradh*; and toward the south-east and immediately adjoining the latter, the *Teach Cormaic*, the House of Cormac.

Between the house of Cormac and the rath of the Forradh existed, it is supposed, the ruins of *Tea-mur*, from which Temur, or Tara, takes its name, in memory of a Milesian queen called Tea. In the centre of the internal mound of the Forradh stands an upright stele or circular pillar-stone, which was formerly on the top of the Mound of the Hostages, but was removed to this spot in the year 1798, and erected as a headstone to the grave of thirty-seven of the insurgents, who were killed in a skirmish with the military in this neighbourhood. Dr. Petrie supposes this stone to be the celebrated *Lia Fail*, on which the early Irish kings were crowned, and which has been generally believed to have been carried to Scotland for the coronation of Fergus Mac Eark, and afterwards removed by Edward I. from Scone to Westminster Abbey. The Lia Fail was the stone so famed in ancient history, which was said to have roared beneath the Irish kings at the time of their in-



auguration. For the various authorities bearing upon this point, we must refer our readers to the "History and Antiquities of Tara Hill," already so frequently referred to. We fully acknowledge the force of the reasoning of Dr. Petrie on this subject, and admit the validity of his arguments with respect to the history of the Stone of Destiny, and we must believe that it is not that now in Westminster Abbey; but at the same time we are not by any means convinced that this *round pillar stone*, now placed over the croppies' grave, is *the* stone. Perhaps the *flat sculptured stone*, latterly called the Cross of St. Adamnan, may have been it.*

To the east of the Forradh, immediately adjoining the road, is the Well of Neamhnach [*Newnagh*], a beautiful spring, formerly shaded by a magnificent ash tree, the roots of which still stretch over it. The only two other object of general interest to the tourist here are, the *Rath of Laoghaire*, upon the slope of the hill towards the south, in which it is said King Laoghaire was buried in a standing position; and about a quarter of a mile distant, in the same direction, among some trees crowning an adjoining elevation, the great fort called the Rath of Queen Meve, which is very well worth inspection.

From the centre of the Forradh on the one side, and the King's Chair upon the other, we gain most extensive views of the great plains of Meath, extending along the Boyne from the towers of Trim to the wooded heights of Slane; stretching over the course of the Blackwater to the regal hill of Tailtean, to Kells and to the mountains of Cavan; and, towards the south-east, taking in the tower of Skreen and the ancient castle adjoining.

There were several ancient roads leading through and from the royal residence at Tara, but, without entering into the general history and topography of the place, their description would be uninteresting. We regret to say that one of the raths of Tara was removed the year before last, by an inhabitant of Navan, for manure; and we understand a similar act of desecration is meditated towards another during the present harvest. Surely the proprietor of the soil, if acquainted with

* This opinion was likewise held by O'Donovan. See his valuable and voluminous letters on Tara, in the Ordnance Library, which we have lately perused.

these circumstances, would interfere to prevent further obliteration of these most interesting historic remains.

While our limits forbid our entering at all upon the records of Tara,—for the account which we could here afford to give would be so meagre, that we feel it would rather obscure than elucidate its true history,—we cannot forbear, in concluding this brief itinerary, quoting, in the subjoined note, the following hymn of St. Patrick, composed, it is believed, at the time he visited Tara, immediately after his arrival in Ireland, and which is supposed to have been sung by the Saint and his attendants as he approached this seat of monarchy surrounded by his Pagan enemies. It is not of so much consequence here, whether it really was composed by Patrick, or not until some two or three centuries after his death; its authenticity as a very ancient document has been fully established, and it exhibits in a remarkable manner the purity of faith of the early Irish Christian Church. It has been published by Dr. Petrie from the celebrated *Liber Hymnorum*, preserved in the Library of Trinity College, Dublin, a manuscript which, in the opinion of Archbishop Ussher, as expressed in a letter to Vossius, was in his time a thousand years old. It is written in the very ancient Irish dialect in which the Brehon laws are preserved, and seems to be oldest Christian Irish document extant.*

* The translation is as follows :

“ At Temur to-day I invoke the mighty power of the Trinity. I believe in the Trinity under the Unity of the God of the Elements.

“ At Temur to-day I place the virtue of the Birth of Christ with his Baptism, the virtue of his Crucifixion with his Burial, the virtue of his Resurrection with his Ascension, the virtue of the coming to the eternal Judgment.

“ At Temur to-day I place the virtue of the love of Seraphin; the virtue which exists in the obedience of angels, in the hope of the Resurrection to eternal reward, in the prayers of the noble fathers, in the predictions of the prophets, in the preaching of the apostles, in the faith of the confessors, in the purity of the holy virgins, in the deeds of just men.

“ At Temur to-day I place the strength of heaven, the light of the sun, the whiteness of snow, the force of fire, the rapidity of lightning, the swiftness of the wind, the depth of the sea, the stability of the earth, the hardness of rocks between me and the powers of paganism and demons.

“ At Temur to-day may the strength of God pilot me, may the power of God preserve me, may the wisdom of God instruct me, may the eye of God view me, may the ear of God hear me, may the word of God render me eloquent, may the hand of God protect me, may the way of God direct me, may the shield of God defend me, may the host of God guard me against the snares

It is with some reluctance that we so soon return to the Boyne ; for at Loch-Gabhair, or Lough-Gower, near Dunshaughlin, a few miles from hence, we could have introduced our readers to some subjects connected with the domestic life and usages of the Irish people, prior to the tenth century, from a vast collection of weapons, domestic implements, and culinary utensils, and even objects employed in the toilet, as well as an enormous heap of animal remains, which were discovered in that locality not very long ago ; and have entered, at some length, and from most valuable authentic materials within our reach, into details concerning the races of cattle, and animals of the chase, as well as those used for domestic purposes, at that period in Ireland. But these we also fear to touch on ; they are rather without the pale of this guide book ; we cannot at present do more than direct attention to this interesting locality, and to the subjects which these remains illustrate. Perhaps upon some future occasion we may conduct the pilgrims of the Boyne to Skreen and Dunshaughlin.*

Crossing the left bank of the Boyne at Bellinter bridge we enter the noble demesne of Ardsallagh,† now belonging to the

of demons, the temptations of vices, the inclinations of the mind, against every man who meditates evil to me, far or near, alone or in company.

" I place all these powers between me and every evil unmerciful power directed against my soul and my body, as a protection against the incantations of false prophets, against the black laws of Gentilism, against the false laws of heresy, against the treachery of idolatry, against the spells of women, smiths, and Druids, against every knowledge which blinds the soul of man. May Christ to-day protect me against poison, against burning, against drowning, against wounding, until I deserve much reward.

" Christ be with me, Christ before me, Christ after me, Christ in me, Christ under me, Christ over me, Christ at my right, Christ at my left, Christ at this side, Christ at that side, Christ at my back.

" Christ be in the heart of each person whom I speak to, Christ in the mouth of each person who speaks to me, Christ in each eye which sees me, Christ in each ear which hears me.

" At Temur to-day I invoke the mighty power of the Trinity. I believe in the Trinity under the Unity of the God of the elements.

" Salvation is the Lord's, salvation is the Lord's, salvation is Christ's. May thy salvation, O Lord, be always with us."

* See Proceedings of the Royal Irish Academy, vol. i. p. 424, and Annals of the Four Masters, A. D. 675-848.

† Ardsallagh would seem to be an anglicised form of Ard-salach, i. e., the dirty height ; but it is more probable that its original form was Ard-saileach, i. e., *altitudo saliceti*, or the height of the willows or willows, which may possibly have flourished on the high banks of the Boyne here of old.

Duke of Bedford, who has recently erected here a handsome Elizabethan mansion, in which report whispers he will annually spend some time. In no part of its course does the river present the same extreme calmness and repose as here. Widening into deep, still pools, shaded by aged timber, and fringed with wild plants of gigantic growth, huge colts-foot; with the modest blue forget-me-not and the little yellow potentilla peeping through their dark umbrageous foliage; long, topling bulrushes, fragrant meadow-sweet, and broad water-lilies, stretch in wild luxuriance along the placid banks. Long avenues of lime trees, and groves of tall grey-stemmed beeches with arcades of aged yew, give an air of antiquity as well as grandeur to this handsome park. One almost always expects to meet some remnant of ecclesiastical buildings where aged yew trees abound, and accordingly we read that St. Finian founded the monastery of Escair-branain near this, but at present even the site of that ancient edifice is unknown.

We are not, however, altogether disappointed in our search, for the holy well of St. Bridget still exists here, in the immediate vicinity of the house, and but a few paces from the river. Although a modern cut stone pointed arch has by some tasteless architect been thrown over it, still the thorns and elders that overhang its pure waters, the mullein, the ground ivy, and wild geraniums that droop and festoon the adjoining bank, and the old carved head of St. Bridget, with its plaited hair and prim formal features,—the very impersonation of a mother abbess,—all combine to render this once celebrated spot a pleasing picture. We wish we could say as much for the house, which looks as if it was in a sort of half-mourning, being built of very dark—almost black—limestone, with all the quoins, chimneys, and ornamental portions nearly white. Time, however, may greatly assist to remedy this, and soften the glaring effect which it now presents, but we greatly fear it will never add to its height, equalize its proportions, nor mend the deficiency in many of its details. Still, with all this, it is a very fine pile of building, and every well-wisher of the country should rejoice to see such mansions rising in the land. The interior is as yet unfurnished. A series of green terraces,—in the olden style, when clipt yew trees, quaint statues, and urns, were their general accompaniments,—lead from the principal entrance down a gentle slope towards the river side.

The Boyne now turns nearly northwards to Navan. Upon its left bank, about half a mile from the river, and not far from the road leading from Bellinter to Navan, the old church of Cannonstown or Cannistown claims a passing notice, from its picturesqueness, and its affording several beautiful specimens of early Irish ecclesiastical architecture. The circular choir-arch, springing from highly-decorated imposts, the bell-turret in the western gable, the nave and east window, with the piscina, afford the tourist and the antiquarian student a good opportunity for studying one of our churches of the thirteenth century; and, in the surrounding graveyard, rude portions of a cross and a font, now used as head-stones, give additional interest to the investigation of the tourist; while some noble ash trees, the usual guardians of our graveyards and ruined churches, greatly assist to heighten the picture of Cannistown.



At Kilcarn, immediately adjoining, the Dublin road is carried over the Boyne by a well-built bridge, and continues upon the western bank, between which and the river intervenes a narrow stripe of greensward, while the opposite, or eastern bank, rises abruptly from the water's edge, and forms a pleasing wooded rampart from this point to Navan.

Let us cross the river again, and make a little detour of about half a mile from this spot to view the old church of Kilcarn, which derives its name from an adjoining cairn. It is now a complete ruin, claiming attention only from the ancient baptismal font, which was recently exhumed here, but which has been very lately removed into the neighbouring Roman Catholic chapel of Johnstown.* Mr. Wakeman, in his Hand-

* The preservation of this beautiful font is due to an intelligent blacksmith, named Walsh, who resides in the neighbourhood, and whose family burial-

book of Irish Antiquities, has given the following description and illustrations of this most interesting relic:

"Placed upon its shaft, as represented in the cut, it measures in height about three feet six inches; the basin is two feet ten inches in diameter, and thirteen inches deep. The heads of the niches, twelve in number, with which its sides are carved, are enriched with foliage of a graceful but uniform character, and the miniature buttresses which separate the niches were decorated with crockets, the bases resting upon heads, grotesque animals, or human figures, carved as brackets. The figures within the niches



are executed with a wonderful degree of care, the drapery being represented with each minute crease or fold well expressed. They were evidently intended to represent Christ, the Virgin Mary, and the twelve Apostles. All the figures are seated. Our Saviour, crowned as a king, and holding in his hand the globe and cross, is in the act of blessing the Virgin,

place is in this churchyard. About twenty years ago this font stood in the old ruined church, and it was the usual practice for the "boys" who came to a funeral to try who could throw a stone into it with greatest ease and adroitness. Old Walsh, who is "a bit of an antiquary," perceiving the too probable fate of this beautifully sculptured stone, dug a great hole and buried it within the precincts of the church, where it remained until he exhumed it, the year before last, for Mr. Wakeman to make a drawing of it. It is now, as mentioned in the text, in the chapel of Johnstown, where it has been set up as a holy water vessel immediately inside the door, but placed so near the wall that a considerable portion of its sculpture is obscured.

who also is crowned, the 'Queen of Heaven.' The figures of most of the Apostles can easily be identified: St. Peter, by his key; St. Andrew, by his cross of peculiar shape; and so on.



They are represented barefooted, and each holds a book in one hand. The font did not, when drawn, rest upon its ancient shaft, nor had it done so in the memory of the old people of



the neighbouring village; but the shaft still remained within the church, and the whole has since been restored."

Immediately approaching Navan, the river makes a bold sweep round the foot of the hill, from which rise up the ruins of Athlumney Castle, the dilapidated towers and tall gables of which shoot above the trees that surround the commanding eminence on which it is placed, while glimpses of its broad, stone-sashed, and picturesque windows, of the style of the end of the sixteenth century, are caught through the openings in the plantation which surrounds the height on which it stands. This beautiful pile consists of a large square keep, with stone

arched floors and passages rising into a tower,* from which a noble view can be obtained of a clear day: and a more modern castellated mansion, with square stone-mullioned windows, tall chimneys, and several gables in the side walls. In the immediate vicinity is the ruin of a small church of about the fourteenth



century, with a triple belfry in the western gable. In front of this ancient feudal hall, and immediately crowning the high eastern bank of the river, on the grounds of Dr. Hudson, the present owner of Athlumney, an exceedingly perfect and most gracefully shaped sepulchral mound is placed. If it were opened under the direction of persons competent to the task, the antiquary and ethnologist might expect the discovery of most interesting remains within it.

Of the history of the castle of Athlumney and its adjoining church, there is little known with certainty; but, standing on the left bank of the Boyne, opposite this point, we cannot help recalling the story of the heroism of its last lord, Sir Launcelot Dowdall, who, hearing of the issue of the battle of the Boyne, and the fate of the monarch to whose religion and politics his family had been so long attached, and fearing the approach of the victorious English army, declared, on the news reaching him, that the Prince of Orange should never rest under his ancestral roof. The threat was carried into execution. Dowdall set fire to his castle at nightfall, and, crossing the Boyne, sat down upon its opposite bank, from whence, as tradition re-

* This fine old tower is now draped with ivy, planted by the hand of Miss Edgeworth.

ports, he beheld the last timber in his noble mansion blazing and flickering in the calm summer's night, then crash amidst the smouldering ruins; and when its final eructation of smoke and flame was given forth, and the pale light of morning was stealing over that scene of desolation, with an aching and a despairing heart he turned from the once happy scene of his youth and manhood, and, flying to the Continent, shortly after his royal master, never returned to this country. All that remained of this castle and estate were forfeited in 1700. Many a gallant Irish soldier lost his life, and many a noble Irish gentleman forfeited his broad lands, that day. We wish their cause had been a better one, and the monarch for whom they bled more worthy such an honour.*

The inhabitants of Navan, like those of most Irish towns through which a river runs, have turned their backs upon the stream, scarcely a glimpse of which can be obtained from any of its narrow streets. There is here a picturesque weir, and immediately below the bridge which crosses it on the Drogheda road, the Boyne receives the Blackwater, which is there nearly as large as the stream into which it flows. There are also two valuable and extensive flour mills at this point.

As we only engaged to present our readers with scenes of beauty or of interest, we cannot be expected to devote much of our space to a description of Navan!—a dirty, ill-built, straggling collection of houses, boasting the honour of having been *half* a county-town. It contains, however, 5000 inha-

* Tradition gives us another, but by no means so probable a story about Athlumney castle, which refers to an earlier date. It is said that two sisters occupied the ancient castles of Athlumney and Blackcastle, which latter was situated on the opposite bank of the river; and the heroine of the latter, jealous of her rival in Athlumney, took the following means of being revenged. She made her enter into an agreement, that to prevent their mansions falling into the hands of Cromwell and his soldiers, they should set fire to them at the same moment, as soon as the news of his approach reached them, and that a fire being lighted upon one was to be the signal for the conflagration of the other. In the mean time the wily mistress of Blackcastle had a quantity of dry brush-wood placed on one of the towers of the castle, which, upon a certain night, she lighted; and the inhabitants of Athlumney perceiving the appointed signal, set fire to their mansion, and burned it to the ground. In the morning the deception was manifest. Athlumney was a mass of blackened, smoking ruins, while Blackcastle still reared its proud form above the woods, and still afforded shelter to its haughty mistress.

bitants, and is not without its wealthy trader and thriving petty merchant. A church, a chapel, an infirmary, a bride-well, workhouse, and fever hospital, constitute its modern erections. It was originally a parliamentary borough, and in olden times was a place of considerable note, having been walled by Hugh de Lacy, and containing an abbey, founded by Jocelyn de Nangle, on the site now occupied by the barrack. It is probable that a cross existed in this town; and, in all likelihood, it stood in the market-place, where all the passing funerals now make a solemn circuit. A friend of our's possesses a portion of a small sculptured cross lately dug up at Navan.

The original name of Navan was Nuachongbhail. The Annals of the Four Masters afford us an account of a great plundering of Meath, as far as Tara, by the O'Neills and O'Donnells, in the year 1539: "They obtained immense and innumerable spoils on this expedition, for the Irish had not in latter times assembled to oppose the English army that destroyed more of the property of Meath than this plundering army; for many were spoils of gold and silver, copper, iron, and every sort of goods and valuables, besides what they took from the towns of Ardee and Nuachongbhail, which they utterly plundered on that expedition."* When Lord Justice Leonard heard of this, he collected all the English forces in Ireland, and pursuing the invaders came up with them at Ballyhoe in Farney, where a battle ensued, in which the Irish were completely routed.†

A branch of the Dublin and Drogheda Railway has lately been extended to this place; it crosses the Boyne upon a series of arches immediately below Athlumney Castle, and in the

* In a note upon this word, *Nuachongbhail*, by O'Donovan, in the second volume of the published copy of the Annals, we read: "It appears from the Life of St. Fechin, published by Colgan, that this was the ancient name of the place where the town of Navan, in Meath, now stands: 'Nuachongbhail est oppidum Mediæ ad ripam Boinnii fluvii a Pontani [Drogheda] decem millibus passuum distans ab Authrumnia quinque.'—*Acta Sanct.* pp. 135, 141.

"In the account of this invasion of the Pale given in the Annals of Kilronan, this town is called an Uairn, which is its present Irish name, as pronounced by the natives of Meath. Ware, who seems to have known the ancient and modern names of this place, calls it Navan, in his Annals of Ireland at this year."

† See Some Account of the Territory and Dominion of Farney, by E. P. Shirley, Esq., M. P., already referred to.

cuttings on the eastern side of the river were discovered a quantity of most interesting antiquities, bridle-bits and horse trappings of iron, bronze, and silver, rings, buckles, head-stalls, peytrells, and clasps, &c. ; besides a large collection of bones, both human and those of the lower animals.* While these pages were passing through the press, a most extensive souterrain was discovered in the cutting of the railway on the western bank, just under Athlumney, consisting of a straight passage fifty-three feet and a-half long, eight broad, and six high, branching into two smaller passages which run off at right angles from it, and ending in two circular bee-hive shaped chambers, precisely similar to those at Clady, together forming the figure of a cross. The walls of this great cave having risen to a height of about four feet and a half, they then begin to incline, and the roof is formed by enormous flag-stones laid across ; these stones are all rough and undressed, and are placed together without mortar or cement. This extensive cave, so recently discovered, will form an additional object of attraction to the tourist. A few bones of oxen are all that have as yet been found in it.†

The meeting of the waters of the Boyne and Blackwater at Navan forms the natural division between the second and third portions of the former. Let us in the next chapter follow and describe the course of the latter.

* These antiquities are in the Museum of the Royal Irish Academy ; so far so good. A very perfect human skull, and fragments of two others, were found in this heap. For these fragments (which are good specimens of the long-headed early Irish race) we are indebted to Mr. Wakeman. The only perfect head found was sent out of the country ; it was given to the late Dr. Prichard, immediately before his death, and no account of it has since appeared. We are not collectors ; we have not the least desire to *possess* either bones or brasses ; if such came into our possession we should feel ourselves bound to give them, sooner or later, either to the national collection of the Academy or to some of our friends who might have museums ; but we confess we feel indignant when we see things of this class sent out of the country without either drawings, casts, or models, having been first made of them. Like ourselves, our late friend Dr. Prichard did not value skulls merely as old bones, so a good cast of this head found at Navan would have answered all his purposes just as well.

† A somewhat similar cave may be seen in Mr. Metge's grounds, not far distant from Navan.

CHAPTER VI.

THE BLACKWATER.

GENERAL VIEW OF THE BLACKWATER OF MEATH; ORIGIN OF ITS NAME.—ST. PATRICK'S CURSE.—THE RIVER'S SOURCE AT LOUGH RAMOR.—VIRGINIA.—ST. KIERAN'S WELL, CHURCH, AND CROSSES.—SQUARE FORTS.—HILL OF LLOYD.—KELLS; ITS EARLY HISTORY.—HOUSE OF ST. COLUMBKILL.—ROUND TOWER.—THE CROSS.—ANNALS OF KELLS.—HEADFORD.—TAILTEAN, ONE OF THE ANCIENT SEATS OF MONARCHY; ITS EARLY HISTORY; ITS GAMES, BATTLES, FAIRS, AND MARRIAGES.—THE PRESENT APPEARANCE OF Teltown; ITS HILL, RATHS, AND LEGENDS.—ST. PATRICK AND KING LOEGHAIRE.—DONAGHPATRICK; ITS HISTORY; THE MOATE AND CHURCHYARD.—THE CHURCH AND CASTLE OF LISCAWTON.—RATHALDRON; ITS CASTLE.—MONUMENTAL CROSS OF NEVINSTOWN.

THE Blackwater runs out of Lough Ramor, or Loch Muinreahar, in the south-eastern extremity of the county of Cavan; it would appear, however, from some notices in the ancient topographies, that the true source of the river was in the hilly district of Sliabh-Guaire, to the north of Virginia. This river resembles in a remarkable manner that to which it is tributary, the Boyne, exhibiting the same even but tortuous course, winding through the same fertile meadows, and its banks presenting similar scenes of sylvan beauty, adorned by the same description of feudal and monastic remains, and commemorated by localities memorable in history and in song; the palaces of Pagan kings; the raths of warriors; the pillar-stones of Druids; the footprints of early Christian saints, their oratories, round towers, and churches, their wells and crosses; and the battle-fields, fortresses, and castellated mansions of more modern times. The entire length of the river, following its various windings from its source to Navan, is about twenty miles; its direction is from north-west to south-east; and the great northern road from Navan to Virginia, through Kells, passes first upon its northern, and then upon its southern bank, for the entire of its course, and so close to it that nearly all the objects of interest, or that are worthy of inspection, on this river, are more easy of access than those on any other which we are acquainted with.

The name Blackwater is applied to several rivers in Ireland, the most celebrated of which is the magnificent Blackwater of

the south.* In the topographical description of the Boyne at the commencement of this work, we hazarded a conjecture (p. 25), that the river called Finnabhainn [i. e. White River] in the very ancient histories was no other than that now denominated the Blackwater of Meath, because it is said to have its source in Sliabh-Guaire,† a district in the vicinity of Lough Ramor, to which we have already alluded ; and a small stream which flows into this lake of Cavan lends support to this idea, and is in all probability the true source of the river, in the same manner as the Shannon, though said to rise in Lough Allen, has its real source in the neighbouring mountain of Sliabh an Iarainn. *Abhainn Sele* was the name of this river till the time of St. Patrick, who, having cursed it, its waters are said to have assumed a peculiar dark hue, and it has ever since been known by its present name of *Abhainn Dubh*. The circumstance is thus recorded in a passage in the Tripartite Life of St. Patrick,‡ which likewise serves to fix the situation of Tailtean or Teltenia: “*Prima autem feria venit Patricius ad Talténiam: ubi regie nundinæ et publici regni ludi et certamina quotannis servari solebant. Ibiq̃ue convenit Carbreum Nielli filium, et Laogarii Regis fratrem fratriq̃ue animi ferociâ et incredulitate similem. Huic S. Patricius verbum vitæ prædicaret viamque salutis ostenderet, vir adamantini cordis, non solum recusavit prædicatæ veritate credere, sed viam vitæ proponenti machinabatur mortem: et in vicinio fluvio nomine Sele Sancti viri socios flagellis excepit, quia Patricius eum appellavit inimicum Dei.*”—*Trias Thaum.* p. 129. Colgan adds in a note: “*Fluvio nomine Sele, cap. 4, hodiè fluvius hic Abha-dhubh id est fluvius niger, appellatur.*”

We shall have occasion again to refer to this insult offered by the sons of Carbre and Loeghaire to Patrick, when we come to describe Teltown.

Lough Ramor, from which the Blackwater flows, is a very beautiful sheet of water, charmingly irregular, and studded with islands, several of which, as well as its undulating sides, are tastefully planted. The lake, which is said to have burst

* See Mr. O’Flanagan’s charming work on the southern Blackwater.

† See *Leabhar-na-gCeart*, or the Book of Rights, published by the Celtic Society, p. 188.

‡ *Trias Thaumaturga*, part. ii. c. 4, p. 173, N. 14.

from Sliabh Guaire,* is about five miles in length, and from a mile to a mile and a half in breadth. In the year A. D. 845, King Malachy I., who first broke down the Danish power in Ireland, attacked and destroyed an island in this lake, on which a number of Irish outlaws and rebels of Meath, who joined the Danes against their own monarch, had fortified themselves. The Irish annals state that these rebels were in the habit of plundering the districts in the neighbourhood of the lake "more Gentiliun;" and that Malachy destroyed their island, and put themselves to death. Upon its northern shore stands the neat little town of Virginia, where the tourist who may wish to visit the source of the Sele will find admirable accommodation. After a course of about a mile and a half, the river touches Meath at the barony of Castlekieran, having the coach-road parallel with, and but a short distance from it. It now completely enters Meath, through which county it passes during the remainder of its course. For the first few miles the only objects of antiquarian interest in its vicinity are a number of forts and earthen raths, which crowd upon both sides of the river, and show the military importance of this locality, as well as its populous condition, in early times. Several of these enclosures are of great extent, and two which stand upon the immediate brink of the stream are worthy of note, from the peculiarity of their form, being perfectly square.

About three miles above Kells, on the southern bank of the river we meet the first group of interesting antiquarian remains, consisting of the ancient Church of St. Kieran, with the remains of five termon crosses in its vicinity, four of which are placed north, south, east, and west of the ruin. The northern one was erected in a ford in the river, a very remarkable situation for one of these early Christian structures. The base still stands in its original locality, but the shaft, the arms, and the top were removed, it is said, many years ago, by some good Protestant, who, anxious to show his loyalty, as well as his detestation of such idolatrous structures, threw them into into an adjoining deep pool in the river. Such is one of the local traditions, but we shall presently relate another just as probable.

* Annals of the Four Masters, A. D. 2859 ; and see note †, p. 10.

The accompanying illustration represents the cross which exists upon the south side of the church. It is not quite so large as that upon the north, which measures twelve feet in height, although the upper portion (that above the circle) has been broken off. The western cross is very imperfect; one of its arms and a portion of the head having long since been destroyed. The old tradition current among the people here concerning these crosses is, that St. Kieran had a number of them hewn at the quarry of Carrickleck, and brought here to adorn his church. They were the wonder, the admiration, and—alas! that such a sentiment should enter into the breast of Christian saints—the envy also of all the neighbouring saints and church builders. St. Columb, who was then erecting his church and tower at Kells, cast, it is said, a longing eye upon St. Kieran's crosses: he came by night and surreptitiously abstracted at least three of these, which the traditional legend says are those now remaining at Kells. At last, upon the night that he was taking away the fourth, St. Kieran awoke, and caught him in this very act of petty larceny. Kieran immediately "buckled" in his brother of Kells, just as he was stepping into the ford of the river with the base of the cross on his back; but the latter being the younger and the stronger man, the cross-owner was soon worsted. He wasn't, however, to be bet so asily, so he still held fast by the thief, who, seeing that he could not get off clear with his booty, threw it into the middle of the river, from which it has never since been removed, and where, except during a heavy flood, it is always to be seen.

It is hard to hear those slanders of the good St. Columb, or



of any saint in the calendar; but still it must be confessed, that, notwithstanding his piety, and what appears to have been a stronger feeling with him, his taste for architecture and church founding, he was often the cause of fierce wars and family broils among his not very peaceable countrymen, constantly stirring up agitation and fomenting rebellion, for which he came under the just censure of his superiors, was obliged to do penance, and was finally, it is said, sent off to Iona, which was then, perhaps, a sort of Norfolk Island, to which unruly Irish saints were transported. These saintly errors are, it is true, but idle rumours, but some way or other dark allusions to them have crept into the Annals, and even into the written lives of our Irish saints, who, after all, appear to have been but men, swayed by like passions with poor sinning mortals of the present day.

The original name of this place, to which frequent references occur in the Annals, was *Bealach-duin*, the "Road or Pass of the Fort," and from the numerous raths in its vicinity, and all along the river, it must have been, like most other Irish names of places, a very significant appellation. Here we read that Ciaran, or Kieran, the Pious, died on the 14th of June, 770; so that, notwithstanding the force of tradition—to which, by the way, some of St. Columb's successors still attach so much value—authentic history enables us, from the positive anachronism of the legend, to acquit the great churchfounder of having stolen the crosses. The spot thus consecrated by St. Kieran was afterwards called *Disert Chiarain*, from which the present barony and parish of Castle-Kieran takes its name.*

The church, no portion of which can be regarded as the original structure founded by St. Kieran, is a small oblong building, erected apparently upon low arches, of a late period of Gothic architecture, and quite devoid of mouldings or or-

* See the Annals of the Four Masters at the years A. D. 770, 778, 855, 868, &c., with O'Donovan's notes thereon. These references are to volumes yet unpublished, and for permission to examine which we are deeply indebted to our friend George Smith, Esq. There was a *Patron* held here formerly. O'Clery places the festival day of St. Kieran on the 14th of June, the day of his death. Dean Butler, in his notes to John Dymmok's "Treatise on Ireland," published by the Archæological Society, says Castle-Kieran is sometimes called "Trystel Kieran," and that "there was a church here appropriated to the Priory of St. John the Baptist at Kells."

nament,—a sort of crypt. Its direction is, as usual, east and west. No doorway or window-case remains, to indicate by their style the period to which the church might be referred; but judging from the masonry, which consists of small stones and rubble-work set in an unusually great quantity of mortar, we should consider it an erection of a period not earlier than the fourteenth century. Of the three nearly perfect crosses, one is placed at a short distance to the west of the church, one to the south, and the third and largest, though least perfect, to the north. The base of a fourth is found to the east; so that originally the church must have been placed between four crosses. Unlike the exquisite remains of the same class, at Kells and Monasterboice, these crosses were, except the circle by which the head and arms are connected together, almost totally devoid of ornament or sculpture of any kind.

There is also in the graveyard a fine specimen of the oldest style of monumental stone found in Ireland, but it bears no inscription.



About a furlong's length to the west of the old church may be seen St. Kieran's well, one of the most beautiful holy wells in Ireland, and shaded by a hoary ash tree of surpassing size and beauty, which is faithfully represented in the accompanying graphic delineation. The well is situated on the side of a beautiful and exquisitely green sloping bank, upon which the neighbouring sheep love to congregate. It

springs from a limestone rock of considerable extent; and appears first in a small natural basin immediately at the foot of the tree.

Within the well are several trouts, each about half a pound weight. They have been there "as long as the oldest inhabitants can recollect," and, strange to tell, they are said not to have grown an ounce within that period! These fish are held in the highest veneration by the people, who, when the well is being annually cleansed of weeds, carefully preserve the blessed creatures, and replace them as soon as possible.

About ten years ago a report spread over Meath and the surrounding counties, that Saint Kieran's ash tree was bleeding, and thousands of people flocked to the place to witness the wonder, and many brought with them vessels and bottles in which they hoped to carry away a portion of the miraculous fluid. With this it was hoped they might perform cures such as "common doctors" could not even attempt.

"The holy wells—the living wells—the cool, the fresh, the pure—
A thousand ages rolled away, and still those founts endure;
And while their stainless chastity and lasting life have birth
Amid the oozy cells and caves of gross material earth,
The scripture of creation holds no fairer type than they—
That an immortal spirit can be linked with human clay!
How sweet, of old, the bubbling gush—no less to antlered race,
Than to the hunter and the hound that smote them in the chase!
The cottage hearth, the convent's wall, the battlemented tower,
Grew up around the crystal springs as well as flag and flower;
The brooklime and the water-cress were evidence of health,
Abiding in those basins, free to Poverty and Wealth:
The city sent pale sufferers there, the faded brow to dip,
And woo the water to depose some bloom upon the lip;
The wounded warrior dragged him towards the unforgotten tide,
And deemed the draught a heavenlier gift than triumph to his side.
The stag, the hunter, and the hound, the druid and the saint,
And anchorite are gone, and even the lineaments grown faint,
Of those old ruins into which, for monuments, had sunk
The glorious homes that held, like shrines, the monarch and the monk."*

The Blackwater, or Owen Duff, as it is called by the peasantry, now winds on towards Kells, the church and round tower of which appear in the distance; and to the south-west the beautifully verdant hill of Lloyd, with its lighthouse-like

* The Holy Wells of Ireland, by J. D. Fraser, in "The Ballad Poetry of Ireland."

observatory, from which a most commanding prospect can be obtained, attracts attention. The river then bends somewhat to the south, and in the splendid demesne of Headford spreads out into a series of small lakes and ponds, partly natural and partly artificial, and encloses several small islands. This noble demesne, belonging to the Marquis of Headford, though possessing no natural features that attract attention, "has in its general appearance a degree of magnificence arising from its extent, unity of design, the richness of the verdure, the long and gently inclined plains into which the surface is naturally disposed, and the arrangement and preservation of the plantations;"* but the grounds are at present very much neglected, and the long-continued want of a resident proprietor is but too manifest throughout.

Within three-quarters of a mile to the south-west of the river stands Kells, one of the most memorable places in early Irish ecclesiastical history. The modern town is pleasingly situated, and its principal streets present several very charming views of the adjoining ruins, of which the round tower, the beautifully sculptured cross in the market-place, and St. Columbkille's house in the north-western suburb, are the most remarkable. The neighbouring demesne of Headford, with some well-grown timber adjoining, the general graceful outline, and the fertility and high state of cultivation of the surrounding district, all conduce to set off to considerable advantage this little town. The population of this place in 1841 was 4205, located in about 600 houses.

The name by which this town is generally known in early Christian and middle age writings is Ceanannus, head-fort or residence—Kenlis. We read in the Annals of the Four Masters that, a few years prior to the Christian era, King Fiacha-Finnailches erected *Dun-Chuile-Sibrinne*, which MacGeoghegan, in his translation of the Annals of Clonmacnoise, says was certainly Kells. "It was by this king that the earth was first dug in Ireland that water might be in wells. It was difficult for the stalk to sustain its corn in his reign. Every calf that was brought forth in his reign was white-headed,"†—A. M.

* See Fraser's Hand-Book for Travellers in Ireland, p. 494.

† Annals of the Four Masters, with Translation and Notes, by John O'Donovan, Esq. Dublin: Hodges and Smith. Now in process of publication.


3972 to 3991,—and hence the King's cognomen of Finnailches, according to the bards. The celebrated Cormac Mac Art is said to have resided for some time at Kells. Dermot, the son of Fergus Kervail, made a grant of this place to St. Columb, who founded a monastery here about the year 550, and dedicated it to the Virgin Mary. No vestiges of this structure at present exist. There are, however, some architectural remains here, of about that period, of surpassing interest; of these perhaps the most interesting is that figured in the adjoining wood-cut, generally known as St. Columb's House, a small, arched, and stone-roofed building.*



This is supposed to have been used as a small chapel or oratory, as well as a dwelling-house, like what is called St. Kevin's Kitchen at Glendalough, and the house of St. Flannan at Killybegs. Several descriptions of this building have been given.

* The accompanying view of St. Columbkill's house, which will afford the reader a better idea of its appearance than any description of our's, was drawn by Mr. Wakeman, and published in his useful little work, already so frequently referred to.

The following, by Dr. Petrie, is the most accurate: "This remarkable building is, in its ground plan, of a simple oblong form, measuring externally twenty-three feet nine inches in length, and twenty-one feet in breadth, and the walls are three feet ten inches in thickness. It is roofed with stone, and measures in height, from its base to the vertex of the gable, thirty-eight feet; and as the height of the roof and width of the side walls are nearly equal, the gables form very nearly equilateral triangles. The lower part of the building is arched semi-circularly with stone, and has at the east end a small semicircular-headed window, about fifteen feet from the ground; and at the south side there is a second window with a triangular, or straight-lined head, about the same height from the ground, and measuring one foot nine inches in height. These windows splay considerably upon the inside. The present entrance doorway of this building, which is placed in the south wall, is obviously not original or ancient; and the original doorway, which is now built up, was placed in the west end, and at a height of eight feet from the ground. The apartment placed between the arched floor and the slanting roof is six feet in height, and appears to have been originally divided into three compartments of unequal size, of which the largest is lighted by a small aperture at the east end. In this chamber is a flat stone, six feet long and one foot thick, now called St. Columb's penitential bed."* The accompanying illustration shows the character of the angular-headed window just alluded to.



When we last visited this house it was inhabited by a miserable, wretched family.

We next turn to the round tower which stands beside the wall of the churchyard, and of which the illustration upon the next page is a very good view.

This tower is a very perfect specimen of those interesting and almost peculiarly Irish structures. It is about 100 feet high, with a door some ten feet from the ground. The top, though not the roof, is still nearly perfect; in it there are

* See Dr. Petrie's Essay on the Origin and Uses of the Round Towers of Ireland. Dublin: Hodges and Smith.

four windows, remarkable for presenting examples of the three varieties of such apertures found in round towers, namely, with square, round, and triangular heads.

As the conclusions arrived at by Dr. Petrie, with respect to the origin and uses of the Round Towers of Ireland, cannot be too widely disseminated, or too generally known, and as, moreover, this at Kells, and that at Donoughmore, on the Boyne, near Navan, are, even to the tourist and the popular reader, highly confirmatory of his views, we here insert the general results of his inquiries.



I. "That the towers are of Christian and ecclesiastical origin, and were erected at various periods between the fifth and thirteenth centuries." In support of this position the learned author remarks, that "the towers are never found unconnected with ancient ecclesiastical foundations. Their architectural styles exhibit no features or peculiarities not equally found in the *original* churches with which they are locally connected, when such remain. On several of them Christian emblems are observable, and others display in the details a style of architecture universally acknowledged to be of Christian origin. They possess invariably architectural features not found in any buildings in Ireland ascertained to be of Pagan times.

II. "That they were designed to answer, at least a twofold use, namely, to serve as belfries, and as keeps or places of strength, in which the sacred utensils, books, relics, and other valuables, were deposited, and into which the ecclesiastics to whom they belonged could retire for security in cases of sud-

den predatory attack." The proofs adduced in support of this are, that "their architectural construction, as will appear, eminently favours this conclusion. A variety of passages, extracted from our Annals and other authentic documents, will prove that they were constantly applied to both these purposes."

III. "That they were probably also used, when occasion required, as beacons and watch-towers. There are some historical evidences which render such a hypothesis extremely probable. The necessity which must have existed in early Christian times for such beacons and watch-towers, and the perfect fitness of the round towers to answer such purposes, will strongly support this conclusion."

Adjoining this round tower is an ancient cross, beautifully sculptured, eleven feet four inches high, the base of which has been very recently uncovered; and within the enclosure of the churchyard, near the belfry, the remains of a second, still larger, the shaft alone measuring ten feet six inches; the third—the great sculptured cross of Kells—stands in the market-place of the town.

The square bell-tower stands distinct and separate from the modern church; it consists of three stories ending in a spire; and some sculptured stones and tablets, probably much older than this structure, are built into its side walls, as well as an ancient inscription in old black letter characters, recording the re-edification of the adjoining church in 1578.*

* For the following literal transcript of this inscription we are indebted to our learned friend, Joseph Huband Smith, Esq. It is on two separate stones:

"The bodie of the church being in utter ruine and decaye was reedified in anno domini, 1578, et in anno rr Elizabeth xx throughte the Willge and care of the reberende father in God hughe brady bpsshop of meathe and Sir Thome Garuie archedieacon of the same and deane of christ church Dublin bothe of here maiestie is priue consaile Sir Henric Sidney knight of the nobill ordire being thene lord deputie &c. the said reediffing was begone and seatt forward be the adbyse and valy

"carfull travaill of the auncient burgis Nicholas B— then being suffraigne of kenllis 2 of Julii anno predicto with other valy furtherens bought the towff of this c upon his owin pris chargis God is not unright—at he shuld forget the worke and labour that preceede whiche lobe is shewed for his name is sake."

A few miles from Kells (but not sufficiently near to be included in our excursion along the Blackwater) is the old Church of Rathmore, a picturesque ruin, with a most interesting tablet still existing inserted in its walls; and a

The great Cross of Kells, of which we here present our readers with a wood engraving, is one of the most beautiful in Ireland, and, although not so tall or massive, may in elegance of design, in form, and in variety and perfection of sculpture, and the richness of ornament, be classed with the crosses of Monasterboice and Clonmacnoise. The shaft is eight feet nine inches high: when perfect, it must have been nearly twelve feet high. The width across the arms is five feet four inches. The top, which in our large Irish crosses is often carved in the shape of a small church or shrine, has been broken off, but the base, which is rather larger than usual, being fifteen feet in girth, is very perfect, and well worthy of minute attention. On it may be seen, as on some of the ancient friezes, a series of mounted figures, apparently in procession, in good relief. Both the figures of the men and horses remind us strongly of some of the old Greek and Roman friezes. The shaft, arms, and circle, are of one entire stone.*



Kells was at one time strongly fortified. The castle, said to have been erected by Walter de Lacy, stood near the site of the

tombstone erected in 1531, to the memory of Christopher Plunket, son of Sir Alexander Plunket, who was Lord Chancellor of Ireland in 1492. There is here also a fragment of a sepulchral cross. See Mr. Huband Smith's communication on the subject in the Proceedings of the Royal Irish Academy for 12th June, 1848, p. 184, vol. iv.

* There is a tradition current that the shaft of this cross was prostrate till placed upon its pedestal by Dean Swift. Another fact connected with this cross, still keenly remembered by the inhabitants of Kells, is, that it formed part of the gallows from which several men were hanged in 1798.

great cross, and one of the towers of the town wall still stand on the south-western side of the church.

The Annals of Kells would fill a volume such as this; we can here only allude to a few of the most remarkable historic events which occurred here. We already mentioned the erection of the early ecclesiastical buildings at Kells by St. Columb. It is recorded that in 806 Cellah, Abbot of Iona, took refuge here from the Norwegians, and repaired or rebuilt the abbey. Numerous battles were fought, both within and on the plains around Kells, which sustained several sieges, and was frequently plundered, sacked, burned, and destroyed; its churches robbed, its shrines polluted, its altars desecrated, its relics stolen; its abbots and monks murdered, and its soldiers and inhabitants either butchered or carried off as prisoners by the Irish themselves, by the English settlers, or by the Danish invaders, for upwards of nine hundred years. Plague, pestilence, and famine, the sword, fire, battle, murder, and sudden death, form the chief items in the records of this ancient and most celebrated place. We read that Sitric and the Danes of Dublin made great havoc of all things belonging to this abbey in 1108, and Edward Bruce defeated Lord Roger Mortimer, and burned the town of Kells in 1315;—and thus might we occupy an entire chapter.

One of the most valuable pieces of antiquity connected with this place, and which has come down to modern times, is the celebrated Book of Kells, a most beautifully illuminated Irish manuscript, still preserved in the library of Trinity College.

Descending the river upon the northern bank we arrive at Teltown, about midway between Kells and Navan. This is one of the most celebrated spots in Ireland; perhaps, next to Tara, it is the most ancient, if not the most notable. An entire chapter might be devoted to it, describing its topography, transcribing its annals, relating its legends,—Pagan and Christian,—and giving a detailed account of its battles, sham and real; its fairs, games, sports, and marriages; these, however, would far exceed the limits of a guide-book, intended chiefly to direct the tourist, and point out the scenic beauty, and the memorable localities upon the hitherto neglected Boyne and Blackwater, which is all this little work pretends to. Let the following notice suffice. Upon a green hill sloping gradually from the water's edge, and rising to a height of about 300

feet, amidst the most fertile grazing lands in Meath, if not in Ireland, may be seen a large earthen fort, about a furlong's length to the right of the road, with a few hollows or excavations in the adjoining lands, apparently the sites of small, dried up lakes; and to the left of the road, nearly opposite these, parts of the trench and embankments of two other forts, which, judging from the portions still remaining, must have been of immense size, greater even than any of those now existing at Tara. These mark the sites of the early Pagan settlement, and the position of the palace of Tailtean, one of the four royal residences which existed in Ireland in very early times.

The first notice which the Annals record of Tailtean (the name of which is still preserved in the modern Teltown) is, that in the year of the world 3370, in the reign of Lugh Lamhfhada, "The fair of Tailtean was established in commemoration and in remembrance of his foster-mother *Tailte*, the daughter of Maghmor, King of Spain, and the wife of Eochaidh, son of Erc, the last king of the Fírbolgs."* This fair continued down to the time of Roderick O'Connor, the last monarch of Ireland, and was held annually upon the first of August, which month derives its name in the Irish language from this very circumstance, being still called *Lugh-nasadh*, or Lugh's fair,—the Lammas day,—to which several superstitious rites and ancient ceremonies still attach throughout the country generally. Upon these occasions various sports and pastimes, a description of Olympic Games, were celebrated, consisting of feats of strength and agility in wrestling, boxing, running, and such-like manly sports, as well as horse races and chariot races. Besides these the people were entertained with shows and rude theatrical exhibitions. Among these latter are enumerated sham battles and also aquatic fights, which it is said were exhibited upon the artificial lakes, the sites of which are still pointed out. Tradition assigns the site of the fair to that portion of the great rath still existing upon the northern side of the road, and about a quarter of a mile to the north-east of the great fort, or Rath Dubh;† and here it is said the most remarkable of the Tel-

* Annals of the Kingdom of Ireland by the Four Masters.

† None of these localities, with the exception of the great fort and the two adjoining hollows, are marked upon the Ordnance Map. Indeed the remains of Tailtean have been, except by Mr. O'Donovan, in his unpublished letters,

town ceremonies took place—the marriages or betrothals. Upon one side of this great embankment were ranged, it is said, “the boys,” and on the other “the girls;” the former ogling, the latter blushing; for human nature is, we suppose, the same at all times and in all places, among our forefathers and mothers at Teltown upwards of a thousand years ago, or in a modern drawing-room, or at a flower-show or review. They then, having had a good view of each other, passed down a little to the south, where there is a deep hollow in the land, evidently formed artificially, probably the ditch of one of the ancient forts, and called *Lug-an-Eany*, where they became separated by a high wall, which prevented their seeing each other. In this wall, say the local traditions, there was a door with a small hole in it, through which each young lady passed her middle finger, which the men upon the other side looked at, and if any of them admired the finger he laid hold of it, and the lass to whom it belonged forthwith became his bride; so that we find a fair and pretty hand, a delicate and taper finger, with its snowy skin and delicately formed nail, were even more captivating among the Irish lads and lasses some twelve hundred years ago than they are at the present day. He took her for better for worse, but the key-hole or wooden ring was not as binding as the modern one of gold; for, by the laws of Tailtean, the marriage only held good for a year and a day. If the couple disagreed during that time they returned to Tailtean, walked into the centre of Rath Dubh, stood back to back, one facing the north, and the other the south, and walked out of the fort, a divorced couple, free to try their luck again at *Lug-an-Eany*.* What a pity there is no Teltown or Black Fort marriage in the present day! What numbers would take advantage of it!

In the bottom of this hollow there is a well, which in wet weather overflows, and its waters trickle down the adjoining hill towards the Blackwater. Leading nearly southward from this spot we pass down the remains of an ancient paved, but now grass-grown way, called “Cromwell’s road,” and near

altogether too much neglected. There exists ample material, both from the records and the existing remains here, for a very interesting archæological paper on the subject.

* A somewhat similar custom existed in Wales, and parts of England and Scotland, till very lately. The expression, “a Teltown marriage,” is often used in Meath to this day.

where this joins the modern main road there is another hollow, still containing some water, pointed out as the site of one of the artificial lakes. The fair of Tailtean was continued up to about eighty years ago, and some vestiges of the sports, particularly the fighting, existed within the memory of man at a *Patron* which used to be held on the opposite side of the river.*

The Great Fort, or *Rath Dubh*, measures round the outer wall of circumvallation 321 paces, having openings in it nearly due north and south. The height of the surrounding earthen embankment varies from fifteen to twenty feet. Standing in the centre of this great fort we again obtain one of those refreshing views which we have so often attempted to describe when following the course of the Boyne. Looking up towards the north-west, the hill of Lloyd presents a grand and imposing object. Below it the eye rests upon the steeple and round tower of Kells, appearing to rise out of the woods of Headford; while in the extreme distance the round hills of Cavan bound the horizon. Immediately around us is a country of immense fertility and with a gently undulating surface, divided into fields of great size,—that in which we stand contains nearly 100 acres,—bordered by rows of well-grown timber, rising out of tall quickset hedges. There is scarcely a cottage, or even a farmer's house, to be seen. All seems one vast pasture farm, through which the Sele winds in pleasing curves, presenting glimpses of its dark blue waters among the flowery meadows which stretch along its brink. The wooded hill of Foughan rises up beyond it to the south-west, and following its track by the little ruined church of Teltown, by the heights of Donaghpatrick, over the woods of Liscarton, above which the old castle in that locality topples, and by the plantations of Rathaldron, the eye rests upon the hills of Skreen and Tara in the extreme north-eastern distance.

St. Patrick visited the royal residence of Tailtean early in his missionary career, and not merely in the local legends, but in the written Lives of that saint, we meet with abundance of

* This meeting and rustic pastime was, we understand, suppressed by the neighbouring magistrates and clergy about thirty years ago, in consequence of the rioting which generally took place there. It is a remarkable circumstance, and confirmatory of the conjecture of its being a remnant of the Teltown sports, that this assembly, though called a *Patron*, was not held in honour of any saint, but upon Lammass Day.

tales and fables regarding the miracles and the wonders which he wrought here upon the sons and servants of Cairbre, brother of King Loeghaire.

Many of the legends told of Patrick by the people here are evidently but paraphrases of his "doings" at Tara. The Shadrach, Meshach, and Abed-nego story about the fire trial between the servant of Patrick and the servant of the Druid gets here a new dress, with new names and "entirely new scenery, machinery, decorations, and processions." King Loeghaire or Leary (not Cairbre), who was a wonderful Druid and powerful magician entirely, is the chief personage in the Tailtean fables. After being defeated in various trials of skill and necromancy with the saint, who could make no hand of him at all, Patrick was forced to put him down into a dark "condemned hole," near the river, called to this day, "an t-áithghearr go h-Iffrionn," "the short road to hell," where the heathen king, Loeghaire, is still believed to be, if he never got any farther. Some fool-hardy people went a few years ago to lift *mooreen* out of this spot, but they had scarcely broke the *scraw* that covered the soft surface of the hollow, when a terrible roaring was heard coming up out of the bottom of the earth, and presently a most vinimous sarpint, with a long mane and a head as big as a horse, riz up out of the pit, and looked about him; but when he saw nobody, for all the men had run away, he drew himself down again, and no one ever attempted to make any inquiries after the ould king of the black rath since. But all that is nothing to what happened at the building of Donpatrick Church hard by. Every one knows that Prince Conall gave the saint one of his beautiful raths there to build a church upon, and that the workmen engaged in the erection of it came very short of provisions one hard summer,—just, for all the world, like the year before last. Well, Loeghaire when he heard that, sent him a furiously wicked bull that was the terror of the whole country, and used to be horning and aiting every body that came next or nigh him,—he was as cross and as thievish as the ould king himself,—in hopes that he'd finish the blessed man all out. The baste was sent over to the other side of the water, and when he saw St. Patrick, he stopt bellowing and snorting all of a sudden, and was as quiet as a suckling calf. 'Kill him,' says the saint; so they made a great feast

of him. Next day the king came down to the river side, just walking along mighty easily, letting on as if he didn't want to know anything about what happened, but hoping all the while that the bull had made a meal of some of the good Christians. He wasn't long there when some of the saint's servants bid him the time of day, and told him how much they enjoyed the bull, which, we may be sure, was no ways pleasing to his majesty; but to convince him, not only of the truth of the story, but to give him a taste of his power, St. Patrick ordered his servants to bring out the well-picked bones, and to tie them up in the skin, and to throw them into the river to Leary. That was easy enough, but then comes the miracle. The bundle had hardly touched the water, when out of it rose the bull, well and harty, large as life, bone to bone, and sinew to sinew, and swam over to the king. And yet, for all this, history records that the old reprobate died in his mother Church, and was buried in the hill of Tara, in a standing position, accoutred in his battle dress. Conversions of old people or grown up men and women are not as common or as easy as people imagine.

A short distance above Teltown the river is crossed by Bloomsbury Bridge; but the tourist will find greater and more frequent objects of attraction on the northern bank, till he reaches Donaghpatrick, about a mile and a quarter lower down.

In the valley, by the water's edge, about midway between these two places, and beside a broad curve of the river, we meet the ruins of *Cill-Tailltean*, the little church of Teltown, which was plundered by Diarmaid Mac Murchadha and the Danes in 1156, and again by the same prince and the English in 1170, in their marauding excursions among the rich churches of East Meath.

We now arrive at Donaghpatrick, which takes its name from *Domnach-Padraig*, the ancient church of Patrick, which formerly stood here, on the site now occupied by the modern parish church. This was the "*Ecclesia Patricii Magna*," the Domnach Mor, or great church, sixty feet long, so frequently alluded to in our Irish hagiology,* one of the earliest daimhlaigs, or stone sacred edifices, erected in Ireland after the in-

* See Petrie's Round Towers.

troduction of Christianity. It is related in the life of St. Patrick, attributed to St. Evin, and published by Colgan in the *Trias Thaumaturga*, that Conall, the brother of King Loeghaire, who resided here, not only gladly accepted Christianity, and was baptized, but also showed great kindness to Patrick, and gave him his house or rath on which to erect a church; and the outline of this very cashel can still be discerned in the present graveyard. The only other evidence of great antiquity now remaining here, is what appears to be a fragment of a gable tombstone similar to that still existing at Slane, of which we give a drawing, in the description of that place (p. 182). It can be seen just protruding above ground to the south of the present church.

Upon the left of the road, as we approach the church, stands, without exception, one of the very finest raths of the military class to be seen in Ireland. It is of immense size, but, its outline being now obscured by trees and much underwood, it escaped the notice of the Ordnance surveyors, and has not been marked on the map of this part of Meath. It much resembles that at Downpatrick, consisting of a central circular mound, rising gradually out of several circumvallations, or earthen embankments, four of which can still be traced; the great ring fort at Dowth, and the King's Rath enclosing the Forradh at Tara, and Rath Dubh at Tailtean, extend over a greater space; but of its kind there is nothing to compare with this along the Boyne or Blackwater.

It is much to be regretted that earthen mounds of this description should be planted; a graceful tree at top, or a few growing on the sides, add to their picturesqueness; but covering them with trees and underwood quite obscures their form and conceals their purpose. May not this moat have been the celebrated Rath Airthir, the eastern fort, now Orisstown; or even the house which the good Conall erected for himself after he so hospitably gave his own to Patrick?

From hence to Navan objects of almost equal interest and beauty present themselves on both sides of the river. The scenery is the same, presenting graceful, well-wooded, swelling undulations of surface, adorned by the seats of resident proprietors, with some interesting antiquarian remains; castles, churches, moats, crosses, occurring in nearly equal numbers, and of similar value on both sides. Upon the south-western

bank we have Liscarton castle, and the ruins of its most beautiful Gothic church; Ardraccan, and the fine moat of Navan; and on the north-eastern road, Rathaldron House, and the old cross of Nevinstown, with a much finer view of the river and the surrounding country than that which can be obtained from the opposite side.



The accompanying view presents us with Liscarton castle, (which is still in part inhabited), and the adjoining dwelling-house. It is pleasantly situated on a green lawn sloping to the river: and a short distance to the west of it, surrounded with trees, stands the church just alluded to, forming in the shade of the surrounding grove, with its tall, light, pointed windows, a most charming picture.

This castle appears to have been, from its strength and extent, of great importance. We know little of its history, except that in 1633 it belonged to Sir William Talbot, Bart., who held it of the king *in capite per servitium militare*. It originally consisted of two large quadrangular towers, connected together by a large hall, the roof of which no longer exists, but its position is shown by marks in the wall at either end. The thatched, modern-looking building shown in the accompanying cut is a portion of one of the towers much reduced in height. The church is remarkable for the extreme beauty of its eastern and western windows, each of which consists of one great light, divided by a shaft branching off on a level with the spring of the arch into two members, which join the arch-head about the centre of the curve. An exquisite variety of

tracery, in the decorated style of Gothic architecture, fills the head of both windows, and the mouldings are deep and well executed. Upon the exterior face may be observed well carved human heads projecting from the drip stone. There were two doorways, one in each side wall, near the western end.

The moat of Navan, about a mile and a half lower down upon this side of the river, and which forms such a conspicuous object from all sides, is of the military class, and well worthy of inspection, from its size and its appearing to have been in part formed out of the natural hill.

Upon the opposite bank we have Gibbstown, with its noble approach, and Rathaldron castellated mansion, partly ancient and partly modern, approached by one of the finest avenues of lime trees in Meath, perhaps in Ireland; it consists of a strong, well-built quadrangular tower, of very considerable antiquity, to which a handsome castellated dwelling-house has lately been added. Not far from it, in a field towards the east, we meet the way-side cross of Nevinstown. As Mr. J. Huband Smith has presented the Royal Irish Academy with a detailed description of this relic, we shall here quote his judicious and accurate observations from the published Proceedings of that body:

"One side bears an inscription; the opposite has a shield, with armorial bearings, *party per pale*, nearly effaced. Beneath the dexter side are the initial letters M. C., and, under the sinister, M. D. The height of the shaft is at present three feet six inches above the slab, in which a socket is cut to receive the tenon upon the lower end of the shaft. This slab stands on a low grassy hillock, the remains, doubtless, of an ascent of three or four stone steps, which, when complete, the cross surmounted.

"A restoration of the entire inscription showed that the upper part of the shaft had been broken off, and with it the first line of the inscription. Of what remains the first line is illegible, but the rest is tolerably distinct. It is in the black-letter character of the sixteenth century, the letters being beautifully formed; and (filling up the contractions) it runs thus:

"'. . . . Armigeri, et Margareta Dexter uxoris ejus ac heredum eorum qui hanc crucem fecerunt anno Domini 1588 quorum animabus propicietur Deus, Amen.'

"This inscription leaves little doubt that this memorial was one of the wayside crosses so generally erected by the piety of individuals about the sixteenth and the preceding centuries, but which the ill-directed zeal of a subsequent period so unsparingly mutilated, and often wholly destroyed. Upon inquiry it proved that a road, leading from Navan to Rathaldron Castle, long the residence of one of the principal branches of the ancient family of the Cusacks, once passed close in front of this cross."

The name of the husband of Margaret Dexter Mr. Smith soon after learned from a manuscript in the possession of Mr. H. T. Cusack. "This MS. is written in French, and entitled 'An Historical Memoir and Genealogy of the ancient and illustrious House of Cusack, of the Kingdom of Ireland.' It appears to have been compiled by the Chevalier O'Gorman in the year 1767. It states that 'Michael de Cusack, lord of Portrane and Rathaldron, married Margaret Dexter, who brought him, as a marriage portion, the castle, town, and lands of Rathaldron. He was 'Greffier' [a term which Boyer translates 'Registrar,' or Keeper of the Rolls] of Westmeath and of Louth in 1553, one of the Barons of the Exchequer in 1580, and died in 1589.' From this it may be safely concluded that the initials 'M. C.' upon the cross are those of 'Michael Cusack,' and that his was the name sculptured on the upper part of the cross, now lost."

CHAPTER VII.

THE BOYNE FROM NAVAN TO SLANE.

DONAGHMORE ROUND TOWER.—BLACKCASTLE.—BABES' BRIDGE.—ARDMULCHAN.—DUNMOE.—STACKALLAN BRIDGE.—CASTLE DEXTER.—BEAUPARC.—FENNOR.—SLANE CASTLE.—THE HERMITAGE OF ST. EBC.—VIEW FROM THE HILL OF SLANE.—THE ARRIVAL OF ST. PATRICK.—NAME AND ORIGIN OF SLANE.—FERTA-FEAR FEIG.—THE MONASTIC AND ECCLESIASTICAL RUINS.—AN ANCIENT TOMB.

FROM Navan to the Boyne's mouth the river, though intersected by several weirs, and descending several rapids, has been rendered navigable by means of a canal, affording transit to lighters of several tons' burden, by which a considerable traffic, particularly of coals and corn, is carried on between this place and Drogheda. Along the road by this canal and the river the tourist can walk to Beauparc, or descend, as we have effected the voyage, in a boat, drawn by a single horse; and this mode of conveyance we would strongly recommend to our friends, not only as the least fatiguing, particularly for ladies, but also as enabling the tourist to cross the river at pleasure, for it is only in some places that the canal is necessary.

Immediately on leaving Navan, where the river resumes its original north-easterly direction, the scene reminds one strongly of some of the views upon the Dutch canals. The river here is deep, and its current slow, the force of the water being retained by a weir lower down. On the left bank stands Blackcastle, the seat of the Rothwells,—a square, modern building, designed more for comfort than architectural beauty; but the grounds, which are naturally picturesque, are well laid out, and afford many pleasing prospects of woodland glade and sloping meadow, as we descend the river; and the wood which skirts the stream throws a cool refreshing shade on its left bank, for above a mile of its course.

Adjoining the demesne of Blackcastle, on the Slane road, about a mile from Navan, on the western bank of the river, we pass the group of ecclesiastical ruins figured in the engraving upon the next page, the round tower and church of Donoughmore.

The original church, called *Domnach-mor-muighe Echnach*,

the great church of the plain of Echnach, is said to owe its origin to St. Patrick, who gave it to his disciple Cassanus. As this interesting group of ecclesiastical remains, which forms such a charming picture from every side by which we approach it, has been accurately described by Dr. Petrie, and as the tower itself is in every respect not only one of the most picturesque in appearance, but one of the most conclusive as to the Christian origin of these structures in Ireland, we afford our readers the following detailed account of it and the adjoining church, from the pen of the great authority alluded to, rather than any description of our own. He has given an account of this tower in two places,—in the Transactions of the Royal Irish Academy, where there is a drawing of the doorway, and in the Irish Penny Journal, from which latter, being the most detailed, we quote.



Regarding the erection of the great church at Domnach-mor, we learn from a passage in the Tripartite Life of St. Patrick, that,

“ ‘ While the man of God was baptizing the people called Luaignii, at a place where the church of Domnach-mor in the plain of Echnach stands at this day, he called to him his disciple Cassanus, and committed to him the care of the church recently erected there, preadmonishing him, and with prophetic mouth predicting that he might expect that to be the place of his resurrection ; and that the church committed to his care would always remain diminutive in size and structure, but great and celebrated in honour and veneration. The event has proved this prophecy to be a true one, for St. Cassanus’s relics are there to be seen in the highest veneration among the people, remarkable for great miracles, so that scarcely any of

the visitors go away without recovering health, or receiving other gifts of grace sought for.'—*Tr. Th.* p. 130.

"But though the existing ruins of the church of Donaghmore sufficiently indicate it to have been a structure 'diminutive in size,' its architectural features clearly prove that it is not the original church of St. Patrick's erection, but a re-edification of the thirteenth century, in the usual style of the parish churches erected by the Anglo-Norman settlers within the Pale. Neither can the round tower, though unquestionably a structure of much higher antiquity than the present church, be referred to the time of the Irish apostle, or perhaps to an earlier age than the ninth or tenth century. At all events its erection cannot be ascribed to an earlier date than that of the tower of the church of Kells,—a religious establishment founded by St. Columbkille in the sixth century,—as these towers so perfectly agree in architectural style and masonry, that they appear to have been constructed by the same architects or builders.

"This very beautiful tower is built entirely of limestone, undressed, except around the doorway and other apertures, and is of admirable masonry. It has two projecting ledges or steps at its base, and six rests for stories, with intermediate projecting stones or brackets in its interior. These stories are each, as usual, lighted by a single aperture, with the exception of the upper one, which has two openings, one facing the east, and the other the west; and the apertures present all the architectural varieties of form observable in our most ancient churches.* The circumference of this tower, near its base, is sixty-six feet six inches, and its height, to the slant of the roof, which is wanting, is about 100 feet. The wall is three feet nine inches in thickness, and the doorway is twelve feet from the ground. This doorway, which is of very beautiful execution, and, as usual, faces the west end of the church, is five feet two inches in height, and has inclined sides, and a semi-

* Since this was written the top of Donaghmore tower has been repaired; but while we must, with every admirer of the ancient architecture of Ireland, and every one who desires to see those ruins preserved from utter destruction, applaud the motive that induced this reparation, we cannot but regret that more attention was not paid to the form of the tops of other round towers. In this modern top there are no windows whatever, an anomaly in Irish round towers.

circularly arched top. It is two feet three inches wide at bottom, and two feet beneath the spring of the arch at top. Over the door there is the figure of the Saviour sculptured in relief, partly on the key-stone and partly on the stone over it ; and on each side of the architrave there is a human head, also in relief, as on the doorway of the church of Kells.

"Some antiquaries, in their zeal to support the theory of the Pagan origin and the antiquity of the round towers, have asserted that this doorway is not the original one, but an 'after work.' But there is not the slightest ground for such a supposition, and this sculpture, as a profoundly skilled architectural antiquary, the late Sir Richard Colt Hoare, well observed, furnishes 'a decided proof that these buildings were not (as some writers have conjectured) built by the Pagans.'

"A similar argument against the application of the round towers to the purposes of a belfry, has been grounded on the circumstance of the western front of the church having three apertures for bells above its gable. But it should not be forgotten that this structure has no claim to an earlier date than the thirteenth century, when a variety of bells, and a different mode of hanging them, were brought into use by the Anglo-Norman settlers.

"The church of Donaghmore has been confounded by Archdall and subsequent writers with the ancient church of Domnach-Tortain, also founded by St. Patrick, but which was situated near Ardracacan."

Since the above was written we visited, in company with Dr. Petrie, the round tower of Brechin in Scotland, and had there an opportunity of seeing a very perfect and much more finished representation of the Crucifixion, carved in relief, on the top stone of the doorway; and that tower is probably not older than the tenth



century; there is also a hatchment with heraldic devices carved, in relief, on the front of the door-sill.

The foregoing wood-cut is a faithful representation of the figure over the door of Donaghmore tower.

A mile below Navan, there is a large flax factory, which, like other similar establishments, though highly advantageous to the country, is no addition to the picturesqueness of the scenery. Beyond this mill we pass an abrupt bank, called Knock-a-Raymon, in which, a few years ago, a vast quantity of animal remains, and some sepulchral urns in small kistvaens were discovered. It was evidently one of the barrows of the aborigines; and we record the circumstance here, not from any present interest attached to the place, for it is now but a potato garden, but because we feel that the name and locality of every spot of Irish ground, in which such records of our ancestry are discovered, should be carefully noted, in order that the historian and the searcher into the unpublished manuscripts and archives, which are being now, for the first time, properly examined, may be aware of the fact,—for a vast number of these cairns and tumuli are alluded to in the annals referring to the Pagan occupation of this country. Not far from this point, we find the sacred well of Tober Ruadh; and now the right bank spreads out into broad meadows, glowing with the bright yellow blossoms of the butter-cups and may-flowers.

At the first lock upon the canal, an abrupt precipitous hill, the Knockminaune, or Kids' Hill, is crowned by a minor tumulus, the view from the summit of which commands the church of Ardmulchan, and two of the most interesting objects in the beauties of the Boyne,—the round tower of Donaghmore, already described, and the grey massive castle of Dunmoe. Seen from this point, the tall slender tower rising out of the green woods of Blackcastle, and cutting clear and sharp on the horizon, against the blue sky, forms an object of intense interest and beauty in this most charming landscape; and lower down upon the river's bank, the ancient fortress of the D'Arcys stands in gloom and grandeur on a brown and generally verdureless mound, without a tree or a single spot of green to relieve the sombre hue of its high walls and flanking towers.

The contrast between these two memorials of the art and history of this country is very striking, and tells the tale of

times to boast of, and also to mourn. The stately, chaste, and simple style of the early pillar, whose age cannot be far from 1000 years, added to the knowledge which we possess of the erection of the original church which once adjoined it, points to the first preaching of Christianity in our island, when a few devout Christians and some of the early fathers of the Irish Church settled round these buildings, and passed a life of pastoral quiet and simplicity; and now, surrounded by patriarchal timber, and revered by the people, it remains almost as perfect as when it came from the hands of the mason; and may continue so for centuries yet to come, unless some prying and infatuated antiquary should be allowed to grope under its foundation, for fragments of human bones to decorate museums, or give to the vulgar and uninformed some fancied proof of a theory as unintelligible as it is absurd. Turn to the castle of the D'Arcys,—a thing comparatively of yesterday, marking the boundary of the English Pale: it tells of the worst days of misrule in this unhappy land, where, without conquering the proud hearts, or gaining the warm affections of the Irish, the Anglo-Norman barons, who, with mailed hearts as well as backs,—neither civilizing nor enriching the country,—resided amongst us.* It is now fast falling into decay, and in a few years more will be but a great cairn of stones.

A bridge crossed the Boyne below this point in former days, a single arch of which, upon the right bank of the river, still remains. Before its complete demolition, it went by the name of Farginston's, or "the Robbers' Bridge," tradition says, on account of some noted horse-stealers, in the early part of the last century, having made it their chief resort. The country people also tell us, that Cromwell's army crossed it in its passage up the Boyne; and a village poet, named Courtney, has celebrated this ancient pass in some doggerel rhymes, which still live in the mouths of the neighbouring peasantry. The ancient name was "Babe's Bridge," and that it was one of the

* It struck the *Times* Commissioner, who commenced the late crusade against the Irish landlords, that the great majority of them are English, or of English descent. Is it known to the world, that while English settlers have become the proprietors, there never was any extensive importation of English farmers or yeomen into the southern and western parts of Ireland?

earliest bridges upon the Boyne may be learned from James Grace's *Annals of Ireland*, where we read, that, in the year 1330, "there was also a great flood, especially of the Boyne, by which all the bridges on that river, except Babe's, were carried away, and other mischief done, at Trim and Drogheda."

The next points of interest are, Ardmulchan church upon the right, and somewhat below it, Dunmoe Castle, upon the left. And here the true beauties of the Boyne, its real Rhine-like characters, commence, and crowd upon us for the next few miles of its course. High beetling crags, crowned by feudal halls and ruined chapels,—steep, precipitous banks, covered with the noblest monarchs of the forest,—dells, consecrated to the moonlight dance of sprites and elfins, and rocks, memorable for their tales of love, and legends of the olden time, catch the eye at every turn in this noble stream, presenting new beauties, ever-varying pictures, here in sunshine, there in shade, with charming bits of scenery, which simple prose cannot describe: the painter's art alone can embody, or give an accurate representation of these. We "stop not for brake, and we stay not for stone;" clear and blue the stream runs fast, and we must onward with its course, skimming lightly over its surface, rather inciting inquiry by our remarks, and directing attention in our researches, than attempting anything like an elaborate or detailed description.

The ruins of Ardmulchan (Ard-Maelchon, or Maelchu's height), top one of the highest banks above a bold stretch of the river, and consist of a tall square tower or belfry, and the remains of a church, which stands surrounded by an ancient graveyard, and some walls, believed to be part of one of the castles of the Tyrrells. That this church tower is composed of the material of some earlier building may be learned from the fact of the lintel in one of its upper doors being formed of an ancient sculptured tombstone, as shown in the accompanying wood-cut. We are well aware that crosses are sometimes found carved on the soffit of the



lintel in some very ancient church doors; but they are not of the same description, nor partially concealed, like this at Ardmulchan.

In the year 968, Amlaff Cuaran, with his Danes, and a party of Leinstermen, plundered Kells, and carried off a vast prey of cows, and gained a victory over the southern Hy-Neill at Ard-Maelchon.*

Ardmulchan belonged at one period to the Earl of Kildare. By an inquisition taken in the tenth year of the reign of James I., it was found that in the parish church of St. Mary (Ardmulchan) was a perpetual chantry of one priest, who was constantly to celebrate service therein, and this chantry was a body corporate. It at present belongs to the rectory of Painstown. A very beautiful well below this spot is worthy of attention; and a short distance beyond the church we meet with an ancient military fort, consisting of a circular mound, enclosed with a fosse and rampart. A grove of ash-trees now covers the entire, their tall, slender stems permitting the outline of this ancient relic to be seen at a considerable distance, while their feathery tops form an umbrageous shadow to the whole. Miss Beaufort, in her learned "Essay upon the State of Architecture and Antiquities previous to the landing of the Anglo-Normans in Ireland,"† informs us that a kistvaen or small stone chamber was discovered at Ardmulchan some years back, by a gentleman, in removing an artificial tumulus. It contained several skeletons, urns, and some golden ornaments. Into a deep pool in the river, opposite Taaffe's lock, called Lug-Gorrom, or the Blue Hole, it is said that the bells of this church were thrown at the time of the Reformation.

Dunmoe Castle stands on a commanding eminence, above one of the fords upon the Boyne, and must have been originally a position of considerable strength. The stones, however, with which it is built, are remarkably small, in consequence of which it is yearly crumbling into a shapeless mass of ruins. It is an oblong pile, with circular flanking towers on its river face, which measures seventy-three feet.‡ It was

* Annals of the Four Masters.

† Transactions of the Royal Irish Academy, vol. xv. p. 159.

‡ The accompanying sketch, by Mr. Wakeman, is taken from the right bank of the river. In Mr. Thomas Cromwell's "Excursions through Ireland," 1820,

originally built, it is said, by De Lacy, but the present structure bears the evidence of an Anglo-Norman keep of the sixteenth century. It has had many masters and stood several sieges in its day. During the civil wars of 1641, after the defeat of the English forces near Julianstown, an Irish detachment was sent to take Dunmoe; but Captain Power, who commanded it, with a mere handful of men, so long and bravely resisted his assailants, that the latter had to resort to stratagem to take it, and by producing a forged order from the Lords Justices, Parsons and Borlace, induced its gallant defender to surrender the castle and proceed to Dublin. Oliver Cromwell, it is said, took a passing shot at it from the opposite bank of the Boyne, but did not think it worthy of further notice. The ball which he fired at Dunmoe, or one shown as



such, was, until a very recent period, used as a weight at a neighbouring crane. This castle was re-edified and inhabited while James II. was in Ireland. Its last lord was D'Arcy, whose name is now usually associated with it. The

will be found a beautiful drawing, by Petrie, of Dunmoe Castle, vol. ii. p. 79. Since then it has been considerably dilapidated.

peasantry state that an underground passage leads from it under the Boyne to the opposite bank. Dunmoe was burned in 1799, but a portion of the roof remained within the last thirty years. Within the adjoining enclosure is a small chapel containing the mausoleum of its last lords; it is now a filthy dungeon, exposed to the atmosphere, and strewn with the bones and coffins of the descendants of this once noble family. Some twenty years more, and the traveller will have to inquire for the site of this celebrated castle of the Pale.

"I walked one day adown the Boyne,
From Domnach-Mor to Slaine;
How rich the fields on every side,
In cattle, wood, or grain.

The river flowed in summer pride,
And on its banks of green,
How many a noble ancient home
Seemed sent'nelling the scene.

I marked the salmon springing free,
Beneath the glittering fall;
I heard the cuckoo in the glen
Repeat her welcome call.

The hare would skip from out the green,
And, sporting on the lea,
Seem mad with joy—with very joy,—
O, who so blythe as he?

The nearer kine had left the field,
To cool them in mid-stream;
With glossy sides and switching tails,
They stood, and seemed to dream.

The sheep-bells tingled on the hill;
And from the mossy wheel
That flashing plays 'neath old Dunmoe
An ancient sound would steal."*

The ruins at Ardmulchan adjoin the direct road between Navan and Drogheda on the southern bank of the river, and the railway passes immediately beside them. This southern road, though it does not here command views of the Boyne, presents many objects of great interest, and passes through a charming

* "Vigilantius," in the *Irishman*. One who knows the Boyne well.

country. Leaving Ardmulchan, with its adjoining demesne, on the left, we pass by Hayes, the Meath residence of the present Earl of Mayo; and on the road side between that and Beauparc, we meet two fine raths,—one of considerable extent, and overlooking the river, “the horse fort” near the cross roads leading to Stackallan-bridge, and the other a little further on, at Dollardstown, a most picturesque wooded mount, with a surrounding fosse and ditch. A few trees, such as these upon this mound are rather an improvement; but when raths are covered with low underwood or brushwood, or completely obscured by timber, as at Donaghpatrick and New Grange, we lose much of their scenic effect. Several other raths stand by the wayside between this point and Drogheda; and lower down towards Rosnaree, where the road skirts the river, we obtain views of those great sepulchral pyramids, which form the cemetery of Brugh-na-Boinne, particularly those of Knowth, New Grange, Dowth, and that elegantly shaped little rath which stands in a green meadow within a bold stretch of the river opposite Roughgrange.

Presuming, however, that the tourist has descended the river in a boat, or loitered by one or other of its margins, we would conduct him to our next point of interest, Stackallan, where Broad Boyne Bridge, leading to the Slane and Navan road, crosses the river. In the immediate vicinity is the residence of Viscount Boyne, lately occupied by the Seminary or College of St. Columba. This, like almost every spot of ground along the Boyne and Blackwater, to which a name attaches, has been commemorated in our ancient histories. Its Irish name is Tigh Collain—*Teach-Collan*, the house of Collan, which was, we read, situate in the ancient territory of Ui-Crimhthainn, at present comprised in the baronies of Upper and Lower Slane.*

In the neighbourhood of Stackallan, upon the Slane and Navan road, on the northern bank of the river, there are two

* O'Donovan, in his note on the record of the death of “Cethernach, bishop from Teach-Callain,” who died on a pilgrimage at Hi, A. D. 1047, writes: “It is curious to remark, that in some of those districts, colonized by the Danes and English, the *Teach* or *Tigh*, of the Irish, was made *Sta* or *Sti*, as in this instance [Stackallan], and in Stickillen, Stagonnell, Stillorgan, in Irish *Uí Chuilín*, *Teach Chonail*, *Uí Chonáin*.” The same learned authority thinks the name should be *Teach Conáin*, *St. Conan's house*. See Annals of the Four Masters, p. 851, A. D. 1047.

trivial objects, still not so uninteresting as to be passed by without a peep into the one and a glance at the other, if only to assist us in making good the promise contained in our first chapter as to the multitude and variety of remains extending along the Boyne. These are Tober Padraig, a blessed well, dedicated to our patron saint, but now neglected and disused, and Baronstown cross, a wayside monumental cross, the pillar or shaft of which, supported by a short pedestal or base, still stands on a small knoll near the road; the head has been broken into fragments, several of which may be seen scattered around. This monument was erected by one of the Dowdalls, the great cross-builders of Meath, of whose memorials of piety and affection two other examples of a similar description may be seen not far off, one in the town of Duleek, and the other at Annesbrook, in its neighbourhood. The shaft of this cross at Baronstown is four-sided, and on each face there is a rather rude and ill-spelled inscription. Upon the western face, beneath a figure of St. Patrick, we read,

"I PRAY YOU, SAINT PATRICK, PRAY FOR THE SOULES OF OLIVER PLUNKET, LORD BARON OF LOUTH, AND DAME JENET DOWDAL, HIS WIFE."

Upon the south front:—

"THIS CROSSE WAS BULDED BY DAME JANET DOWDALL, LATE WIFE UNTO OLIVER PLUNKET, LORD BARON OF LOUTH, FOR HIM AND HERSELFE, IN THE YERE OF OUR LORD GOD" * * * [*Probably 1590.*]

Underneath a rude image of St. Peter, on the east side:—

"I PRAY YOU, SAINT PETER, PRAY FOR THE SOULES OF OLIVER PLUNKET, LORD BARON OF LOUTH, AND DAME JENET DOWDAL, HIS WIFE."

On the back, towards the north, under a plain shield, similar to that which exists at top of the south front, is the "Hail Mary," and an invocation for the prayers of the Virgin.

A little to the south-east of Broad Boyne Bridge, another military fort (this may be the house of Cletty of the Irish writers), similar to that at Ardmulchan, appears on the right bank. The river here forms a smooth, glass-like sheet of water, and below the bridge affords us one of those striking effects which the weirs upon the Boyne exhibit, of a long

unbroken line of liquid, bent into a graceful curve, goldened with the sunshine, as it glides in swift but silent track over the long horse-shoe fall, and then breaks into a million streams—its spray dancing in the sunshine, and its bubbles reflecting all the prismatic colours of the rainbow, as it again springs onward in its course. These charming effects, whether varied by the grey morning's light, or the evening's uncertain haze, or having an air of obscurity thrown over them by the veils of mist which rise and play round the fall, or float like phantoms over the broad surface of the river—here assuming the figure of a stately vessel, there rising into tall, castellated form—creeping under the arches of bridges, re-appearing in an instant; wrapping in their shroud the aged trees, which dip into the waters,—drifting again along the surface, like the broken fragments of some tall iceberg, and suddenly lifted above the mirror on which they play, leaving the surface on which they had appeared to breathe, again unbroken on its outline,—add not a little to keep those scenes in our remembrance. If we stand at sundown on the bridge of Slane, when there is any body of water in the river, on a calm summer's evening, listening to the soothing monotony of the fall, and cast our eyes over the broad reach of the Boyne above, we cannot fail to be struck with the effect which is here attempted to be described.

The broad reach of the river below the bridge at Stackallan has been supposed by some antiquarians to be in the vicinity of *Brugh-na-Boinne*, one, if not the chief of the royal cemeteries, and where the monarchs of Tara were interred of old; but we think the evidence is in favour of a locality lower down beyond Slane, to which we shall presently refer. A deep pool, immediately below the bridge, receives the name of *Lugaree*, the king's hole, where the river well deserves the name of the "Broad Boyne," which it still retains. Some ancient pagan remembrances and superstitions attached to this locality, up to a very recent date; and, at a *Patron* which used to be held here some years ago, it was customary for the people to swim their cattle across the river at this spot, as a charm against fairies and certain diseases, as in former times they drove them through the Gap of Tara.*

* The same practice is still observed at Newtown-Trim upon the first Sunday in August. St. Sinchea's well, *Tober t-Sinne*, is said to be in the neighbour-

To many of our readers, however, and most of the tourists who may follow our wanderings, or require a guide-book in their excursion, a more interesting subject than ancient customs, or even the tombs of kings, invites us onward; for the wood-crowned heights and leafy banks of Beauparc, one of the most picturesque spots in Ireland, and the noble demesne of Slane, lie immediately before us. Beyond the fall of Stackallan we pass through the most delicious scenery, particularly along the left bank, where groves of noble beech trees and aged chesnuts fringe the heights, and an underwood of laurels, thorns, and sweet-briars mantle upon the undulating surface of the shores beneath, till we pass the mill and bridge of Cruisetown, where (supposing that we have come down in a boat, which is by far the best plan) we commit ourselves to the centre of the stream, and bestow an equal share of our attention upon both banks. Here the river forms a number of sudden curves, each winding presenting us with a new picture more beautiful than its predecessor. The banks spring high and abrupt from the water's edge, so that in some places the massive trees, rising in piles of the most gorgeous foliage, appear topling over us from their summits, and darken the deep smooth pools they overhang. Upon a summer's day an air of calm repose pervades this spot; the very songsters of the grove seem hushed in admiration, and unwilling to disturb the peaceful thoughts which here gradually steal over the beholder. On the right the modern mansion of Beauparc peeps through the never-ending green of tall pines, sycamores, oaks, and elms. On the left the ivy-mantled walls of Castle Dexter raise themselves above the dark plantation, contrasting the times of feudal rule and massive defensive architecture, with its light domestic neighbour of more modern date. The limestone rock, here twisted into a variety of curious contortions, breaks through the surface, and relieves the eye, almost satiated with the endless variety both of colour and foliage. Through occasional openings we obtain glimpses of long vistas, formed by the overhanging boughs, and terminated by glades of turf, on which the sun beams with unusual splendour. The river spreads out, and the sun again glances upon its smooth waters; the

hood of Broad Boyne Bridge, but, unless that now called on the Ordnance Map Tober Patrick be it, we are not aware of its site.

massive perpendicular rock of Fennor, about which we could tell many a fairy legend and relate many a tale of love, rears aloft its giant form, with its fir-fringed summit and bold grey front, draped with festoons and long tendrils of dark green ivy; and then, as we float downward with the stream, enjoying beauties scarcely known and little noticed in this country, the modern castle of Slane suddenly bursts upon us, occupying a most commanding situation, and appearing, with its surrounding wooded hills, the back-ground or extreme distance of a picture framed by the elevated banks of the Boyne, which here spreads out in front of it into a noble sheet of water, for which there does not, at first view, seem any exit.

To visit these different objects of interest in detail;—here is the ruined fortress of Castle Dexter, from which the surrounding townland of Carrickdexter probably takes its name. The ovens and huge fire-places in this castle attest the good living of its early occupants; but the windows are not so well preserved, neither were they originally so well made as those at Athlumney. Very little is known of the history of this beautifully situated castle, at least that was acces-



sible to us through the ordinary sources of information. It is said by the people around to have been erected by one of the Flemings, the early lords of Slane, and to have been their original residence. From its name, however, we should suppose it to have belonged, if it was not built, by one of the D'Exeter family, some of whom were located in Meath, although the great sept was in Connaught, where they assumed the Irish name of Mac Jordan. In the "*Annales Hiberniæ Jacobi Grace, Kilkenniensis*," under the year 1312, we read that "Milo Verdon married the daughter of Richard de Exoniis (Dexter);" and the inscription on the monumental wayside cross at Nevinstown, already mentioned at page 157, assists to throw some

light on the history of the Meath branch of this family. The name is also mentioned (as a witness) in the Register of All-Hallows, Dublin, lately printed by our Archæological Society. A story is told that a salmon-trap formerly existed in the river immediately adjoining Castle Dexter, and when a fish was caught its struggles touched a wire connected with a bell in the castle, which gave the cook notice of its capture. A similar tale is, however, told of several other castles and monasteries standing by the brinks of rivers.

Slane Castle, the seat of the Marquis of Conyngham, and memorable in modern times, from its being visited by King George IV., stands on a swelling bank of verdant green-sward, rising gradually from the river. It is a large castellated mansion, with towers and embattled parapets, but not boasting much beauty of architectural design. It is principally the surrounding scenery, the combinations of sylvan beauty formed by its own extensive demesne, blending with that of Beauparc, the neighbouring woods of other seats, the charming associations awakened by the ancient ruins standing on the romantic shores of its noble river, and the highly cultivated landscape on all sides, which claim for Slane Castle the eulogiums of its modern describers. Leaving this



modern residence of the lords of Slane, we drift onward, still approaching the northern bank, and land at the church or hermitage of St. Erc, which stands within the demesne, upon the

shore immediately below the castle, embosomed within the dark shadows of a grove of ancient yews, one of the most romantic ruins of its date and style in Ireland. Considerable portions of this picturesque building still exist. The accompanying engraving faithfully represents the doorway.

It takes its name from Erc, "the sweet-spoken judge," the first Bishop of Slane, who was consecrated by St. Patrick, and died A. D. 514.* It was afterwards the retreat of Malachi and Donat O'Brien, two hermits, who resided here in 1512. Over the pointed door we find the fleur-de-lis, and upon the inner doorway some rose ornaments, rather unusual in Irish architecture. Within the little chapel is the tomb of the Earls of Drogheda, and upon the walk above the hermitage there lies a handsome sculptured stone, with twelve figures upon it, evidently a portion of an ancient tomb, and well worthy the attentive examination of the antiquarian student.



From the mixture of round and pointed arches, as well as the evident difference in the styles of masonry, it is manifest that this building at St. Erc's was erected or remodelled at two different eras.



* The Annals of the Four Masters say Bishop Erc died upon the 2nd November, 512. "His age was four score years and ten when he departed. This Bishop Erc was judge to Patrick. It was for him Patrick composed this quatrain :

"Bishop Erc,—
Everything he adjudged was just ;
Every one that passes a just judgment,
Shall receive the blessing of Bishop Erc."

In the historical tale of the banquet of Dun na n-Gedh, a composition of the twelfth century, there is a curious reference to this place. King Domhnall, having completed his great fort, or house, determined, as was usual on such occasions, to give a feast, and for that purpose sent forth his stewards to collect every delicacy of the season, for, like many a modern Heliogabulus, "Domhnall did not deem it honourable that there should be in Erin a kind of food that should not be at that banquet."

"And the collectors went forth throughout Meath, in search of the eggs, until they came to a small Duirtheach [hermitage], in which was one woman with a black hood upon her head, and she praying to God. The king's people saw a flock of geese at the door of the Duirtheach; they went into the house and found a vessel full of goose eggs. 'We have had great success,' said they, 'for should we search Erin, there could not be found more goose eggs together in one place than are here.' 'It will not be good success,' said the woman, 'and it will not redound to the happiness of the banquet to which this small quantity of provisions will be brought.' 'Why so?' said they. 'It is plain,' said the woman; 'a wonder-working saint of God's people dwells here, namely, Bishop Erc, of Slaine,* and his custom is to remain immersed in the Boinn, up to his two arm-pits, from morning till evening, having his Psalter before him on the strand, constantly engaged in prayer; and his dinner every evening on returning hither is an egg and a half, and three sprigs of the cresse of the Boinn; and it behoves you not to take away from him the small store of food which he has. But the proud people of the king made no reply to her,—for they were plebeians in the shape of heroes on this occasion,—and they carried away the property

* "This is an anachronism, for Bishop Erc, of Slaine, who was contemporary with St. Patrick, died in the year 514 (Ussher's *Primordia*, p. 442), and this battle was fought in the year 688, that is 124 years after Erc's death! The probability is, that the original composer of the story had written *Comharba* [i. e. successor] of Erc, of Slaine; but all the copies to which we have access at present agree in making the saint Erc himself." See "The Banquet of Dun na n-Gedh, and the Battle of Magh-Rath, an ancient historical Tale, now first published from a Manuscript in the Library of Trinity College, Dublin, with Translation and Notes, by John O'Donovan, for the Irish Archaeological Society."

of the righteous man and saint, in despite of him [her]. But woe to him to whom this small quantity of food was brought, for a great evil sprang from it afterwards; for Erin was not one night thenceforward in the enjoyment of peace, or tranquillity, or without a desire of evil or injustice, for some time.

"The holy patron, Bishop Erc, of Slaine, came to his house in the evening, and the woman told him how he was plundered. The righteous man then became wroth, and said: 'It will not be good luck to the person to whom this kind of food was brought; and may the peace or welfare of Erin not result from the banquet to which it was brought; but may quarrels, contentions, and commotions be the consequence to her.' And he cursed the banquet as bitterly as he was able to curse it.

"As the king's people were afterwards at the assembly, they saw a couple approaching them, namely, a woman and a man; larger than the summit of a rock on a mountain was each member of their members; sharper than a shaving knife the edge of their shins; their heels and hams in front of them; should a sackful of apples be thrown on their heads not one of them would fall to the ground, but would stick on the points of the strong, bristly hair which grew out of their heads; blacker than the coal or darker than the smoke was each of their members; whiter than snow their eyes; a lock of the lower beard was carried round the back of the head; a lock of the upper beard descended so as to cover the knees; the woman had whiskers, but the man was without whiskers. They carried a tub between them which was full of goose eggs. In this plight they saluted the king. 'What is that?' said the king. 'It is plain,' said they, 'the men of Erin are making a banquet for thee, and each brings what he can to that banquet, and our mite is the quantity of eggs we are carrying.' 'I am thankful for it,' said the king. They were conducted into the palace, and a dinner sufficient for a hundred was given to them of meat and ale. This the man consumed, and did not give any part of it to the woman. Another dinner sufficient for a hundred was given them, and the woman alone consumed it. They demanded more, and another dinner for a hundred was given them, and both of them together consumed it. 'Give us food,' said they, 'if you have it.' 'By our word we shall not,' said Casciabach, the king's *Rechtairè*, 'till the men of Erin in general shall come to the feast.' The others then said, 'Evil

shall it be to you that we have partaken of the banquet first, for the men of Erin shall be quarrelsome at it, for we are of the people of Infernus.' And they predicted great evils to the multitudes, and afterwards rushed out, and vanished into nothing." This banquet was the cause of the celebrated Battle of Magh Rath.

Not far distant from the Hermitage was Lady Well, but it is now nearly obliterated; and in the wall of the pleasure-ground of the castle may be seen the carved effigy of an ecclesiastic, probably a bishop: and below, a little to the right of the bridge of Slane, stands the old church and ruined castle of Fennor, but they do not possess sufficient interest to require minute examination.

Let us pass under the handsome gate of Slane demesne, through the neat little town adjoining, where, at its comfortable hotel, we may enjoy as bright and generous a glass of claret, and receive as good cheer, as at any similar establishment with which we are acquainted; and then climb the hill which rises immediately over the town. On the western brow of the hill stands a noble circular, entrenched rath, possibly the seat of the palace of the monarch from whom its present name is derived. We are now upon the wooded height which so frequently caught our eye as we passed down the Boyne, and upon the spot so



often referred to in the foregoing descriptions,—Slane, the early residence and the burial-place of King Slanius (see page 14). Ascending the hill, we stand beside a group of ruins, the remains of the church and monastery figured above.

Here, pilgrim, stop; rest on yonder monumental slab, beneath the shadow of that tall, ivy-mantled tower, the belfry of the cathedral—it once was gorgeous with the shrines of Fathers, and illumed by many a flickering taper, though now the hemlock fills its aisles, and the purple foxglove waves its lonely banneret. The ground whereon we stand is sacred,—consecrated by the foot-prints of our patron saint, hallowed by the dust of kings. Look abroad over the wide, undulating plains of Meath, or to the green hills of Louth: where, in the broad landscapes of Britain, find we a scene more fruitful and varied, or one more full of interesting, heart-stirring associations? Climb this tower and cast your eye along the river. Look from the tall, pillar-like form of the Yellow Steeple at Trim, which rises in the distance, to where yon bright line marks the meeting of the sea and sky below the Maiden Tower at Drogheda, and trace the clear blue waters of the Boyne, winding through this lovely, highly cultivated landscape, so rich in all that can charm the eye and awaken the imagination; take into view the hills of Skreen and Tara; pass in review the woods of Hayes, Ardmulchan, Beauparc; look down into the green mounds and broad pastures of Slane; follow the Boyne below you, as it dances by each ford and rapid, to where the great pyramids of western Europe, Knowth, New Grange, and Dowth, rise on its left bank; see you not the groves of Townley Hall and Old Bridge, marking the battle-field of 1690, with the ill-fated hill of Donore, where the sceptre passed for ever from the royal line of Stuart, obtruding its long-remembered tale of civil strife upon us? Duleek stands in the distance. Beyond those hills that border Louth lie Monasterboice, and Mellifont, the last resting-place of the faithless Bride of Brefney. Those steeples and turrets which rise in the lower distance were shattered by the balls of Cromwell; and that knoll which juts above them is the Mill Mount of Drogheda. What a picture have we here, from this Richmond Hill of Irish scenery! What an extensive page of our country's history does it unfold to us! What recollections gush upon us as we stand on the abbey walls of Slane, and take in this noble prospect at a glance! The records and the footprints of two thousand years are all before us; the solemn procession of the simple shepherd to the early Pagan mound; the rude slinger standing on the earthen cir-

cle; the Druid fires, paling before the bright sun of Christianity; the cadence of the round tower's bell; the matin and the vesper hymn swelling from the hermit's cell, or early missionary church; the proud galleys and glancing swords of fierce northern hordes; the smoking ruins of church and tower; the shout of rival clans in civil feuds; the lances and banners of Norman soldiers; the moat, and fosse, and draw-bridge of the keep, still echoing back the strife of hostile ranks,—the native for his soil, the stranger for his hire; the ford defended, and the castle won; the pilgrim's cross, the stately abbey, and the baron's hall; in church, the stole ejected for the surplice; the town besieged, the city sacked; and then the rattle, and the roar, and smoke of recent battle;—have, one and all, their epochs, ruins, sites, or history, legibly inscribed upon this picture.

The early Irish name of Slane was Ferta-fear-Feig, the graves of the men of Feig,* and one of the first notices of it which our annals contain relates to a most remarkable epoch in the history of this country. We mentioned that Patrick landed at the Boyne's mouth; he afterwards passed up that river's bank a day's journey into Meath. Although some months in the island, it is not said that he made any extensive or remarkable conversions to Christianity till the Easter of 433, on the Thursday night before which we read the following account of him, as collected from the various Lives of St. Patrick by Ussher and Colgan, and thus condensed by the learned Dr. Lanigan:—"Having got a tent pitched there (Slane), he made preparations for celebrating the festival of Easter, and accordingly lighted the paschal fire about nightfall. It happened that, at this very time, the King Loeghaire and the assembled princes were celebrating a religious festival, of which fire-worship formed a part. There was a standing law that, at the time of this fes-

* Where these graves are has not yet been determined; perhaps they formed part of the great neighbouring cemetery of Brugh-na-Boinne, for in an ancient MS. in the Library of Trinity College, Dublin, called "Irish Triads," enumerating three of each of the most remarkable objects in Erin,—as the three mountains, the three cataracts, the three plains, and the three rivers,—it is stated that the three darkest *caves* of Ireland are Uaimh Cruachna, i. e. the cave of Croghan; Uaimh Slaine, i. e. the cave or crypt of Slane; and Dearc Fearná, i. e. the cave of Dunmore, near Kilkenny. See also the Annals of the Four Masters, A. D. 928, and the Dublin Penny Journal, vol. i. p. 73. Can New Grange be the cave of Slane?

tival, no fire should be kindled for a considerable distance all around, until after a great fire should be lighted in the royal palace of Temoria, or Tarah. St. Patrick's fire was, however, lighted before that of the palace, and, being seen from the heights of Tarah, excited great astonishment. On the king's inquiring what could be the cause of it, and who could thus dare to infringe the law, the magi told him that it was necessary to have that fire extinguished immediately, whereas, if allowed to remain, it would get the better of their fires, and bring about the downfall of his kingdom. Loeghaire, enraged and troubled on getting this information, set out for Slane with a considerable number of followers, and one or two of the principal magi, for the purpose of exterminating those violaters of the law. When arrived within some distance from where the tent was, they sat down, and St. Patrick was sent for, with an order to appear before the king, and give an account of his conduct. It was arranged that no one should show him any mark of respect, or rise up to receive him; but, on his presenting himself before them, Horc, son of Dego, disobeyed the injunction, and, standing up, saluted him, and, receiving the saint's blessing, became a believer."

The subsequent preaching of Patrick at Tara, and its results, are set forth in the various Lives of the saint. A nobler spot on which to raise the beacon of Christianity could not possibly be chosen. The itinerary of St. Patrick up the Boyne might form a guide to the ancient topography of the river.

A cloictheach, or round tower, formerly existed at Slane, and probably stood on the site of the present ecclesiastical ruins, where it must have formed an object of surpassing beauty. It was destroyed by the Danes of Dublin, about the middle of the tenth century. It is alluded to in a great many of the ancient records; the following is, perhaps, the fullest, and at the same time the most intelligible notice of it to the popular reader: "A. D. 948. The cloictheach of Slane was burned by the Danes, with its full of reliques and good people, with Caoinchair, reader of Slane, and the crosier of the patron saint, and a bell, *the best of bells*." An abbey of canons regular was founded here at a very early date, and Archdall (who was rector of Slane) informs us, on the authority of Mezeray's History of France, that it "was remarkable for being many years the residence of a royal prince; for we find that, in the year 653,

Dagobert, King of Austrasia (part of France), when at the age of only seven years, was taken by Grimoald, mayor of the palace, and by his direction he was shorn a monk, "rendered unfit to hold the reins of government, and banished into Ireland. From oral information we learn that he was received into this abbey, where he obtained an education proper for the enjoyment of a throne; he continued here during the space of twenty years, when he was recalled into France, and replaced in his government." By what means the author of the *Monasticon* obtained this latter information, or what oral traditions, referring back for such a length of time, should be received as history, we cannot now pause to discuss. Among the several tombs around the abbey the stranger's attention is pointed to one, said to bear the fleur-de-lis upon it, and this, "from oral information, we learn" is the tomb of the son of the King of France!—but any one accustomed to examine such objects, at once recognises it as the tomb of an Irish ecclesiastic, being figured with a cross, each arm of which ends in a leaf-like ornament, and also having upon it a chalice; and beneath the foot of the cross the name W. J. Kirwan may still be deciphered. Several other curious old tombs may be observed here; one, in particular, to the south of the church, is of a remarkable form, and, in all probability, of greater antiquity than any Christian tomb in Ireland, except a similarly constructed one which we are given to understand exists in the churchyard of Saul, near Downpatrick, and that to which we already referred at Donaghpatrick, a fragment of which occupies a precisely similar position with respect to the adjoining church there. This tomb at Slane, of which the accompanying is a sketch, consists of two large gable-shaped flags, about three feet of which rise above the ground, and separated by an interval of about six feet. Each of these stones is grooved exactly like the gable of a house, the grooves appearing to be intended for the reception of the ends of horizontally inclined



flags which formed the roof. That this is a tomb of great antiquity, and to which peculiar reverence attaches, may be learned from the fact that, at all the funerals of the lower orders here, the people, in carrying the corpse round the graveyard, according to ancient custom, invariably lay it down for a short time at this spot. Within the enclosure of the burial-ground, and to the north of the abbey, is the well of Tober Patrick, formerly in great repute, and which the people say not only rises and falls with the floods of the Boyne, but sometimes has bits of bulrushes floating in it. This rising and falling of the water in this holy well is not peculiar; several similar circumstances are related of other holy fountains. (See Nennius).

The noble pointed window, in the highly decorated style denominated flamboyant, over the round arched doorway in the western side of the tower, together with the many rare examples of architecture, of great elegance of design, both in the ruins of the church and the adjoining monastery, not forgetting the prim face of a nun, sculptured in a stone, built up in the wall which now encloses the grave-yard, and the wide range of prospect obtained by climbing the tower itself, are well worthy a morning's visit to Slane. The church is somewhat more than 100 feet long by eighteen wide. Within it, among the nettles and rank weeds, may, if carefully looked for, be found the ancient font. It is unornamented, octagon in shape, and the basin, as usual, twenty-two inches in diameter. The ruins of the monastery, which are very extensive, are quite detached from the church, and to the north-east of it.

In the park of Slane were found, some years ago, those brass antiquities now in the Museum of the Academy, believed to be musical instruments, and called crotalins by Walker and Ledwich, but which were probably fastenings or clasps. By the shores of the deep meadows through which the Boyne sweeps here, the curragh of wicker-work, covered with horsehide, may still be seen. We might stop our course to describe its construction, or speculate on the circumstance of this ancient relic of the rude early navigators of this river still remaining, in the very heart of civilization; and step by step might we thus follow the river's windings from the bridge of Slane to the sea, redeeming, at every turn, the boast we made of presenting our readers with a series of tableaux of the most interesting stream in Ireland, but that more inviting objects, about two miles lower down, attract attention.

CHAPTER VIII.

THE ROYAL CEMETERY OF BRUGH NA BOINNE.

THE SENCHAS-NA-RELEC.—BRUGH NA BOINNE.—THE INTERMENT OF KING CORMAC.—ROS NA RIGH.—KNOWTH.—THE TUMULUS OF NEW GRANGE; ITS ENTRANCE, PASSAGE, AND CHAMBER.—CRYPTS IN THE INTERIOR.—ANTIQUÉ CARVINGS.—ANCIENT HISTORY OF THIS MOUND.—DOWTH.—RECENT EXAMINATION OF ITS INTERIOR.—DESCRIPTION OF ITS CHAMBERS AND PASSAGES.—BOSSAN.—CLOGHLEA.—NETTERTVILLE.

THERE were several royal burial places in Ireland in early Pagan times, eight of which have been enumerated. In the *Senchas-na-Relec*, or the History of the Cemeteries, contained in the *Leabhar na h-Uidhre*, a work compiled at Clonmacnoise, in the twelfth century, we learn that among these chief cemeteries were Cruachan, now Rathcroghan, in the county of Roscommon, where there are still considerable remains; Tailltean, Teamhair Erann, or Tara, and Oenach Colmain; so from these it would appear that the monarchs were sometimes buried in the immediate vicinity, or perhaps within the enclosure of their dwellings, like King Loeghaire, who was contemporary with St. Patrick, and who was interred in a standing position, with his weapons and war dress upon him, in the external rampart of the rath which bears his name at Tara, with his face turned southward, towards his enemies, the Leinstermen.

But by far the most celebrated and extensive of all the Irish cemeteries was that denominated Brugh, or *Brugh na Boinne*, the Burgum Boinne, the fort or town of the Boyne, of which an account is given, not only in the work already alluded to, but in another Irish manuscript of great antiquity, the *Dinnseanchus*, a tract contained in the great Speckled Book of Ballymote; and to this place references continually occur in almost every ancient Irish manuscript. This was the great royal cemetery of the Kings of Tara; and from an examination of the various authorities which describe it, as well as the monuments themselves which still exist, it is manifest that Brugh na Boinne was no other than the assemblage of mounds, caves, pillar-stones, and other sepulchral monuments, forming the great necropolis which extends along the left or northern bank of the river, from Slane to Netterville. “The nobles of

the Tuatha De Danaan were used to bury at Brugh (i. e. the Dagda, with his three sons, also Lughaidh, and Oe, and Ollam, and Ogma, and Etan, the poetess, and Corpre, the son of Etan), and Cremthann followed them, because his wife, Nar, was of the Tuatha Dea, and it was she solicited that he should keep Brugh as a burial-place for himself and his descendants, and this was the cause they did not bury at Cruachan.”* The Lagenians (Leinstermen) of the race of Cathair, were buried at Oenach Ailbhe; the Clann Dedad, at Tara; the men of Munster at Oenach Culi and Colmain; and the Connaughtmen at the Relec na Riogh, at Rathcroghan. The monuments at Brugh are enumerated as “The bed of the Dagda first; the two paps of the Morrigan, at the place where Cermud Milbhel, son of the Dagda, was born; the grave of Boinn, the wife of Nechtan; the mound of Tresc; the grave of Esclam, the Dagda’s brehon, which is called Fert Patric at this day; [the monuments of] Cirr and Cuirrell, wives of the Dagda; these two hillocks; the grave of Aedh Luirgnech, son of the Dagda; the cave of Buailcc Bec; the monument of Cellach, son of Maelcobha; the monument of the seed of Cinaedh, son of Irgalach; the prison of Liath-Macha; the glen of the Mata, i. e. the Monster, as some assert; the pillar-stone of Buidi, the son of Muiredh, where his head is interred; the stone of Benn, i. e. the monument on which the monster, Mata, was killed; it had one hundred and forty legs and four heads; the Mound of the bones; the Caisel (stone enclosure) of Aengus, &c. &c.”

From this description we learn somewhat of the nature of an ancient Irish Pagan cemetery, and of the kind of remains which we are to expect wherever any traces of such still exist, and we shall see presently that this in the neighbourhood which we are now investigating fully answers the description. In the “Genealogies, Tribes, and Customs of Hy-Fiachrach,” given in the Book of Lecan, lately translated by Mr. O’Donovan for the Irish Archæological Society, we have some account of the Releg na Riogh, or cemetery of the kings of Croghan in Connaught, in the description of the death and interment of Dathi, whose body, it is said, was carried to battle by Amhalgaidh, as a stimulant to the warriors of his clan and a terror to his enemies. The passage runs thus: “Dungal, Flannghus,

* See Translation of the Senchas-na-Relec, in Petrie’s Round Towers, p. 101.

Tuathal, and Tomaltach, were the four servants of trust who carried with them the body of the king. The body of Dathi was brought to Croghan, where the kings of the race of Heremon were for the most part interred, where to this day (1666) the cairrthe dhearg, *red pillar-stone*, remains as a monument over his grave, near Rathcroghan. That the body of Dathi is interred in the middle of Aonach na Cruaghna is attested by Torna Eigeas, in his poem pointing out the burial-place of the kings of the race of Heremon to the men of Erin."—p. 25. From this we learn not only the use of the pillar-stone, about which, as well as the cromlech (generally but erroneously called a Druid's altar), speculative and imaginary antiquaries—who are usually unacquainted with the Irish language or Irish history—have written so much, and with such an assumption of learning, but also the fact that the graves and monuments of Irish chieftains were well known 200 years ago. The cemetery is still to be recognised among the great Rathes at Croghan, and we have often seen the pillar-stone alluded to, where it stood in a field near the cross-roads of that place, and was used as a "scratching stone" by the fat cattle that grazed among the raths and upon the fertile plains of Rathcroghan.

Did our space permit, or if the object for which this book is written allowed it, we could, from abundant materials now at hand, record the modes of interment as well as the exact burial-places of many of the Pagan Irish chieftains and warriors, together with their mode of death, and many other most interesting particulars connected with this subject. It is related that Caeilte, the foster-brother and one of the generals of Finn Mac Cumhail, killed Fothadh Airgthech in the battle of Orlarba, near the Larne, in the county of Antrim, A. D. 285, with a spear, the *iron* head of which passed through him, and was left buried in the earth. The grave of the vanquished is afterwards recognised by Caeilte, who, it would appear, threw the spear or dart at his enemy from a rock in the neighbourhood. He thus describes the locality: "The round stone from which I made that shot will be found, and east of it will be found the iron head of the spear buried in the earth; and the ulidh [cairn] of Fothadh Airgthech will be found a short distance to the east of it. There is a chest of stone about him in the earth. There are two rings of silver and his *bunne doats* [bracelets!] and his torque of silver on his chest, and there is

a pillar-stone at his cairn, and an Ogum is [inscribed] on the end of the pillar-stone which is in the earth, and what is in it is—' Eochaid Airgtech here.' ”*

We are now in a position to inquire after the site of Brugh na Boinne, the royal cemetery of “the Fort of the Boyne.” About two miles below Slane the river becomes fordable, and several islands break the stream. Here, upon the left, or south-western bank of the river, is the place called Rosnaree, the ancient Ros-na-Righ, or the Wood of the Kings, and upon the opposite swelling bank of the river occur a series of raised mounds, raths, forts, caves, circles, and pillar-stones, bearing all the evidence of ancient Pagan sepulchral monuments, which, there can now be little doubt, was the Irish Memphis, or city of tombs, already so frequently alluded to. The following reference from the History of the Cemeteries, already referred to, will, we think, set the question at rest, and fix the site of Brugh-na-Boinne here, and not, as has been conjectured, at Stackallan. We already mentioned, in describing Clady, that King Cormac Mac Art died at the house of Cletty. His burial is thus detailed: “And he (Cormac), told his people not to bury him at Brugh (because it was a cemetery of idolaters); for he did not worship the same God as any of those interred at Brugh; but to bury him at Ros-na-Righ, with his face to the east. He afterwards died, and his servants of trust held a council, and came to the resolution of burying him at Brugh, the place where the kings of Tara, his predecessors, were buried. The body of the king was afterwards thrice raised to be carried to Brugh, but the Boyne swelled up thrice, so as that they could not come; so that they observed that it was violating the judgment of a prince to break through this testament of the king; and they afterwards dug his grave at Ros-na-Righ, as he himself had ordered.” And again, “The nobles of the Tuatha De Danaan were used to bury at Brugh.”

From this it is evident that the place where the servants of Cormac endeavoured to cross the river with his body was

* See Petrie's Round Towers, p. 108. See also the Annals of the Four Masters, A. D. 285, with O'Donovan's note thereon. From the foregoing quotation it would appear that Ogham inscriptions were used in the third century. With the exception of some markings upon the edges of one of the stones recently discovered at Dowth, which look like Ogham characters, we do not find inscriptions of this nature along the Boyne or Blackwater.

at the ford of Ros-na-Righ, in order to inter it in the cemetery of Brugh-na-Boinne. The Dagda, whose monument is enumerated in this cemetery, was a king of the Tuatha De Danaans, named Eachaidh Ollathair, whose reign for eighty years, commenced (it is said in the annals) at the year of the world 3371. He was styled Daghdha-mor, the "Great Good Fire," from his military ardour; and his monument in the cemetery of the Boyne was called Sidh-an-Brogha. May it not be one of those great sepulchral mounds now in sight, which we are about to describe? Several of the other personages whose monuments are enumerated as being in this great cemetery have been already mentioned.

About a mile and a half below Slane, and extending along the northern bank of the river, we meet the great Irish cemetery to which we have just alluded. This consists chiefly of a number of sepulchral mounds, or barrows, varying in magnitude, and occupying a space of about a mile in breadth, northward of the river's bank, and stretching from Knowth to the confines of Netterville demesne, over a distance of nearly three miles. In this space we find the remains of no less than seventeen sepulchral barrows, some of these—the smaller ones—situated in the green pasture lands, which form the immediate valley of the Boyne, while the three of greatest magnitude are placed on the summit of the ridge which bounds this valley upon the left bank, and a few others are to be found at Monk-Newtown, beyond the brow of the hill, towards Louth; making upwards of twenty in all, including the remains at Cloghalea, and the great moat on which the fortress of Drogheda now stands, and known in the Annals as the mound of the grave of the Wife of Gobhan. This latter, however, is on the right or southern bank.

The three great mounds of Knowth, New Grange, and Dowth, principally demand attention, not only on account of their magnitude, but because one of them has remained open for some years, and a third has been lately examined. Each of these is situated within view of the other, and at about a mile distant, and consists, at first sight, of a great natural hill, rising abruptly from the surrounding surface; and this idea is rather strengthened by the circumstance of one of these having become covered with wood, and another having until lately borne on its summit a modern stone building. An eye

practised to the forms of ancient structures at once recognises these vast pyramids as the work of man, and a closer inspection soon sets this point at rest. To follow in detail these magnificent Pagan monuments—for such they are—as they present themselves, in our downward course, we first meet with Knowth, an abrupt, hemispherical mound, with rather a flattened top, rising out of the sloping hill of the townland from which it takes its name. Some enormous masses of stone, arranged in a circular manner round its base, tell us, however, that it is evidently the work of design; and some excavations made into one of its sides show that it consists of an enormous cairn of small stones, covered with rich greensward, occupying in extent of surface about an acre, and rising to a height of nearly eighty feet. As far as we can judge by external appearances, although history is against us, it appears to be as yet uninvestigated; but as there are no means of access to its interior, we can only speculate as to its use, and the mode of its construction, from an examination of similar structures in this vicinity. We therefore pass on to the next monument, that of New Grange, of which the accompanying illustration, taken from the road adjoining, affords a tolerably correct idea.



Like that just described, it consists of an enormous cairn or hill of small stones, calculated at 180,000 tons weight, occupying the summit of one of the natural undulating slopes which enclose the valley of the Boyne upon the north. It is said to cover nearly two acres, and is 400 paces in circum-

ference, and now about eighty feet higher than the adjoining natural surface. Various excavations made into its sides, and upon its summit, at different times, in order to supply materials for building and road-making, have assisted to lessen its original height, and also to destroy the beauty of its outline; but this defect has been obviated in part by a plantation, chiefly of hazel, which has grown over its surface.

A few yards from the outer circle of the mound, there appears to have stood originally a circle of enormous detached blocks of stone, placed at intervals of about ten yards from each other. Ten of these, three of which are here shown,




still exist on the south-eastern side. Such is the present appearance of this stupendous relic of ancient Pagan times, probably one of the oldest Celtic monuments in the world, which has elicited the wonder, and called forth the admiration of all who have visited it, and has engaged the attention of nearly every distinguished antiquary, not only of the British Isles, but of Europe generally; which, though little known to our countrymen, notwithstanding that it is within two hours' drive of Dublin, has attracted thither pilgrims from every land. It is said that a large pillar-stone, or *stele*, originally stood upon its summit. Before we speculate upon the date or origin, or offer any conjectures as to the uses of this vast cairn, we will conduct our readers into the interior, and point out

the objects within most worthy of attention. This mound is hollow; it contains a large chamber, formed by stones of enormous magnitude, and is accessible through a narrow passage, also formed of stones of great size, placed together without mortar or cement; and, considering their bulk and the positions they occupy, exciting our astonishment how such Cyclopean masonry could have been erected by a people who were, in all probability, unacquainted with those mechanical powers so necessary in the erection of modern buildings. Moreover, although some of the stones, both within and without this tumulus, bear marks of being water-worn, and were probably lifted from the bed of the Boyne, others belong to a class of rock not found in the neighbourhood at all; some are basaltic, and others must have been transported here from the Mourne mountains.

When this opening was *first* discovered it is now difficult to say. Sir Thomas Molyneux, who is generally, but erroneously, supposed to have first described this monument, states that the opening was accidentally discovered, by removing some of the stones to make a pavement in the neighbourhood. The earliest describer of New Grange was Edward Llhwyd, the Welsh antiquary, and keeper of the Ashmolean Museum, in Oxford, who, in a letter, dated Sligo, 12th March, 1699, and published by Rowlands, in his "*Mona Antiqua Restaurata*," gave the following account of it, which we quote, the more particularly as he evidently had examined it carefully, and in order that its present state may be compared with its condition 150 years ago.* "I also met with one monument in this kingdom, very singular; it stands at a place called New Grange, near Drogheda, and is a mount, or barrow, of very

* Although the *Mona Antiqua Restaurata* was published in Dublin, in 1723, the letter bears the date which we have mentioned above. In "the collection of such papers as were communicated to the Royal Society, referring to some curiosities in Ireland," we find a paraphrase of Mr. Llhwyd's Essay, printed here in 1726, but much less full, or explicit, than the original. Molyneux's account was printed in his Discourse concerning Danish Mounds, Forts, and Towers in Ireland, first published in 1725. It is, therefore, evident that the original describer was Llhwyd. See also Philosophical Transactions, vol. v. p. 694; Governor Pownall's Description in *Archæologia* II.; Higgins's Celtic Druids; Miss Beaufort's Essay, in Transactions of the Royal Irish Academy; Petrie in Irish Penny Journal; Sir R. C. Hoar's Tour in Ireland, &c. &c.

considerable height, encompassed with vast stones, pitched on end, round the bottom of it, and having another, lesser, standing on the top." When we first visited New Grange, some twelve years ago, the entrance was greatly obscured by brambles, and a heap of loose stones which had ravelled out from the adjoining mound. This entrance, which is nearly square, and formed by large flags, the continuation of the stone passage already alluded to, is now at a considerable distance from the original outer circle of the mound, and consequently the passage is at present much shorter than it was originally, if, indeed, it ever extended so far as the outer circle. A few years ago, a gentleman, then residing in the neighbourhood, cleared away the stones and rubbish which obscured the mouth of the cave, and brought to light a very remarkably carved stone, which now slopes outwards from the entrance. This we thought at the time was quite a discovery, inasmuch as none of the




modern writers had noticed it. The Welsh antiquary, however, thus describes it:—"The entry into this cave is at bottom, and before it we found a great flat stone, like a large

tomb-stone, placed edgeways, having on the outside certain barbarous carvings, like snakes encircled, but without heads."

This stone, so beautifully carved in spirals and volutes, as shown in the graphic illustration upon the opposite page, is slightly convex, from above downwards; it measures ten feet in length, and is about eighteen inches thick. What its original use was,—where its original position in this mound,—whether its carvings exhibit the same handiwork and design as those sculptured stones in the interior, and whether this beautiful slab did not belong to some other building of anterior date,—are questions worthy of consideration, but which we have not space to discuss.


At the same time that this remarkable micaceous slab, which is of a greenish colour, and quite different from the other stones in the vicinity, was exposed, a few years ago, the edge of another very curious, and most exquisitely carved stone, was found projecting from the mound, a short distance above and within the line of the present entrance. That figured beneath represents a portion of the carved edge of this lintel, which projects horizontally above the entrance.




This stone, of which we can only perceive the edge, is five feet eight inches long; its sculpture, both in design and execution, far exceeds any of the rude carvings which are figured, apparently at random, upon the stones found within the cave; and as it never could have been intended to be concealed from view, it is most probable that it decorates the entrance into some other chamber, which further examination may yet disclose. The largest of the Egyptian pyramids contains several chambers, superincumbent upon the great sepulchral vault in which the sarcophagus was placed. This sculptured stone is of

the same composition—a micaceous slate—as the great spirally carved slab beneath, and is not found at all in this neighbourhood; nor, indeed, are any of the great stones of the passage or the chamber of a rock found in the vicinity, while the small broken stones, which form the great bulk of the mound, were evidently gathered around.

We now enter the passage which faces the Boyne; it runs very nearly north and south, and measures sixty-three feet in length; it is formed of twenty-one upright stones upon the right side, and twenty-two on the left, and is roofed with flags of immense length, resting in some points upon the upright side-stones, but in other places chiefly supported by masonry external to them; one of these is seventeen feet long and six broad. The general height of the passage, for about three-fourths of its length, is about six feet: but from the accumulation of earth towards the entrance, it is scarcely so much at present. It then rises suddenly, and again, within seventeen feet of the chamber, it rises so as to slope gradually into its roof; and the stones of which this portion is composed are of gigantic size, many of them eight and ten feet high. Its average breadth is about three feet; but some of the side stones having fallen inwards, so as almost to touch; one requires to creep on all-fours to pass this point. Most of these side stones are remarkably smooth, even on parts where the rubbing of a century and a half could not have produced this polish, and appear to have been long exposed to the action of water or the atmosphere. Some have smooth transverse indentations, as represented by this drawing; and very many of the stones throughout this building, as well as others used for like purposes in the neighbourhood, have small sockets, or mortices, cut near or in their edges, of which we have an example before us. These appear to have been made for the insertion of wedges, either to split the stone, or to lift it.



The passage leads to a large dome-roofed chamber. As all is perfect darkness within this cavern, it is necessary to illuminate it in order to form any just idea of its figure or extent. When about half lighted up, and we begin to perceive the size and character of this great hive-shaped dome, and its surrounding crypts, formed by stones of such immense size, half revealed to us by the uncertain light of our tapers, an air of mystery steals over the senses,—a religious awe pervades the place; and while we do not put any faith in the wild fancies of those antiquaries of the last century, who would make the world believe that this was a great Druid temple, an *Antrum Mythræ*, in which the sacred rites of Paganism,



with its human sacrifices, were enacted, we wonder less at the flight which their imaginations have taken. This cavern is nearly circular, with three offsets, or recesses, from it,—one opposite the entrance on the north, and one on each side, east and west, so that the ground plan, including the passage, accurately represents the figure of a cross.

The wood-cut on the last page, from a rough sketch by Mr. Connolly, gives by far the truest idea of one of these crypts, which we have yet seen. It shows the right or eastern recess, eight feet deep, nine high, and seven broad; it is slightly narrowed at the entrance.

The basement of the great chamber, to about the height of ten feet, is formed of a circle of eleven upright stones, partially sunk in the ground, placed on edge, with their flat surfaces facing inwards, and forming the sides of the cavern. From this course springs the dome, formed by stones somewhat less in size, placed horizontally on the flat, with the edges presented towards the interior; and by each layer projecting slightly within that placed beneath, they thus, by decreasing the circle, form a dome, without an arch, and the whole is closed at top, by one large slab: the stability of the mass is preserved by the pressure of the surrounding material.

This form of roofing, which evidently preceded a knowledge of the principle of the arch, is to be found in many of our early buildings,—generally Pagan, and chiefly sepulchral, in this country,—in the interiors of some of the duns or raths, and in very early Christian oratories; and not only in Ireland, but in Egypt, Greece, and Asia Minor, in one of the pyramids of Sackara, as well as in the remains of a temple at Telmessus. Pococke had observed a similar structure in the pyramid of Dashour, called by the Arab name of Elkebere-el-Barieh; and all the visitors to the Cyclopean-walled Mycenæ are well acquainted with the appearance of the great cavern, known by tradition as the tomb of Agamemnon, and believed by some antiquaries to have been the treasury of Atreus; between which and New Grange comparisons have often been made; their resemblance, however, consists in the *principle* on which the dome is constructed. That remnant of the early Hellenic people was formed by an excavation scooped out of the side of a natural hill; the gallery which leads to it does not appear ever to have been covered in; the sides of the dome spring directly from the foundation, like that at Clady, and not from a row or circle of upright pillars. The interior is perfectly smooth, and was originally covered over with plates of brass; some of the nails which fastened them even yet remain; but these latter circumstances merely show a greater perfection in art among the early Greeks,—the architectural principle perhaps is

the same in both. The ground plan of the great Boyne monument also finds its analogue in the Orient; at Tyre and at Alexandria we find tombs carved out of the solid rock, of precisely the same cruciform shape, having three minor excavations projecting from the several chambers. But while we thus allow ourselves to draw upon our recollections of other lands, we fear our readers, and the visitors to New Grange, for whose use in particular we write, may require some further information as to the measurements, construction, and hieroglyphics of this remarkable monument. The top of the dome is nineteen feet six inches from the floor, which is now covered with loose stones and rubbish. From the entrance to the wall of the chamber opposite measures eighteen feet; and between the extremities of the right and left crypts, twenty-two feet. Each of the side chambers is nearly square, their sides being formed of large oblong blocks of stone; but they are not all of the same size; that on the right of the entrance, the eastern, is very much larger than either of the others, and is also the most enriched with those rude carvings, volutes, lozenges, zig-zags, and spiral lines, cut into the stones, and in some instances standing out in relief, to which we alluded in describing the passage.


In order to afford our readers some idea of these curious markings, we have introduced the accompanying illustrations.

Upon a careful examination of the spiral carvings, we find them nearly all formed of a double coil, commencing with a loop, and, in most instances, having seven turns.—Many of these spirals or scrolls look like the first drawings or markings for the subsequent engraving in relief, such as we find in the finished work of the great flag at the entrance.



The first wood-cut on the next page shows the projecting edge of the top stone in the southern wall of the great right hand recess. The lozenges, six in number, are cut in,

and are about three-quarters of an inch deep. Another specimen of this form of decoration may be perceived on the hori-



zontal slab at the meeting of the passage with the roof. A few of those have carvings upon them of spirals, coils, and zig-zag lines, cut, about half an inch in depth, by some sharp tool.

Here again is a portion of the device found upon the roof of the eastern recess, carved upon a great flag, twelve feet in length, which spans the entire breadth of the crypt. Upon the back of the same chamber we find, and have represented in the first wood engraving on the opposite page, the carving which is to be seen on a projecting ledge,



which juts out from the back wall like a second roof. These "scribings" appear to have been done with a tool like the pick used in roughening mill-stones.

The chamber opposite the entrance affords, at first view,

but few specimens of this curious scroll-work. But that upon the left (the western), which is by far the shallowest, presents



us, besides some of the coil-marks, with two remarkable examples of the carving, cut into its right-hand jamb, totally different in form from all the others.


This, which we find low down upon the side of the stone facing the crypt, differs from all the rest, and has excited much mystical speculation among the followers of General Vallancey, who supposed it to be an undoubted piece of writing; but what the language is, or what tale it tells, they had not made up their minds; and as that school has now become nearly extinct, we fear the matter is not likely to be much further investigated at present. It is of a piece with Vallancey's speculation about the name New Grange (which is evidently of English introduction) having any reference to *Grian*, the sun, &c.



The following very remarkable circumstance struck us while investigating this ancient structure of New Grange, some years ago. We found that those carvings not only covered portions of the stones exposed to view, but extended over those surfaces

which, until some recent dilapidation, were completely concealed from view, and where a tool could not have reached them; and the inference is plain, that these stones were carved prior to their being placed in their present position; perhaps were used for some anterior purpose. If so, how much it adds to their antiquity!

This carving, which is also in the western recess, bears some resemblance to the palm-branch, or to the impression of the male fern, and is not cut so deep as the others. The eastern jamb of the chamber opposite the entrance has fallen inwards, and recently exposed a portion of the under surface of a great flag, which is now, for the first time since the erection of the building, exposed to view. This flag has, like most of the other stones here, a sort of skin, or brownish outer polish, as if water-washed. Now, in all the exposed carvings upon the other stones, the indentures have assumed more or less of the dark colour and polish around; whereas in this one the colour of the cutting and the track of the tool is just as fresh as if done but yesterday. It must have been effected immediately before the stone was placed in its present position. The



question may well be asked, what was the purpose of those; are they mere ornamental carvings, or are they inscriptions from which the history of this monument, or whatever it was originally intended for, might be learned? Are they ideographical, or hieroglyphic, in the strict sense of that word; that is, sacred carving? To this latter we are inclined; and, if we may be allowed to coin a word to express our meaning, we would call them *Tymboglyphics*, or *tomb-writing*, for similar characters have as yet only been found connected with the vestiges of ancient sepulchres, as here, at Dowth, and on tombs of a like character in the counties of Down and Done-


gal. That the meaning of these scriptures, if any such they have, beyond being sacred to the dead, shall ever be brought to light from the haze of obscurity which now enshrouds them, is very problematical.

In each recess we find an oval, slightly dished, or hollowed stone basin, a rude primitive sarcophagus. This, upon the right-hand chamber, which is three feet long, is one of the most perfect, and differs from the others in having two minor indentations cut upon its upper concavity. It stands in another larger and shallower basin, while the western crypts contain but one such sarcophagus, as shown below.



Having conducted our readers thus far over the details, we think they are anxious to know what is our opinion as to the purpose for which New Grange was constructed.

We believe, with most modern investigators into such subjects, that it was a tomb, or great sepulchral pyramid, similar, in every respect, to those now standing by the banks of the Nile, from Dashour to Gaza, each consisting of a great central chamber, containing one or more sarcophagi, entered by a long stone-covered passage. The external aperture was concealed, and the whole covered with a great mound of stones or earth in a conical form. The early Egyptians, and the Mexicans also, possessing greater art and better tools than the primitive Irish, carved, smoothed, and cemented their great pyra-



mids; but the type and purpose in all is the same. From Llhwyl's description we learn, that when New Grange was examined in 1699, it was found much in the same state which it now presents; that "under foot there were nothing but loose stones of every size, in confusion, and amongst them a great many bones of beasts, and some pieces of deer's horns." Neither in this account, nor in that published in Boate's Natural History of Ireland, does he make any mention, either that "the bones of two dead bodies, entire, not burned, were found upon the floor, in all likelihood the relics of a husband and his wife, whose conjugal affection had joined them in their grave as in their bed!" as related twenty-five years afterwards by Molyneux; nor of the "slender quarry-stone, five or six feet long, shaped like a pyramid," which the latter author states lay on the floor. That these rude bowls or typical urns originally contained human remains, we have little doubt; but from a careful examination of the authorities which refer to the accidental opening of New Grange, at the end of the seventeenth century, we feel convinced that this monument had been examined long prior to that date; and, therefore, we derive little information from modern writings as to what its original condition was. That the Danes were well aware that these tumuli contained caverns, and probably knowing that gold and treasure was to be found within them, rifled several of those ancient sepulchres, we have undoubted authority; for in the Annals of Ulster we read the following memorable account of an instance of this description; and although New Grange (which, as already stated, is a mere modern name, which gives no reference either to its use or locality) is not specified, it may fairly be inferred that it formed one of the group of the Boyne pyramids rifled by the plundering Northmen, A. D. 862. "The cave of Achadh Aldai, and of Cnodbha (Knowth), and the cave of the sepulchre of Boadan, over Dubhad (Dowth), and the cave of the wife of Gobhan (at Drogheda), was searched by the Danes—*quod antea non perfectum est*—on one occasion, that the three kings, Amlaff, Imar, and Auisle, were plundering the territory of Flann, the son of Conaing." The Annals of the Four Masters thus record the same circumstance: "The cave of Achadh Aldai in Mughdhorna-Maighen [Breagh]; the cave of Cnoghbbhai; the cave of the grave of Bodan, i. e. the shepherd of Elcmar over Du-

bhath; and the cave of Gobhann at Drochat-atha; were broken and plundered by the same foreigners." All these sepulchres were in one territory, the land of Flann, son of Conang, one of the chieftains of Meath; and, in all probability,* the cave of Achadh Aldai,—that is, the field of Aldai,—the ancestor of the Tuatha De Danaan kings,—is that which is now known as New Grange? How far anterior to the Christian era its date should be placed, would be a matter of speculation; it may be of an age coeval, or even anterior, to its brethren on the Nile.

Were we to strip the chamber and passage of New Grange of the surrounding mound, to remove the domed portion of the cave, and to replace the outer circle, at those parts where it is deficient, we should have presented to us a monument not unlike Stonehenge.

Not only in the surrounding plain, but even on the hill of New Grange itself, do we meet small sepulchral caves and mounds. The whole is one vast cemetery. On the western side of the natural hill sloping from this mound, we some years ago were present at the opening of a small kistvaen, reached by a narrow stone passage,—a sort of miniature New Grange; in it were a quantity of human bones and those of small animals, pigs, sheep, dogs, and fowl; some burned, and some not bearing any marks of fire; but the most remarkable circumstance about it was, that the bottom of this little chamber was lined with stones, the upper surfaces of which bore evident marks of fire,—in fact were vitrified,—showing that the victim, or the dead body, was burned within the grave.

In the north-eastern margin of New Grange is a curiously constructed crypt, like a hermit's cell, but of comparatively modern date. It is, however, worth inspection.

Many years ago, a gold coin of Valentinian, and one of

* Mr. O'Donovan, in his note on Achadh Aldai, in the *Annals*, says: "This place is described by the Four Masters as situated in the territory of Mughdhorna-Maighen, now the barony of Cremorne, in the County Monaghan; but it is highly probable, if not certain, that Mughdhorna-Maighen is a mistake of transcription for Mughdhorna-Breagh, and that Achadh-Aldai is the ancient name of New Grange." It is also added in the same note, "that these mounds were first identified with these passages in the *Annals*, by Dr. Petrie, in his *Essay on the Military Architecture of the Ancient Irish*, read before the Royal Irish Academy, January, 1834." We sincerely wish, with every lover of Irish archæology, that Dr. Petrie could be induced to publish that *Essay*.

Theodosius, were discovered on the outside of the mound; and, not very long ago, a labourer, digging a little to the west of the entrance, discovered two ancient gold torques and a golden chain and two rings. Where are these? Are they in the great national collection of the Royal Irish Academy? Have they been recorded in the *Proceedings* or *Transactions* of that, or any other learned body in the kingdom? No; we regret to say, they were carried out of this country by an Irish nobleman, to exhibit at a learned society on the other side of the channel, in the *Transactions* of which body they will be found figured, together with a letter from their present owner, which, as he is our countryman, we will not quote!



Within view of New Grange, and about a mile distant, seated on one of the higher slopes upon the Boyne's bank, the third great cone of the group attracts our attention,—Dubhadh, or Dowth,—the accompanying view of which was taken prior to the examination of this rath in 1847. Although not so broad at the base as New Grange, it was more conical; the building on the top was a modern structure, a *tea-house* erected by the late eccentric Lord Netterville; and, certainly, although his knowledge or love for antiquities may be questioned, there can be no doubt of his having chosen a spot from whence could be obtained one of the noblest prospects in Meath. A circle of

boulder-like stones, some traces of which even still remain, originally surrounded the base of this mound, which is formed entirely of small loose stones; the external surface, however, has been covered with a thick and verdant sod.

We mentioned that Dowth, or Dubhadh, had been ransacked by the Danes, during one of their inroads in the ninth century; where they broached the mound, or whether they examined all its chambers, it is now difficult to say. A considerable gap existed in the western face of the mound, caused by large quantities of the stones of which it is composed having been removed at different times to erect buildings or to break up into macadamizing materials for the road which passes at its foot. It has been said, we hope without truth, that the grand jury of the county on one occasion presented, in form, for the stones of Dowth, to improve the condition of their roads. In this excavation, on the western side, a passage somewhat similar to that of New Grange had long remained exposed; but, from the falling in of its sides and roof, it was not possible to follow it for more than a few yards on either side. Whether this passage was that originally broken open by Amlaff and his plundering Danes, it is difficult to determine.

A desire having long existed to explore some of these monuments, the Committee of Antiquities of the Royal Irish Academy obtained permission from the trustees of the Netterville Charity, the present proprietors of the Dowth estate, to examine the interior; and funds having been procured, chiefly by private subscription, and afterwards aided by the Academy, the direction of the work was committed to the care of Mr. Frith, one of the County Dublin surveyors; and the Board of Works kindly afforded the tools, or "plant," for carrying on the excavations. Several excursions were made to the spot, for the purpose of deciding on the best means for gaining access to the interior, as, from the analogy to New Grange, it was supposed to contain a central chamber. Opinions were divided as to whether a perpendicular shaft should be sunk from the top by a well-borer, or a horizontal tunnel driven in from one of the sides towards the centre. The remarkably loose material of which the mound is composed presented such objections to both these plans, while the apparent feasibility of obtaining ingress through the passage already open on the western side, so far, at least, as it was possible to follow it,


was so inviting, that this latter plan was adopted; and, although the examination has not been attended with the expected success, we have no hesitation in pronouncing it to have afforded the most valuable results. A catacomb, or series of chambers, not unlike those found beneath the great central chamber in the largest pyramid of the Sackara range, which we described some years ago,* has been fully explored and rendered accessible to the curious, and these we shall presently detail. Having made an open cutting into the western side of the mound, in following out these passages, it was certainly the most advisable, as well as the cheapest plan, to follow in the same course, till the centre was reached. In effecting this, the modern structure on the top was demolished; such, however, was indispensable, and it may act as a warning, and show all the future builders of tea-houses, in such places, what may be the end of their labours. The upper portion above the lintel in this drawing, representing the mouth of the passage, is modern, the stones being replaced by the workmen, but the cut gives a very good idea of the appearance of this passage.

Following this exposed gallery, which runs eastward, and is formed of huge stones, set on end and slightly inclined at top, nine on the right, and eleven on the left, sunk in the ground, and roofed with large flags, similar to that of New Grange,—we are led into a chamber of a cruciform shape, and formed, with slight



* See Narrative of a Voyage to Madeira, and along the Shores of the Mediterranean.

exceptions, upon the type of that already described at page 196, in the great pyramid of New Grange. This passage is twenty-seven feet long, and some of its stones are carved with circles, curved and zig-zag lines. Both in this passage, and at the entrances of several of the minor crypts and recesses which branch from the chamber, we find sills, formed by large flags, projecting above the surface, placed there apparently for the purpose of preventing the external pressure driving in the side walls. The large central chamber is an irregular oval, nine feet four by seven feet, and the blocks of stone which form its upright pillars are fully as large as those found at New Grange, and several of them are carved like those which



we have already described in that place. Many of the carvings, however, at Dowth, which present great beauty of design, differ somewhat from those at New Grange. We find here, in addition to those already figured, a number of wheel-like ornaments and concentric circles, and others with lines radiating from a point; while some very much resemble the Ogham character, consisting of short, straight, parallel lines.* In some

* In A. E. Holmberg's "*Skandinaviens Hällristningar Arkeologisk Afhandling*," there is a figure of a cromlech, with precisely similar markings.

instances we find the representation of a lotus, or lily-leaf, carved with such precision as to give it at first view the appearance of a fossil. And what adds to the interest of these sculptures, particularly that which we just described, is, that the leaf stands out about half an inch in relief, while all the surrounding stone, for many feet adjoining, has been picked away with infinite care and labour. We would direct the attention of the visiter to the great stone, immediately upon the right of the entrance of the central chamber; that, again, upon the right of the northern recess; and others, exposed lately, in the remains of a tomb, or sepulchral chamber, to the south of the present excavations. In the centre of the chamber stands a shallow stone basin, or rude sarcophagus, of an ovoid shape, much larger than any of those of New Grange, measuring five feet in its longer diameter. When the cave was recently opened, only a portion of this basin was discovered in its present locality, but all the fragments, nine in number, have since been recovered in the chambers and passages around, and now complete the entire. There are no basins in the three adjoining recesses. These recesses have narrow entrances, and are less open than those of New Grange; that upon the right and the one opposite the entrance are each five feet deep; the southern recess is six feet nine in length, and, at its western angle, leads into a passage, which opens by a narrow entrance into another series of chambers and passages, the most extensive of which runs nearly southward. The roof of the right hand chamber is nine feet seven inches from the floor. Creeping through these dark passages, and over the high projecting sills which we have already described, we come to two small chambers, one within another, running nearly south-west, and measuring about two feet six each in breadth. Following, however, the long, southern gallery, we find its floor formed by a single stone, ten feet six long; and, in the centre of this flag, we find a shallow oval excavation, capable of holding about one gallon of fluid, and apparently rubbed down with some rude tool, or another stone; it is not unlike one of the shallow, very early quearns in the museum of the Royal Irish Academy. Beyond this flag, and separated from it by a projecting sill, we find a terminal chamber, with a sloping roof, and capable of holding a man in the sitting posture.

The examination of this great catacomb, and the recent exca-

ventions at Dowth, have done good service to the cause of antiquarian research in this country.

No central chamber was discovered, although the centre was reached; it is possible, however, that there may be instead a number of minor crypts existing in the circumference of this great hill. In any future examination of tumuli in this great cemetery, we confess, we would prefer to open one of the minor mounds, situated in the valley of the Boyne: the expense would be much less, and the probability of finding them in their primitive condition very much greater. We hope to see the stones which formed the mound of Dowth replaced in their original position, as so interesting a monument should certainly be restored to the condition in which it was found by those who undertook the examination. This is due, not only to the trustees of the Netterville Bequest, who have permitted the works to be carried on, but to the country at large.

During the excavations some very interesting relics and antiquities were discovered. Among the stones which form the great heap, or cairn, were found a number of globular stone shot, about the size of grape-shot, probably sling-stones, and also fragments of human heads; within the chamber, mixed with the clay and dust which had accumulated, were found a quantity of bones, consisting of heaps, as well as scattered fragments of burned bones, many of which proved to be human; also several unburned bones of horses, pigs, deer, and birds, with portions of the heads of the short-horned variety of the ox, similar to those found at Dunshaughlin, and the head of a fox. Glass and amber beads, of unique shapes, portions of jet bracelets, a curious stone button or fibula, bone bodkins, copper pins, and iron knives and rings, the two latter similar to those found at Dunshaughlin, were also picked up. Some years ago a gentleman who then resided in the neighbourhood cleared out a portion of the passage, and found a few iron antiquities, some bones of mammals, and a small stone urn, which he lately presented to the Academy. Much might here be written upon the remains of the Fauna known to the ancient Irish, did our space permit; we can, however, merely specify some of the bones, and mention some of the articles which were discovered. In the beginning of the last century, a stone urn, somewhat similar in shape to "the upper part of a man's skull," was found in a kistvaen at Knowth; this, we believe,

is now in the collection of the Academy ; it is figured by Molyneux.

The Council of the Royal Irish Academy have promised a report upon Dowth, which is anxiously looked for: the plans and drawings have long since been given in by the engineer. Pending that report, which is in the hands of those best fitted for its preparation, we forbear to enter into the further details of this monument.*

We could point out many other curious structures and ancient remains, both Pagan and Christian, in this neighbourhood. Pillar-stones, probably monumental, stand all round in the valley and on the sloping ground.

The accompanying woodcut shows one of those in the circle of New Grange; it is nine feet high and sixteen in circumference.

A few hundred yards to the south-east of the moat of Dowth we have St. Bernard's Well; some remains of one of those structures denominated Giants' Graves; the old castle of Dowth; and the interesting little church adjoining, which contains, built up in its southern wall, a specimen of very early Irish sculpture, concerning which there is at present little known; it is similar in design to the figure on the cross of St. Adamnan, to which we alluded at page 123. Immediately adjoining are the ramparts, baths, walks, and ponds, made by the late eccentric Lord Netterville, together with some of the finest mulberry trees in this part of the kingdom.

The tourist should visit a small cave, formed with recesses, similar to New Grange, in the pleasure grounds of Netterville; and two other remains, a small circular moat and a fort, in its vicinity. All these antiquarian riches occur within the space of about half a mile; or if we were to extend our range to the mill



* The original sketches of the "Boyne" were commenced in the Dublin University Magazine, several months before any examination of Dowth was undertaken by the members of the Royal Irish Academy.

of Rossan, in Monk-Newtown, we could examine, with much interest, a ring fort and another New Grange, upon a minor scale, which was rudely torn asunder, and left in a dilapidated condition, in the spring of 1847, by some Goth, in order to convert a few of its stones into gate-posts: but we can now merely direct attention to the sites of these latter.

Within the demesne of Dowth or Netterville is to be seen one of the very largest ring forts or military raths in Ireland, except, perhaps, the Giant's Ring at Belfast. It is about 300 paces in circumference, round the top of the embankment, and has a large opening on the south-western side. This O'Donovan supposes was the fort of Dun-na-nGedh, where Domhnall gave his celebrated feast, to which we alluded at p. 176.*

In the same field, and immediately adjoining the road, and now forming the edge of a quarry, we meet Cloghlea, a portion of a stone circle, evidently a part of the side wall or basement of a sepulchral chamber similar to New Grange, than



which it was, perhaps, even larger. Four of these stones, of immense size (one twelve feet long), still stand, two others are prostrate, and two more are lying in the adjoining quarry,—eight in all. Human remains have, on more than one occasion, been found in the vicinity of this remnant of an ancient tumulus. On the edges of these stones will be found indentations similar to those in some of the stones of the passage of New Grange, one of which is figured at page 194.

* See Battle of Magh Rath, p. 7.

CHAPTER IX.

THE ETHNOLOGY OF THE ANCIENT IRISH.

MODES AND MEANS OF STUDYING ETHNOLOGY.—WHO ARE THE IRISH.—HISTORIC REFERENCES.—WHAT REMAINS OF THE ORIGINAL STOCK EXIST.—THE CELTS.—THE FIRBOLGS.—THE TUATHA DE DANAAN.—EARLY IRISH FORMS OF BURIAL.—TUMULI, AND THEIR CONTENTS.—CROMLECHS.—KISTVAENS.—SEPULCHRAL URNS.—INCINERATION.—SCANDINAVIAN RESEARCHES.—CRANIA OF THE ANCIENT IRISH.—BATTLE FIELDS.—ADVICE TO TOMB OPENERS.

THE origin and early history of every nation is involved in considerable obscurity and doubt. As we follow up the stream of time towards its source, or trace back on the page of the world's history, the various people of the earth, we are accustomed to infer the antiquity of a nation from its monuments, or to receive as authority the tales and traditions of its existing inhabitants, when written records are defective. Thus, when we speak of that land of mystery, the offspring of the Nile, we point to its eternal pyramids, its regal tombs, and its solemn and majestic temples, as proofs of the magnificence of conception and design, the perfection in art, the illusive splendour of the religion, and the luxury and pomp of its early occupants. In like manner, and with similar feelings, we view the Acropolis of Athens, or that of Corinth, as instancing taste and refinement among the early Greeks; but, long before the days in which these structures were erected, we turn for proofs of the arts and civilization of the earliest people of that classic land to the tomb and city of Agamemnon, or the Cyclopean-walled Tyrinthus. These, with the ruins of Persepolis, Petra, Baalbec, Hebron, and Palmyra, the palm-groved city of Solomon, together with the various monuments of India and the Americas, the Druid circle of North-western Europe, or the sepulchral pyramid of New Grange, all afford material to the speculative antiquary who takes architecture as his guide, whereby he may unravel the story of our race, or learn, by tracing the similarity in design and artistic execution, either in religious, warlike, or sepulchral monuments, the source from whence the various waves of population were originally given off.

Again, the philologist starts up and traces the origin, or,

if not exactly the origin, at least the connexion between different nations and people, by the study of language, and with most extraordinary assiduity spends years, nay, a lifetime, in investigating the subject of living speech, or the dead but written tongues of various nations; and frequently, by the derivation of some obscure term, traces such cognate affinities—as they are termed—as lead him at once to conclusions often as absurd as they are erroneous. At the same time there can be little doubt that when such investigations are properly and judiciously carried on by men of learning and ability, who bring to the task an extensive acquaintance with the subject of language generally, and who are able to read, or perhaps speak, the tongues they treat of,—in fact, men who have something more than a mere dictionary knowledge of this interesting and hitherto neglected branch of science,—then, and not till then, will any extensive progress be made towards that entrance whereby the paths in the enchanted gardens of the past may be trod with security, and through which the investigator of the natural history of man may yet hope to arrive at the birth-place of nations.

The antiquary in language and the antiquary in architecture and artistic remains seldom agree; and the historian, while he gathers what he can from both, generally increases the maze of difficulty and perplexity under which the reader of the works of the two former labours, by weaving a web of his own, spun from the fables of old songs and imaginative romances, or the legends and traditions still living in the mouths of the people of the country he is engaged in describing. Thus, conjectures the most improbable, and speculations the most absurd, are to be found in the writings of historians on the subject of the early peopling of different countries; and the tenacity with which Irish writers have adhered to the fables of the past has long since become proverbial. Let this not, however, remain a matter of surprise; it has ever been the feeling and the failing of mankind, individually and collectively, to boast of their antiquity. The Tyrians did so in the time of Ezekiel, who, in his graphic and glowing description of the downfall and destruction of their island home, taunts them in these biting and sarcastic words, “Is this your city whose antiquity is of ancient days?” and have we not this feeling starting up in every-day society, and at every

turn, of people magnifying themselves by tracing back their pedigrees like the Hebrews and Phœnicians of old.

Of late years, to aid the investigations of the architect and artistic antiquary, the philologist, and the historian, a fourth science has been called into the field, which, while it in nowise detracts from the former ones, has even already, in its very infancy, done much to advance the proper investigation of the world's history, and promises to prove one of the most industrious and sure handmaids to history generally,—we mean the science of Ethnography, or the natural history of man, including his physical character; his form and stature; the colour of his skin, his hair, and his complexion; his physiognomy; his habits and moral condition, together with his geographical distribution; but more particularly than all the rest, the form of his skull. It sounds strange, but it is nevertheless true, that of all the living creatures that exist upon the surface of our globe, there is none whose zoological characters are, or at least were, until these few years past, so little studied or understood as man, in his animal character. This interesting inquiry, thanks to the labours of Blumenbach, Cuvier, Prichard, Morton, and others, has already become one of popular interest; and although it is rapidly progressing, yet the study of the natural history of man, in the present day, very much resembles the condition geology was in some few years ago, when men generalized from too few facts, and often propounded some wild and extravagant theory from the discovery of a single fossil. Yet, from the vast collections of minerals and organic remains that have been subsequently accumulated, more sober inquirers have drawn up rational and scientific systems. Now, wherever history extends her track, she carries with her, in addition to the traditionary and written records of a country, its antiquities and philology, an inquiry also into the physical characters of the human race or races, either living or extinct, that are to be found therein. Thus to the description left us in the ancient classic writings; to the written records in its hieroglyphic and phonetic writing, and the pictorial exhibitions either carved upon the monuments or imprinted on the walls of tombs and temples; and to those fanes and sepulchres themselves; we are now able, from the examination of the human remains found in that great necropolis of the ancient world,

to add the physical characters of the ancient Egyptians; so that we have almost as lively a representation of the appearance, the warfare, the religious ceremonies, the arts, trades, manufactures and manufacturers, together with the social economy and the habits and manners of that extraordinary people, as any modern writer has afforded us of any country or people at present existing upon the face of the globe. But as other primitive nations were not similarly minded with the red-skinned inhabitants of Thebes, Memphis, or Heliopolis,—as they neither embalmed their dead, carved their sepulchres out of the solid rocks, raised monuments like the pyramids, sculptured statues like the Sphinx or the Memnon, nor left us records of their deeds in a pictorial language preserved for upwards of three thousand six hundred years,—we have but scanty means whereby to found a probable theory as to their origin, habits, or condition, prior to the date of authentic written testimony. And as a country presents more or less of ancient monuments of art, or vestiges of language, even without the aid of written records, so will the antiquary or the historian possess in a greater or less degree the data whereon to found some rational theory as to the date of its first colonization, or the origin of its inhabitants, with their religion and their civil and social condition.

Having offered these brief remarks upon the best means for investigating the early history of a country, we now come to ask ourselves the questions, who we are?—from whence sprung the Irish race?—to what tribes of mankind did we originally belong?—at what period was this country first peopled, and what vestiges of that aboriginal race still exist amongst us to point out their physical characters, their habits, social, warlike, or domestic, their religion, or knowledge of literature, architecture, and the arts? The last inquiry is that most easily answered; we have still remaining in the island some relics of the early inhabitants, chiefly their sepulchral monuments, the cromlech and the kistvaen, the monumental pillar, the rude altar, the terracotta urn, a few bone and shell ornaments, and a variety of flint and iron weapons and implements, knives, arrow and spear-heads, and stone hatchets, together with that which it is our more immediate province to bring before the reader, their bones and skulls; and this may really be said to sum up all that is positively

known about them. As to the inquiry of who they actually were, or from whence they first came, although it may be ungrateful to our national pride to acknowledge it, we must confess we are still wandering in the trackless fields of conjecture. But is this peculiar to the Irish nation? By no means. In Egypt, which for its antiquity and frequent mention in the earliest authentic writings, we have chosen for illustration, we see the monuments of the earliest date, we read the history of its people in characters which vividly bring before us their manners and customs; everything is there portrayed with the freshness of yesterday; the bodies of thousands upon thousands of its people still remain as they came from the hands of the embalmer, as if ready to start into a second existence; the arms of the warrior, the robe of the priest, and the toilet of the lady, are there ready for our inspection: yet, with all this, we positively know nothing certain as to who first peopled the valley of the Nile. So it is with the first people of America,—so with the Chinese,—so with the Irish: the certainty of origin cannot be traced back to any extent. There are, however, a few exceptions to this very general rule in those primitive nations against whom we read of certain direct and positive denunciations being issued by the great Disposer of the goings of man. Have we not still, after the lapse of hundreds upon hundreds of years, the “servant of servants” in the oppressed and enslaved sons of Africa? and do we not meet in the swarthy, sinewy child of the desert, the lawless Bedouin, who knows no law but his own will, and owns no master but his own appetite,—the man “whose hand is against every man?” But, above all, have we not that living miracle still before us, the Hebrew people, ever remaining distinct and separate, though outcast, scattered, and despised, with an unbroken descent, and an unaltered lineage from their forefather Abraham to the present day? These are nations, and we believe the only ones, where, in addition to their stereotyped physical characters and personal appearance, history has afforded a chain of evidence, as to their origin and descent, from the earliest period to the present.

To enumerate the various opinions, the crude hypotheses, the absurd and fanciful traditions of writers as to the origin of the Irish people, might, did space permit, or the subject we are about to treat of require it, afford us amusement, but

certainly little instruction. Some assert that the early people of Erin were a Gothic race, but most writers seem to agree that we were a Celtic colony; but who the Celts were, from whence they sprang, what country they first inhabited, into what tribes they were divided, what was their original language, or what their physical characters or personal appearance, has not yet been decided by the learned; nor whether they existed coeval with, or how they differed from the Gothic, the Teutonic, or the Belgic races, in the early peopling of the western and south-western countries of Europe. And yet how learnedly, how frequently, and with what confidence, do we hear the term "Celts," or "of Celtic origin," or "Celtic Druids," or "the Celtæ and the Belgæ," with such like expressions, made use of in scientific as well as popular discourses! We believe that if the exact meaning of the persons who make use of these expressions was to be inquired into, it would be found to consist in neither more nor less than the original or primitive inhabitants of the countries under consideration. Having taken some trouble in inquiring into this matter,—having examined several authorities that allude to this race,—having traced them, as we thought, from country to country in Europe,—having sought after their remains in the collections of the curious, or in the writings of the modern learned, we found ourselves, like many others, although in possession of a large collection of facts and references bearing upon the origin of the Celts, and their connexion with Ireland, nearly as wise as when we commenced the investigation. In fact, we found we were running in a circle; and what one author put forward to-day, another contradicted to-morrow; so that the nearer we approach the age we live in, the more incongruous and uncertain become the opinions that are set forth. Herodotus informs us that the Celtæ were the primitive people that sprang from the borders of the Danube, yet we possess a skull found in an ancient tumulus on the confines of Hungary, which is evidently altered by artificial pressure, and in a remarkable manner resembles those compressed crania found in the sepulchres of the ancient Peruvians, particularly in the valley of Titicaca.* Similar tumuli, and containing similar re-

* See "Austria and its Institutions," p. 49, where there is a drawing of this very remarkable skull, for a cast of which we are indebted to Count Albert Thun, of Prague.

mains, stretch along the borders of the Danube, through both the Austrias, and extend in a north-western direction into Moravia, and even Bohemia.

Let us now turn to the immediate object before us. With the peopling of Ireland before the flood, as related in Irish manuscripts, or in the legends detailed by Keating, and, since his time, copied into all the popular histories of this country, we do not now deal. They may, or may not be fact, but they affect not the present subject. All authorities agree in according to this island inhabitants at a very early period, long prior to the Christian era: who those aborigines were, or from whence they came, is involved in the same mystery that hangs over the origin of the early people of Europe generally. In Irish they are generally denominated Firbolgs; and it is reported that under them a settled form of government was first introduced into this island. In the mixture of fable and fact which relates to these people, either traditional or in our manuscripts, very little of their habits or physical characters has come down to our time. Of this people, says Dr. Petrie, in his learned Essay on the History and Antiquities of Tara,—“According to the Irish bardic traditions, the hill of Tara became the chief residence of the Irish kings, on the first establishment of a monarchical government in Ireland, under Slainge, the first monarch of the Firbolgs, and continued so till its abandonment in the year 563.” In an Irish manuscript, the Book of Mac Firbis, written about the year 1650, an account of which, from a translation by Mr. Eugene Curry, has been laid before the Royal Irish Academy, by Dr. Petrie, it is said that “every one who is black, loquacious, lying, tale-telling, or of low and grovelling mind, is of the Firbolg descent.” To this Firbolg race a Belgic origin has been usually assigned; those Belgæ appear to have been of German or Gothic extraction; and as far as history has left us a trace of this people, they seem to have been followed, and subsequently subdued, by the Celtæ.

In the Irish version of the *Historia Britonum* of Nennius, we have some account of the early people of this country, from the time of the arrival of Partholan, whose descendants, the early colonists of Erin, were cut off by a plague, it is said, in one week, A. M. 2820. Then came Nemed, and “the Viri Bul-lorum, i. e. the Firbolg,” so called, it is said, by Keating, from

the leathern bags which they had with them in Greece, for carrying mould to lay it on the flat-surfaced rocks, so as to convert them into flowery plains; but as Dr. Todd, the learned editor of the work from which we quote, justly remarks, "Bullum, in the Latinity of the middle ages, signified, according to Du Cange, *Baculum pastoris*, which suggests a derivation of the name Fir-Bolg." Wherever they came from, it would appear that they were a simple pastoral people, who possessed little knowledge of art, science, or war, even according to the acceptation of these terms in the limited sense to which they may be applied in the very early ages. With these afterwards appeared the Fir-Gaileoin, the Viri Armorum, or Spearsmen, perhaps from their warlike propensities: and also the Fir-Domnann, who, as well as the Firbolg, seem to be a pastoral or agricultural people. "Afterwards the Plebes Deorum, i. e. the Tuatha De Danaan, took Ireland; it was of them the chief men of science, as Luctenus, artifex, Credenun, figulus [brazer], Dianus, medicus; also Eadon, his daughter, viz., the nurse of the poets; Goibnen, faber; Lug, son of Eithne, with whom were all arts. Dagda, the great son of Ealadan, son of Dealbaith, the king. Ogma, brother of the king; it was from him came the letter of the Scots"—Ogham.*

The Annals of the Four Masters inform us that the three last kings of this race who were in joint sovereignty over Ireland in A. M. 3471, were Mac Cuill, Mac Ceacht, and Mac Grein. Mr. O'Donovan has added the following valuable comment on this:

"According to an old Irish poem, quoted by Keating in his *History of Ireland* (See Haliday's edition, p. 212), the real names of these kings were Eathur, Teathur, and Ceathur; and the first was called Mac Cuill, because he worshipped the hazel tree: the second Mac Ceacht, because he worshipped the plough, evidently alluding to his wish to promote agriculture; and the third, Mac Greine, because he worshipped the sun as his god. For some fanciful disquisitions upon the history and names of these kings, the reader is referred to Vallancey's Vin-

* See "The Conquest of Eri, as recorded by Nennius," p. 45, *et seq.* We have given this account of the early Irish colonists from the volume recently published by the Irish Archæological Society, rather than extract from the more ancient but fanciful history of Keating, who must have drawn up his account of these people from this and similar other authentic documents.

dication of Irish History, p. 496. In Mageoghegan's translation of the Annals of Clonmacnoise, it is stated that 'this people, Tuathy De Danan, ruled in Ireland for 197 years; that they were most notable magicians, and would work wonderful things by magick and other diabolical arts, wherein they were exceedingly well skilled, and in these days accompted the chiefest in the world in that profession.' From the many monuments ascribed to this colony by tradition, and in ancient Irish historical tales, it is quite evident that they were a real people; and from their having been considered gods and magicians by the Gaedhil or Scoti, who subdued them, it may be inferred that they were skilled in arts which the latter did not understand. Among these was Danann, the mother of the gods, from whom *Da ùic Dananne* (the two paps of Danan), a mountain in Kerry, was called; Buanann, the goddess that instructed the heroes in military exercises, the Minerva of the ancient Irish; Badhbh, the Bellona of the ancient Irish; Abhortach, god of music; Ned, the god of war; Nemon, his wife; Manannan, the god of the sea; Diancecht, the god of physic; Brightit, the goddess of poets and smiths, &c. It appears from a very curious and ancient Irish tract, written in the shape of a dialogue between St. Patrick and Caoilte Mac Ronain, that there were very many places in Ireland where the Tuatha-De-Dananns were then supposed to live as sprites or fairies, with corporeal and material forms, but indued with immortality. The inference naturally to be drawn from these stories is, that the Tuatha-De-Dananns lingered in the country for many centuries after their subjugation by the Gaedhil, and that they lived in retired situations, where they practised abstruse arts, which induced the others to regard them as magicians."

Professor Rask supposes the aborigines of Western and South-western Europe to have been an Euskarian race, from whom sprang the Iberians; and his researches lead him to believe that he can discover traces of the Euskarian language among the French Basques and Spanish Bascayans, as well as in some of the Finnish, Lapland, and Danish tribes; and it has been even asserted that an inhabitant of Ireland and a Spaniard of the Basque provinces, could understand one another. Mr. Borrow, who is probably better acquainted with the Euskarian tongue than any other Englishman at present, asserts that there is not the slightest affinity between them; but accu-

rate as Mr. Borrow's knowledge of the old Spanish may be, he does not appear to be sufficiently versed in the Gaelic, to offer as correct an opinion on it as on most other European tongues. In fact, to approach or handle this subject effectually, we should have scholars versed in the composition and construction of both languages, as well as possessing a fluency of speech in both, especially since mere sound is often the point of resemblance most relied on. From whatever examination we have been able to make, and from the communications with which we have been favoured from other countries, we find traces of the same aboriginal people spread over a large portion of the central and north-west parts of the European continent, together with Ireland, and probably Great Britain also. Whether this first wave of population arrived here from the East, having passed over to us from the South, as from Gaul and the littoral parts of Spain, or by the North, from Sweden and Denmark, is not so easy to determine. At all events, we find the remains of this people precisely similar, and the circumstances under which they are found accurately corresponding in every country where they have yet been discovered. Now, for distinction sake, we will call these the aborigines, and, in accordance with our traditions and histories, the Firbolgs. It is next related that the aborigines were overcome by another, and, evidently from the accounts in the manuscripts, a superior race, the Tuatha De Danaan. These hostile invaders, who are stated to have been skilled in magic, necromancy, and the like black arts, are supposed by some writers, even in the present day, not to be human beings at all, but fairies or sprites. There are, however, too many existing records of these fleshly inhabitants of our isle to doubt their identity; and we believe the very arts and magic assigned to them, particularly by the rude, simple, and comparatively ignorant aborigines of our country, arose from their knowledge of so much chemistry as related to the art of mining and the smelting of metals. Of the physical characters of this people we have but little knowledge. It is, however, related in the manuscript Book of Mac Fírbis, to which we have already alluded, that "every one who is fair-haired, of large size, fond of music and horse riding, and practises the art of magic, is of Tuatha De Danaan descent." That these people were skilled in medicine we have elsewhere shown, and one of the oldest Irish manuscripts on record gives an account

of the celebrated battle fought on the plains of Moy Turey, in the county of Sligo, when Nuada Airgeat Lamh, the king of the Tuatha De Danaan, completely routed the Belgæ or Firbolgs, a vast number of whom are said to have been slain; and on that battle-field, the Marathon of Irish history, we have still remaining the tumuli or barrows erected over the remains of our early Pagan progenitors. Dr. Petrie detailed to the Academy, in the year 1838, an account of a most remarkable collection of cairns, cromlechs, and stone circles, at Carrowmore, in the vicinity of Sligo, all containing human remains. "Such monuments," he stated, "are found in all the battle-fields recorded in Irish history, as the scene of contest between the Belgians or Firbolgs and the Tuatha De Danaan colonies, and he considers these monuments to be the tombs of the Belgians, who, after their defeat in the battle of southern Moy-Thuree, had retreated to Cuil-Iorra, and were there again defeated, and their king Eochy slain in crossing the strand of Ballysadare bay, on which a cairn rising above high water still marks the spot on which he fell." To these Tuatha De Danaan, or metal workers, we are inclined to assign a Celtic origin, and to their art and ingenuity to attribute the workmanship of those beautiful bronze or antique-metal ornaments and weapons, formed by a mixture of copper and tin, so generally found over the face of the country, and now swelling our national collection at the Royal Irish Academy.

The Irish are said to be a Phœnician race, and perhaps these Tuatha De Danaan were the Phœnician Cabiri. We are quite willing to bow to those antiquaries who endeavour to show an early connexion between Ireland and the Tyrian people, and are personally willing to adopt, though we may not be able to prove, the opinion expressed as to the Oriental commerce with this country direct from Tyre and Sidon, or through their colonies in Spain and Tuscany; but it has not been proved that the Phœnicians were the *original settlers* in Ireland. The Gaelic is not the Punic tongue, although we believe the remains of the latter are insufficient to determine the point; but we do confidently assert that the earliest record of the Phœnician people exhibit them to us in the highest state of civilization of that day,—a great commercial and perhaps a literary people also,—skilled above their fellows in all the arts of the time. Sidon and its daughter Tyre, the cradle of Oriental art, are

mentioned by undoubted authority, as flourishing cities nearly sixteen centuries before the Christian era. More than a thousand years before that epoch, their inhabitants were the greatest artificers in the world, and were invited by the wisest and most gorgeous monarch of the East to construct the most splendid edifice that history, either ancient or modern, can point to; and from a people whom the great prophetic poet of the Babylonish court described as exceeding in power, luxury, and magnificence all surrounding nations, we cannot believe sprung the simple early inhabitants of Ireland, to whose handiwork we ascribe the rude cinerary urns, the cromlechs and kistvaens, with shell ornaments, bone pins and bodkins, and some stone weapons, found in tumuli, nor even to the people who lived in the early age of bronze that followed that period. It is a fact,—curious, but generally overlooked by Irish historians who bring hither colonies of different nations,—that there are but the remains of *one* language known in manuscripts, or spoken amongst us.

The Tuatha De Danaan were in turn overcome by the Milesian race [perhaps the Gaedhil or Scoti], but with this people our subject has little to do; for even if the Milesians did come to Ireland at the time and in the manner told in history, and that all the circumstances attending their invasion be as related by the Irish bards, still we believe they differed not in physical characters from their brother Celts who preceded them, although in civilization they were more advanced. After a long lapse of years, when Paganism had given place to Christianity, history becomes more definite in her terms, and more accurate in her descriptions. Probably about the year A. D. 900, those hardy, enterprising Northmen, who conquered wherever they trod, and found their way wherever there was a wave to carry them, landed upon our coast, and held sway for some time over the then existing inhabitants of our country. To this naval and warlike people, and to the age of their invasion, are generally attributed the iron weapons and implements discovered in this country. Dr. Prichard inclined to the opinion that the Romans assisted in the civilization of Ireland; but, with great deference to that eminent authority, we submit that there never have been any remains of that people discovered in this country, and we do not believe the Roman people ever

had a footing in Ireland. With the various English invasions in more modern times every reader of Irish history is familiar.

We shall now demonstrate some of the human remains of the first or earliest inhabitants found in this country, and detail the circumstances under which they have been discovered. At the beginning of the last century, the distinguished physician, Sir Thomas Molyneux, was the first to investigate this interesting subject, which, from his day until the publication of the Proceedings of the Royal Irish Academy a few years ago, remained forgotten and neglected; and the very prejudices and superstitions of the lower orders of our countrymen who might accidentally open any of the ancient burial-places, led them to secrete or destroy any human remains found within them. Owing partly to this cause, and partly to the circumstance of their value not being understood from the days of Molyneux until within the last dozen years, there does not appear to have been any regard paid by antiquaries to the preservation or description of human remains. The following summary includes an account of the various forms of burial made use of by our aborigines, at least so far as we have any authentic account of them:—First and most notable is a dome-roofed stone chamber, containing the remains of one or more bodies, and approached by a covered way, the whole being enclosed in a large earthen tumulus or barrow, and generally surrounded by a circle of upright pillar-stones. This is the true pyramid, modify it as we please, of which the type is to be found in those great oriental monuments, with the characters of which all are acquainted. The most splendid specimen of this description, which we know of in Central or North-western Europe, is the magnificent mausoleum at New Grange, which may well be denominated the Great Pyramid of the West. When New Grange was first opened, a great many years ago, we are told that “two entire skeletons, not burnt, were found on the floor;” but what characters these bones presented, or with what emblems that might mark the date of their interment, we know not, as none of the remains discovered in this vault have come down to the present day. We only hear that the bodies were buried entire, and not burned. In 1839, the account of a tumulus of a similar character, found near Rush, in this county, was presented to the Royal Irish Academy by Lieutenant Newenham. This barrow, called Knochlea, consisted of a chamber about eight feet long and

six wide, placed beneath an immense heap of earth and boulder stones. The chamber was approached by a stone-constructed passage, eleven yards long and one in width. "The lines of stones forming the sides of the passage appear to continue on through the mound towards the north side; and a few feet below the present surface of the barrow, a little to the north of the chamber, there is a bed of periwinkle shells, about eight inches thick, with some limpet and muscle shells intermixed; and beneath this bed of shells there was a quantity of dark, rich mould, with some reddish earth, which has the appearance of being burned. A few human bones, and some bones of small animals, were found in the earth beneath."

Professor A. Retzius, of Stockholm, and Professor Eschricht, of Copenhagen, two most distinguished northern philosophers,—and whose opinions in almost every particular correspond with and confirm the views which we have on two or three occasions ventured to put forward with regard to the characteristics of the aboriginal Irish heads, and the circumstances under which they are found,—have published accounts of the crania of the ancient people of Scandinavia, and the graves or tumuli in which they have been discovered.*

Eschricht informs us that two large tumuli, or "warriors' barrows," as they are popularly denominated, having been opened in the vicinity of Stege, "the position and the contents, which were almost the same in both, testified that they belonged to the barrows of the oldest period. Through a narrow aperture on the south side of each of the barrows ingress was given to a small passage, and thence to a chamber in the middle of the barrow, the proper sepulchral chamber." The passage and sepulchral chamber were constructed with large, flat, unhewn stones. It appears that the smaller tumulus of the two had previously been partially opened from above by some peasants,

* This communication was originally published in a small Danish periodical, the "*Dansk Folkeblad*," by Professor Eschricht; but his views having been questioned by Professor Nilsson, of Lund, who has also written on the Swedish crania and antiquities, they did not at first receive the acceptance which they undoubtedly deserve. We are much indebted to Professor A. Retzius for a copy of S. Nilsson's rare and most valuable work,—"*Skandinaviska Nordens Ur-Inanare ett Försök I Komparativa Ethnografien*," &c., Lund, 1838-1843,—where there are several lithographic representations of the northern crania. Nilsson asserts that the globular crania found in northern tumuli belonged to a Lapland people of the Mongolian race.

and no skeleton was found in it; but several stone weapons, clay urns, and a great number of amber ornaments, lay scattered throughout. In the larger barrow the passage was ten ells long, and the sepulchral apartment sixteen; the walls consisted of large oblong stones, the interstices between which were carefully filled up with slabs of split sandstone. The weapons, tools, and ornaments found in this barrow were all of stone, bone, shell, or amber; but what interests us most are the remains of nine or ten human bodies discovered in this sepulchral chamber, the heads of which were of rather a small size; and this wood-cut is a reduced representation of one of them.

The description of head from which this was taken has many analogies with the remains of a globular-headed race found in ancient sepulchres in our own country, to be described presently. So small a head, says Professor Eschricht, is seldom found among the present Danes. It is the face, however, which appears small;



the capacity of the skull is proportionably large. With regard to the peculiar tribe or race of people to whom this head belonged, all the conjecture that the learned Dane has ventured upon is, that these individuals belonged to a noble tribe of the Caucasian race; but whether Celts, Goths, or Lapps, he does not say. The facial portion of these heads being small, without doubt the whole body was not above the middle size. The traces of the facial muscles, on the other hand, were exceedingly strong; the play of the features was, therefore, during life, very energetic. The orbits or eye sockets are very small, low, and deeply hidden under the eye-brows. The nasal bones were particularly strong, prominent, and inclined towards the horizontal, with a deep groove or sulcus between their root and the margin of the brow. These people must, therefore, have had strongly marked, arched, prominent noses. In those casts and drawings which have been forwarded to us from Denmark and

Sweden the projections which support the eye-brows, or the superciliary ridges as they are styled in technical language, are remarkably prominent; and we are led to believe that the eyes themselves must have appeared small and sunken; and, says our correspondent, "the small face, with the lively play of the features, the small eye set deeply under the eye-brows, and the large, aquiline nose, are characteristics which, taken together, imply a dark colour of the skin, eyes, and hair;" but the globular-headed Saxon Germans of the present day have generally light hair and blue eyes.

A second excavation of a barrow of great size was subsequently undertaken, in the island of Moen, at a place called Maglehaei. The sepulchral chamber in this contained twenty human skeletons, together with the skull and some bones of a dog, and the implements and ornaments were of the same character as those in the early excavations, consisting of bone, stone, and amber, but not the least trace of metal of any description. It is interesting to remark that upon one of the skulls found in this collection, a portion of dark brown hair still remained.

We now turn to another age in northern Europe, the bronze or metallic period. In the summer of 1821 there was dug up at Funen, in a gravel pit, two human skeletons, surrounded, it is said, by various metallic



articles. A silver buckle lay on the breast, a spirally twisted gold ring, like our torques, surrounded one of the fingers, and a large metal pan or kettle lay at the feet. The skulls presented a totally different appearance from those found in the stone chamber, and in connexion with stone ornaments and weapons. This is a faithful representation of one of these long low skulls. The skeletons belonging to this race are said to be of a stature above the common. Subsequently to

Eschricht's communication, we were favoured with one from Professor A. Retzius, together with the cast of a cranium, of what he terms "an ancient Swede towards the end of the heathen era;" it is of the long-headed race, and he mentions that this is one of the common forms of head among the modern Swedes; and both he and Nilsson classify all the heads found in northern tumuli into—first, the oldest, with square-shaped heads like the Laplanders, found along with tools, and hunting or fishing tackle of stone or bone; second, the long-headed race, always accompanied with metallic implements, and which race they considered to be Celtic; and the third, an oval form, also accompanied by metals.

It would extend this ethnographical notice, which is intended chiefly for the popular reader, to too great a length, to detail the various other kinds of ancient burial found in northern countries, but we may remark upon one form of ancient grave found there, of which we have no example in this country, and that is the T-formed or hammer-shaped, of which it would appear there are a vast number, some of great size, and containing many skeletons, generally lying at full length, but sometimes placed in a doubled-up or sitting posture, like those of the ancient Peruvians. These sepulchres are, like that at New Grange or Dowth, formed of huge stones, placed on end, and roofed with immense flags, but not dome-roofed; neither are the basement stones arranged in circles like our's: the lines are nearly always parallel.

We now turn to the Irish heads again, and with them to the second form of burial, the cromlech, where the stone chamber under the centre of a mound is not approached by a passage as in the pyramidal structures at Grange, Dowth, or Rush, and contains one or more skeletons placed in a horizontal or recumbent posture. This is not the place to discuss the old question of the purpose of cromlechs; the opinion of their being altars seems to have completely given way to their sepulchral use and origin; and chiefly from the discovery and accurate investigation of a tumulus at Knockmaroon, in the Phœnix Park, near Dublin, by a committee of the Royal Irish Academy, in 1838.* Within this stone chamber two perfect male skeletons were

* The stone vault, or chamber, of a similar one, is now preserved in our Zoological Gardens.

found in a recumbent posture, and also the tops of the thigh bones of another, and a single bone of an animal, supposed to be a dog. Immediately under each skull was found collected together a number of small sea shells (the *Nerita litoralis*), which evidently formed a necklace; and a small fibula of bone, precisely similar to those found in Denmark, and a small flint arrow-head, were likewise discovered in this kistvaen. Within the mound which formed this sepulchre, but not within the tomb, were found four urns of baked clay, containing incinerated human bones. The two heads found in this sepulchre are, perhaps, the most perfect of their kind in existence; they are chiefly characterized by their extreme length from before backwards, or what is technically termed the antero-posterior diameter, and the flatness of their sides; and in this and most other respects they correspond with the second form of head discovered in the Danish sepulchres, but different from it; these long-headed aborigines of Ireland, and indeed we may say all our skulls discovered in sepulchres of undoubted heathen times, are never found in connexion with metallic substances, but only with stone, bone, shell, or baked clay ornaments, weapons, or implements.

These skulls, one of which is exhibited in this representation, present the same marked characters in their facial aspect, and the projecting occiput and prominent frontal sinuses, as the Danish ones. The nose, in common with all the truly Irish



heads we have examined, presents the most marked peculiarities, and evidently must have been very prominent. With this we have evidences of the teeth having been slightly projecting, and the chin small, square, well-marked, and also prominent; so that on the whole this race must have pos-

sessed peculiarly well-marked features, and a shrewd, intelligent physiognomy. The forehead is low, but not retreating. The molar teeth are remarkably ground down upon their crowns, probably from long trituration of farinaceous food, and the attachments of the temporal muscles are exceedingly well-marked. It may be asked, do the characters exhibited in those skulls express the general appearance of a peculiar people,—were they not accidental varieties? No; we have already examined too many heads of a like character to be mistaken on this point; and, moreover, although we find every variety of head among the modern mixed races of civilised countries, when we come to examine primitive people, or savage tribes, we find the character of their crania and general physical condition more and more stereotyped as we recede from civilization.

Four years ago, while passing through the museum of Guy's Hospital, our eye lighted on a pair of heads lying in a remote corner, which we at once claimed, from their exceeding length, &c., as fellow-countrymen. Through the kindness of our friend, Mr. Dalrymple, we have received casts of these skulls, together with the following account of them. They were discovered, along with fifteen entire skeletons of both sexes and various ages, in 1821, in a great tumulus near Denley, in Gloucestershire; they were placed in several chambers beneath the cairn, which was 120 feet in length. Some bones of the wild boar, and two flint axe-heads, were also found in the tomb, but no remains of metals.*

* For an account of an ancient tumular cemetery recently discovered at Laurel Hill, near York, see Dr. Turnham's paper in the Proceedings of the Yorkshire Philosophical Society for June, 1848.

While examining the splendid collection of heads in the museum of anatomy in the Jardin du Roi at Paris, in 1840, along with the late distinguished Dr. William Edwards, two skulls, without labels or any marks to denote their locality or race, were presented to us. These, from their peculiarly long form, we at once pronounced to be ancient Irish. A laugh being raised at this surmise, and Mons. Laurillard, the Curator, not being able to give any account of them, Mr. Pentland, who presented them, was written to, and his answer informed us that they were found in Etruscan tombs of the very oldest date, which were opened in 1828, near Sarteano; and that with these heads were also found a number of antique vases. How far this supports the peculiar theory of Sir William Betham, we cannot take upon us to decide; but with the similarity of form which these skulls presented to the most ancient Irish and Norwegian, we were instantly struck.


Now we find conditions of head and feature similar to both the early Irish races still existing among the modern inhabitants of this country, particularly beyond the Shannon, towards the west, where the dark or Firbolg race may still be traced, as distinct from the more globular-headed, light-eyed, fair-haired, Celtic people who lie to the north-east of that river. Strange to say, the skull of Swift exhibits most of the peculiarities of this early race, though, as most people assert, he was not of Irish descent; and any one who has examined the old skulls found in the ancient burial-grounds either in Connaught or in Kerry, must have been struck with the appearances which we have now described.

We next come to the third form of burial, containing the relics of the second race of people; for of the first, or those found in the pyramidal structures with the stone passages, we have not seen the remains, and therefore cannot speak as to their form. The vault in which the remains of this second race are generally found is usually beneath the surface, a kistvaen, or small stone chamber, roofed either with a single flag, or covered in with that form of arch resembling a bee-hive dome. There is no tumulus or heap of earth to mark the site of these sepulchres, several of which have been turned up with the plough. Within this small square vault the bones are generally placed in a regular manner, the small ones at the bottom, the long ones, as the legs and arms, at the top, and the whole is crowned with the skull. One of these was found a few years ago in the neighbourhood of Dublin; it is much better proportioned, higher, more globular, and in every respect approaches more to the highest forms of the Indo-European variety of the Caucasian race, than either of the foregoing. It is said, but, we believe, upon very questionable authority, that metallic weapons and instruments have been found in connexion with this form of burial.

That most beautiful cranium figured upon the next page was presented to us by our friend Mr. O'Donovan, and we fear not to assert that in symmetry and general development it comes up to some of the finest Grecian models, though the general capacity of the head is small; but it may have belonged to a small race or a small individual. The small stone chamber in which this skull was found, five years ago, was situated in the outer circle or breast-work of a rath, within 150 yards of the

south side of the Rock of Dun-Masg, or Dunamase, in the Queen's County. Close by the side of the skeleton was found a cinerary urn, with one exception the most beautiful of its kind, either in design or execution, ever discovered in this country.*

The fourth and last form of burial is what may be termed the urn sepulchre, in which we have manifest traces of the burning of the bodies having taken place; but to what age or to what people in particular we are to refer this ancient heathen rite, cannot, we think, be determined; for the cinerary urn, containing the remains of burned human bones, has been found not only as a separate and distinct form of burial, but also in connexion with the cairn, the cromlech, and the kistvaen or small stone chamber. Moreover, we have instances of bones being found partially or completely burned in some of the larger sepulchres, without any trace of the urn whatsoever. Urns containing human remains have been long known in this country, and were first well described by Molyneux, whose remarks upon them have since been copied by Harris into Ware's, and most of the publications that treat of the antiquities of Ireland. In June, 1842, Mr. J. Huband Smith communicated to the Royal Irish Academy a description of the recent discovery of a vast number of cinerary urns at the "Hill of Rath," within a few miles of Drogheda. In the progress of working a quarry at the foot of the hill a farmer discovered



* The most beautiful urn of its kind ever found in Great Britain, either in design or execution, is that small, echinus-shaped urn, with an ear or handle, lately found in the county of Carlow, near Bagnalstown, and which we described in the Proceedings of the Royal Irish Academy for January 10, 1848.

from 150 to 200 urns of unbaked clay, of various sizes, almost all placed in an inverted position, and each of them covering a considerable quantity of human bones. "They were placed, apparently without any regularity, about two or three feet asunder, and having been imbedded in yellow clay, without any flags or stones to protect them, had, in most cases, been pressed in and broken to pieces by the superincumbent earth." Some of the urns were very large. We have carefully examined the contents of one; they bear evident marks of fire, and consist of the bones of several individuals, as well as bones of birds, and a small animal of the dog kind. In another urn was found a flint arrow-head and a small bone needle.*

The second circumstance under which we find cinerary urns is in connexion with the cromlech; and the third, with the small stone kist: an example of the first of which was well shown in the tumulus in the Phoenix Park, where four sepulchral vases, containing ashes and burned bones, were found throughout the tumulus, enclosed in small separate stone chambers, but not within the cromlech itself; whereas in the third form, as in the kist at Dunamase, the vase is found in immediate connexion with the body, and within the chamber. To what period, or to what particular people these urns belong, it is difficult to determine, for we find them with nearly every form of burial among our ancient people. The condition of their contents determines the point as to the ancient people of this country burning their dead; but whether as a sacrificial or funereal rite we leave to the antiquarians to determine. This we may remark, that where found by themselves, as at the "Hill of Rath," they appear to have been funereal, while the circumstance of an urn containing human burned bones being placed within the tumulus or beside the body, the skeleton of which has been found perfect in all its parts, and therefore none of it subject to the action of fire, leads one to suppose that the person whose ashes the urn contains was sacrificed to the manes of the individual for whose body the tumulus or stone chamber

* It is said that a thin scale of copper was also found in one of the urns; but we think that the way in which this got there is very questionable, and by no means proves that the people who placed these urns in this ancient burial-place had any acquaintance with the use of metals. A somewhat similar collection of urns, occurring at Loughanmore, in the county of Antrim, has been described by the same gentleman, but the description of the former will here suffice. Why does not some industrious antiquary write a paper on our Irish urns? The materials for it are most abundant.

was originally erected. At all events we may safely assert, that burning the body and collecting the bones into an urn, was one of the earliest rites of the ancient Irish. It is also well established that both birds and dogs were interred, burned and unburned, with these remains, for their bones are constantly found with the human ones.

The Rev. Dr. Walsh has recorded an instance at Kilbride, in the county of Wicklow, where a stone coffin was discovered in a wild and solitary part of the mountain, and just large enough to contain a small urn, which was inverted over two small bones belonging to human fingers and toes, and no other part of the body! We are indebted to R. C. Walker, Esq., who has opened a great number of tombs in this country, for an account of a most interesting examination which he made of some tumuli in the county of Sligo, a celebrated locality for sepulchral remains, particularly those of the Firbolgs. Mr. Walker informs us that one kist or tomb, which contained the remains of a great number of skeletons, some evidently burned, and others exhibiting no trace of fire, occupied the centre of a large cairn. Some idea may be formed of the magnitude of this great kist when it is known that one of the stones which formed the side of it was sixteen feet in length, and about six feet in breadth. In this tomb were found six different human interments, which occupied the eastern and western ends, the centre part being unoccupied. The bones were not contained in urns, but were collected together into small heaps that rested upon the "freestone flag," which invariably formed the bottom or floor of the inner tomb. The large bones, such as the arms, legs, and thighs, covered the half-calcined remains of the smaller ones, and the skull surmounted the little pyramid thus formed. Round the margin of this heap was collected a quantity of the bones of birds, and some of the lower mammalia, together with a number of small shells, principally the land *Helix*; and each of these six interments was kept distinct, and surrounded by small freestone flags. No weapon or ornament of any kind was discovered in this tomb. Here, then, in this very remarkable tumulus of the class denominated "giants' graves," we have remains of nearly every form of interment employed by the aborigines of this country.

A. N. Nugent, Esq., opened a sepulchral mound in the neighbourhood of Portaferry a few years ago. "There was," he writes

to us, "a circle of large stones, containing an area of about a rood. Between each of these stones there was a facing of flat ones, similar to the building of our modern fences. The outer coating was covered with white pebbles averaging the size of a goose-egg, of which there were several cart-loads—although it would be difficult to collect even a small quantity at present along the beach. "After this was taken away we came to a confused heap of rubbish, stones, and clay, and then some large flag-stones on their ends,—the tumulus still preserving a cone-shape. In the centre we came to a chamber about six feet long, formed by eight very large upright stones, with a large flag stone at the bottom, on which lay, in one heap of a foot in thickness, a mixture of black mould and bones." These bones, some of which were kindly forwarded to us, are all human, and consist of portions of the ribs, vertebræ, and the ends of the long bones, together with pieces of the skull and some joints of the fingers of a full-grown person, and also several bones of a very young child ; none of these had been subject to the action of fire; but among the parcel forwarded to us were several fragments of incinerated or calcined bone, also human. Either these latter were portions of the same bodies burned, or they belonged to an individual sacrificed to the manes of the person whose grave this was; and we are inclined to think the latter is the more probable, from the circumstances under which similar remains have been discovered in other localities. This tumulus was evidently of very ancient date, long prior to the authentic historic period, and was, we should say, erected over some person or family of note in their day. There were no urns, weapons, or ornaments discovered in connexion with it; but our informant states that, in the field in which this barrow was opened, there have been, at various times, small stone chambers or kistvaens discovered, similar to those described at page 230; and in one of these a skull of the long, flat, and narrow character, was some time ago dug up. A farmer in the vicinity likewise told Mr. Nugent that, many years ago while ploughing in this same field, he turned up a stone chamber of the same kind, and that it contained a skull with a portion of hair of a deep red colour attached to it.

Mr. Getty, of Belfast, has been very industrious in the collection of ancient Irish remains; and the Belfast museum at present contains several specimens of old Irish heads. This leads

to another locality in which bones of the ancient Irish people are said to have been found. We allude to the Round Towers, particularly to that lately excavated at Drumbo, in the county of Down, beneath which some bones were found. Interest was excited by this discovery, from the supposition that these human remains would offer some clue as to the origin and uses of these monuments, or assist in determining the probable era of their erection. The enchanted palace of the Irish round tower has, however, been opened for our inspection, and therefore all theorizing on the subject is at an end. We were presented at the time of the examination with a very beautiful cast of the skull found within the round tower of Drumbo; and the moment we saw it we felt convinced that, if it was of a contemporaneous age with the structure beneath which it was found, then the Irish round tower was not the ancient building it is usually supposed to be; for, compared with the other Irish heads, that skull is of comparatively modern date. Now, nearly all the round towers are in connexion with ancient burial-places, and that one in particular is so, and one need only dig around and without it to find many similar remains. We hear that the skeleton was found at full length, imbedded in the clay, within the ancient structure. Now, if the round tower was erected as a monument over the person whose skeleton was found within, the body certainly would not have been buried thus in the simple earth, without a vault or stone chamber, such as the enlightened architects who built the tower would be thoroughly competent to construct. Moreover, we do not believe that a skull thus placed loosely in the earth, without any surrounding chamber, would have remained thus perfect for the length of time which even the most modernizing antiquaries assign as the date of the round tower.



Here, however, is a drawing of a Danish head of undoubted authenticity, for which we are much indebted to the Rev. Dr.

Spratt, of this city. We believe it to be that of Donatus, the first Danish Archbishop of Dublin, who died (according to Sir James Ware) in 1074, and was buried in Christ Church; and it also has the peculiar length in its antero-posterior diameter to which we have referred.

At Larne, in the county of Antrim, a skeleton was lately discovered, which, from the iron sword and other weapons in connexion with it, appeared to have been that of a Templar; and similar remains were not long since discovered at Kilmainham. This Templar's skull, found at Larne, although it has an Irish physiognomy, and a Firbolg form of head, cannot be dated back farther than the eleventh or twelfth century.

We have two instances recorded of human remains found in the bogs of Ireland; one of these, the mummy of which is now in the Royal Dublin Society House, was discovered in a bog, nine or ten feet beneath the surface. When first exhumed the body was perfectly fresh, and enclosed in a dress not unlike that in the description given of Gurth in *Ivanhoe*,—consisting of a tunic of cow-hide, apparently tanned, but with some remains of hair still preserved on the side worn next the skin. This dress is joined in the most accurate and beautiful manner, exhibiting an extraordinary perfection in the art of sewing. The hair on the head, which is both long and fine, is of a dark brown colour, and the skull is compressed in a remarkable manner, owing to a portion of the earthy matter having been removed by the acid of the bog. The body of a man was found under precisely similar circumstances by Mr. R. C. Walker, but it is evidently of more recent date, perhaps not older than the time of Elizabeth; for the dress, which is of woollen texture, and still quite perfect, is precisely that represented in Walker's *Irish Bards*.

Of the modern race it is not our province here to speak; those of our readers who have followed us in the description of the ancient races will recognise among the true Irish of our own time distinct traces of the long-headed, dark-haired, black-visaged, swarthy aborigines or Gothic Firbolgs, and also (for they are very numerous) the oval or globular-headed, fair-haired, light-coloured, blue or grey-eyed Celtæ, or Tuatha De Danaan. But the present Irish race is very mixed; even those with genuine Irish names, the O's and Mac's, exhibit the greatest diversity. Finally, we may add that there can now be little doubt that the

same early race, whose heads exhibit the two forms which we have figured at pages 229 and 231, inhabited, long before the date of written history, Ireland and Great Britain, Sweden, Denmark, and the north-west of Europe generally, together with the ancient Etruria, and perhaps the central parts of Germany also; at least one or two specimens of ancient crania which we examined at Halle and Berlin lead to these conclusions. We have had an opportunity of examining some skulls of the Guanches or ancient people of the Canary Archipelago, found by M. Bertilot in Teneriffe, and they presented precisely similar characters. In Denmark and Sweden, however, the order of these remains appears to be reversed, for there the long-headed race is found in connexion with metallic instruments; and this appears to go far to show that the first great wave of population passed from this country towards the north, and that the original people who, in Ireland, knew only the use of stone and bone weapons, by the time they migrated into Denmark, carried with them the knowledge of metals,—gained, perhaps, from their Celtic conquerors.

To the skulls and human remains found in connexion with sepulchral monuments alone can we assign a positive date, and therefore it is that in the foregoing description we have confined our remarks to those found under such circumstances, and have figured them as typical forms. But we sometimes find human remains in connexion with certain antiquities which serve to fix their date, and sometimes upon battle-fields, the date of the actions of which has been recorded in history; and the crania found under these circumstance have been partially preserved, and many of them we have had an opportunity of examining. In that great collection of animal remains and antiquities, found at Dunshaughlin some years ago, one perfect, and fragments of two other human skulls were discovered. They partake of the characters of the long-headed race, and the antiquities found in that collection would lead us to believe that the persons to whom those skulls belonged lived about the tenth century. And in the collection of bones and antiquities found in the vicinity of Navan, which we have described at page 135, and which must have belonged to a much later period, as we know by an examination of the antiquities, a skull which was there dug up evidently partakes of the character of the long-headed race, but it is

of a more globular form than those found in ancient Pagan tumuli, as if intermixture of races had modified the peculiarities of the crania, from the elongated to the true globular or Tuatha De Danaan. And again at the Ford of Kinnafad, we have shown at pp. 38-40, that the skulls and skeletons of both races, as well as the weapons which were probably employed by each, were discovered. The fragments of heads found in the great cairn at Dowth belonged to the long-headed race. Last month (July, 1849), four skeletons were found in the rocky cliffs above Redbay, near Cushendall, county of Antrim. Through the kindness of a friend we possess one of the skulls of these skeletons; it partakes of most of the characters of the long-headed race, but it is somewhat greater in capacity, and approaches the globular form more than those found in the ancient sepulchres of Pagan times. Now what adds particular interest to these human remains is, that a small stone celt or hatchet, and two bronze celts, were found along with them; these weapons enable us to form some conjecture of the *probable* age of the skulls, and also show that the bronze and stone weapons were used at the same time in this country: but that which fixes the date of the interment of these skeletons was the discovery of two small Saxon silver coins of the early part of the ninth century.*

From the foregoing observations it is manifest not only that two separate races, the earliest characterized by very long heads, and who were probably the Firbolgs, or first colonizers, and the other by more globular and capacious skulls, and who, it would appear, were the Tuatha de Danaan, the conquerors of the former, existed in this country prior to the Christian era; but that both races subsequently existed together, and probably amalgamated. Skulls exhibiting both characters may be observed among the present truly Irish inhabitants, but that the more we approach the south and west the more do the former predominate, both in the existing inhabitants, and in the crania found in ancient burial-places.

It would not suit the present work to enter into a more

* Mr. J. Huband Smith, the kind friend who procured us this skull, informs us that one of them is a coin of Berhtulf, engraved by Ruding (see vol. i. p. 120, and vol. iii. plate 7, No. 8), who was King of Mercia, A. D. 839; and the other is a coin of Ceolnoth, who is stated to have been Archbishop of Canterbury, A. D. 830. See Ruding, vol. ii. p. 182, and vol. iii. plate 13, No. 7.

minute and anatomical description of these crania than that contained in the foregoing observations.

The subject of the ethnology or physical history of the early Irish people having been thus opened, we hope it will not be allowed to rest here, but that many investigators in this fertile field of research will appear. It is only from an examination of a great number of skulls the truth can be elicited, or proper inferences drawn; a single skull is of very little value to any person; and we therefore hope to see our national collection at the Royal Irish Academy increased from day to day by those persons who have become possessed of human remains.

To those who may be engaged in opening ancient tumuli, or who may be accidentally present at such examinations, we would offer the following word of advice. First, note accurately the bearings of the mound, grave, tumulus, or kistvaen, which has been accidentally discovered, or may be about to be opened. Find out the name of the townland, as well as the name of the immediate locality in which it is situated. Observe accurately the position of the skeleton, whether lying at length, placed in a sitting or crouching attitude, or whether the bones appear to have been collected together after they were denuded of the flesh, &c.; and procure, if possible, drawings of the position of the bones. These bones are remarkably fragile, and should be handled with great care. Should urns be found in connexion with these remains, either in the sarcophagus itself, or in small stone boxes placed around it, their position should be noted, and their contents carefully examined. In many instances within our own knowledge, these urns have been wantonly destroyed by the people who found them. Their value should, therefore, be explained to the peasantry.

In conclusion, let us add, that if this essay may be the means of showing the value that ought to attach to our ancient human remains, and of saving such as may be subsequently discovered, from either the destruction or the oblivion to which they have heretofore been consigned, one of the chief objects of introducing it here shall have been obtained.*

* The description of the two forms of skulls, and the details of the various ancient modes of burial, were first broached at the Royal Irish Academy, and afterwards (in 1844) given at a lecture at the Irish College of Physicians; see page 41.

CHAPTER X.

THE BATTLE-FIELD OF OLDBRIDGE.—DROGHEDA.

THE BOYNE IN LOUTH.—THE CAMPAIGN OF 1690.—DESCRIPTION OF THE BATTLE-FIELD OF OLDBRIDGE.—POSITION OF THE IRISH ARMY.—THE HILL OF DONORE.—POSITION OF THE ENGLISH ARMY.—THE KING'S GLEN.—PLAN OF THE BATTLE OF THE FIRST OF JULY.—WOUNDING OF KING WILLIAM.—THE BATTLE OF BOSSNAREE.—TURNING OF THE LEFT WING OF THE IRISH ARMY.—THE PASSAGE OF THE BOYNE.—DEATH OF SCHOMBERG.—THE FIGHT UPON DONORE.—THE RETREAT TO DULREK.—WHAT EFFECTS HAVE FOLLOWED.—NEW BALLAD OF THE BOYNE WATER.—DROGHEDA; ITS EARLY HISTORY; ITS ANTIQUITIES; ITS WALLS.—ST. LAURENCE'S AND THE WEST GATE.—ST. MARY'S CHURCH.—THE MAGDALEN STEEPLE.—THE MOUTH OF THE BOYNE.—COLPE.—THE MAIDEN TOWER.

Below Dowth the banks of the river in many places rise high and abrupt from the water's edge, particularly on the left side, and the stream is, generally speaking, deep and sullen; but although the scene presents much beauty, it is not easy of access; so we must again follow the high road to Drogheda, although, in so doing, we miss many a beautiful view, which is presented below the wooded heights of Dowth and Farm,



till we again join the river's bank, at the confines of the county of Louth, near Oldbridge, where the Mattock river enters the Boyne, and a short distance beyond which we first catch a

glimpse of the obelisk and the battle-field of 1690. About a quarter of a mile above the "New Bridge" upon the Mattock rivulet, on the Meath side, stands the foundations of Proudfootstown Castle, but they scarcely deserve a visit. We now enter Louth. Here the road approaches almost to the water's edge, and, following a graceful curve, which the stream makes at this place, continues so for about half a mile, till we pass the Boyne obelisk, which marks the site of the celebrated battle of the 1st July. The first rapid upon the Boyne occurs here. It is now the site of a salmon weir, and the tide comes up as high as this. As we pass into this defile the scene becomes truly picturesque. Upon the left, the rocky banks of Townley Hall demesne, clothed with the most splendid foliage; upon the right, the deep meadows and green inches are fringed by the woods of Oldbridge; and in the centre, upon a massive rock, which juts over the water, rises the obelisk raised to commemorate the passage of the Boyne, when Stuart and Nassau contended for the crown of these realms. Grander battle-fields,—more extensive plains, as that of Waterloo,—or with the mountains looking upon the sea, as at Marathon,—may easily be found; but for inland sylvan beauty, the diversity of hill and dale, with wooded banks, and a shining river, this scene of action may well challenge competition.

We suppose our readers are already acquainted with the political events which led to the "Battle of the Boyne," and of the details of the campaign, from the time of the landing of King William III. to the end of the month of June, 1690; and as we have neither space nor desire to discuss the various political circumstances which led to this engagement, nor at all to enter into the general history of the country prior to this event, we shall chiefly confine ourselves to a topographical description of the battle-field, not only because it is more immediately connected with the object of this work, but on account of the discrepancies which appear in the writings of various authors, from their want of knowledge of this subject. And as we approach the spot on which, for the last time in Great Britain, the crown of these realms was contested by kings in person, it is our duty to present our readers with a picture of the scene, and to point out to those who may visit the place, the most memorable and best authenticated localities.

After the Boyne passes the great monument of New Grange,

it alters its course, turning towards the north, and, with various minor windings, forms a deep curve between that point and Drogheda, which is distant about five miles in a direct bird line. Having reached Townley Hall, it again turns to the south-east, towards Drogheda, and thus completes the curve or elbow to which we alluded. Within this bend of the river, upon the right or southern bank, the ground rises by a succession of smooth and gentle slopes to the hill of Donore, a conspicuous elevation, crowned by a ruined church, and surrounded by a few straggling ash trees. The Boyne winds round in front of this hill towards the north, from the summit of which it is distant not quite an English mile. To the right, or east, the hill fines off towards Drogheda, about a mile and a half distant. Its western side abuts upon, and is completely protected by the high precipitous banks of the Boyne, now covered by the plantations of the demesne of Farm. Immediately behind it, towards the south, the way lies open to Dublin, along the sea-board line; and toward the south-west, situated about three miles from Donore, is Duleek. To the extreme north-west lies Slane, between which and Drogheda, a distance of about nine miles following the windings of the river, there was not at the time of the battle, nor is there yet, a bridge. Several fords, however, occur between those two points; descending the stream, some weirs, about half a mile below Slane, point out the site of ancient fords, but the principal shallow is at Rossnaree, immediately below the monuments of Knowth and New Grange, about three miles lower down than Slane, and something more than that distance from the hill of Donore. At the weir, where the tide ends, above the entrance of the Mattock river, the Boyne is fordable with difficulty, and the right bank rises rather precipitously immediately beyond its margin. The river then turns towards the south-west, and just below the site now occupied by the obelisk, it enlarges considerably, and several islands occur in it; the most extensive of these are Grove Island and Yellow Island, the former containing more than five acres, and the latter about sixteen. The shallowest ford occurs here; an old road leads down to it, and it is passable for a carriage and horses, at low water, in summer-time. Immediately opposite this ford, upon the Meath or southern side, stood, in 1690, the little village of Oldbridge. The locality which we

have now described may, properly speaking, be called the battle-field of the 1st of July, a considerable portion of which, particularly opposite the fords, is obscured by the plantations of the adjoining demesne.

King James's army, having fallen back towards Leinster, passed through Drogheda, and occupied the northern face of the hill of Donore, and the sloping ground between that elevation and the fords near Oldbridge, within the sweep of the river already alluded to. The Irish cannon were planted upon two elevations commanding the fords, one a little to the south of Oldbridge village, which was here intersected by narrow lanes; the other nearly opposite the Yellow Island, on some projecting hillocks in advance of the right of the Irish lines; the latter place is now marked by a fir plantation. According to Story's map, a third battery was placed opposite the ford, near the Mattock river. Some temporary breast-works were also thrown up in front of the village.*

James and his staff took up a position on the summit of the elevation, and His Majesty, it is said, slept in the little church here the night before the battle. Of this ruin nothing now remains but portions of the walls and the east window, beneath which, and within the enclosure of the church, we find the handsome altar tomb of one of the Synnots. It is probable that this church was a ruin in 1690. The view from this point commands the entire scene upon the north and east, including Drogheda and the mouth of the Boyne. It is a lone, deserted spot, seldom visited by the tourist, though memorable as the place at which the sceptre passed for ever from the last monarch of the royal line of Stuart.

Upon the left, or Louth bank of the river, a bluff hill, sloping off upon its northern face, continues on from Townley Hall towards Drogheda, intersected here and there by deep, narrow defiles, which run down toward the water's edge; behind it is the rising ground of Tullyallen. At the end of Townley Hall demesne, a deep, narrow gorge, now generally known as King William's Glen, opens out upon the river, from

* From an old French bird's-eye view of the Battle-field, published shortly after the action, as well as the tapestry in the Irish House of Lords, it would appear that there was, at the time of the action, a small church in the village of Oldbridge.

which it is not more than three hundred paces distant, and, owing to the circumstance of a projecting brow of the hill through which it cuts, as well as its winding direction, the view up this valley is completely obscured, so that a whole army, of many thousand men, within it, might be screened from cannon-shot, and hid from observation, even from the eminence opposite. On the high bank above, and to the east of this valley, was placed King William's chief battery.

William and his army marched in two columns from Ardee, upon the 30th of June. Having arrived within view of Drogheda, the position of the Irish encampment, stretching along the slopes of Donore, was at once recognised. A person standing upon any of the elevations in that neighbourhood, could with ease recognise every tent in the Irish camp. The English army then turned slightly westward along the northern slope of the ridge we have described, and by which it was in a great measure concealed from the Irish, and took up its position nearly parallel with the Boyne; its right descending into the hollow of the King's Glen, and its left resting in another narrow ravine, at the eastern extremity of the hill, and very similar to the former. It had thus the advantage of being able to reach the Boyne in a few minutes through either of those two deep, narrow ravines; and William not only had this advantage of position, but, while his own army was completely concealed from view, every tent in that of his opponent was plainly mapped before him, and many of them within point-blank range of his cannon. The English being encamped, and the batteries erected, the firing commenced upon both sides, and was continued during the greater portion of the day. The old ballad says, and perhaps truly:

“ King James he pitched his tents between
The lines for to retire,
But King William threw his bomb-balls in,
And set them all on fire.”

It is related, that the Prince of Orange rode with his staff along the heights which run parallel with the river. George Story, an eye-witness of the scene, relates the following incident, which we insert, principally because we have been enabled, from a very careful examination of the locality, to decide upon the exact spot where it occurred.

“His majesty rid on to the pass at Oldbridge, and stood upon the side of the bank, within musquet-shot of the ford, there to make his observations on the enemies’ camp and posture; there stood a small party of the enemies’ horse, in a little island within the river; and on the other bank, there were several hedges, and little Irish houses almost close to the river, there was one house likewise of stone, that had a court, and some little works about it; this, the Irish had filled with souldiers, and all the hedges and little houses we saw, were lined and filled with musqueteers; there were also several brest-works cast up to the right, just at the ford. However, this was the place through which his majesty resolved to force his way; and, therefore, he and his great officers spent some time in contriving the methods of passing, and the places where to plant our batteries. After some time, his majesty rid about 200 yards further up the river, nigh the west of all the enemies’ camp; and whilst his army was marching in, he alighted, and sate him down upon a rising ground, where he refreshed himself; whilst his majesty sate there we observed five gentlemen of the Irish army ride softly along the other side, and make their remarks upon our men as they marched in; those, I heard afterwards, were the Duke of Berwick, my Lord Tyrconel, Sarcefield, Parker, and some, say Lauzun. Captain Pownel, of Colonel Levison’s regiment, was sent with a party of horse and dragoons, towards the bridg of Slane; and whilst his majesty sate on the grass (being about an hour) there came some of the Irish, with long guns, and shot at our dragoons, who went down to the river to drink, and some of ours went down to return the favour, then a party of about forty horse advanced very slowly, and stood upon a plowd field, over against us, for near half an hour, and so retired to their camp; this small party, as I have heard from their own officers since, brought two field-pieces amongst them, dropping them by an hedg on the plowd land undiscovered; they did not offer to fire them, till his majesty was mounted; and then, he and the rest, riding softly the same way back, their gunner fires a piece, which killed us two horses and a man, about 100 yards above where the king was; but immediately comes a second, which had been almost a fatal one, for it grazed upon the bank of the river, and in the rising, slanted upon the king’s

right shoulder, took out a piece of his coat, and tore the skin and flesh, and afterwards broke the head of a gentleman's pistol."

William took, it seems, but little notice of the affair, but rode quietly back into the glen; the enemy were, however, so far deceived, that they raised a great shout, and an express was immediately sent off to the Continent, and bonfires, it is said, actually lighted in Paris to celebrate the fall of Nassau.

The place where this accident occurred was on the side of a small hillock, by the water's edge, a little below the glen, and from which the stones have been taken to build the obelisk erected just beside it.

In one of the editions of the *Memoirs of the Duke of Berwick* there is related a curious account of what would appear to be the same story, of which the following is an outline. The day before the action a considerable number of the officers of the Prince of Orange were standing together in a group. As it appeared probable that the Prince of Orange was one of the number the young Duke of Berwick exclaimed: "Behold a splendid opportunity for putting an end to this war! We must attack that troop and destroy the Prince of Orange." "And who will dare to do it?" observed some one. "I, myself," said the Duke; and immediately, followed by a band of officers drawn on by his example, he attacked and defeated this very troop where he hoped to find the Prince. He looked about in search of him in defiance of every danger, but the Prince was not there."* This account of a piece of heroism, however, ceases to interest us when we remember the fact that at the time alluded to the Boyne at full tide was rolling between the belligerents! Of such tales, however, is history, and the history of battles in particular, often composed.

Thus ended the 30th of June, and thus stood the hostile armies upon the eve of the engagement. We have written the foregoing description of the battle-field from a careful examination of the scene, and the perusal of the most trustworthy documents within our reach. The exact position of each general's division in either army has not been ascertained with certainty, neither has any veritable military plan of the bat-


* *Mémoires du Maréchal de Berwick, Duc et Pair de France, et Généralissime des Armées de Sa Majesté. Tome Premier. A Londres, aux Depens de la Campagne, 1758, pp. 64, 65.*


tle ever appeared. The accompanying map we have had engraved from a plan of the battle, made about sixty years ago, by a Major Brown, for the Right Hon. John Foster, Speaker of the Irish House of Commons.* We present it to our readers and the tourists to the Boyne because it conveys to our mind a much better idea of the scene than either of the two older, ill-constructed plans of Story or Richardson.


Heretofore, the descriptions of the battle of the Boyne have been almost all one-sided. The authorities from which the historians drew were nearly all Williamite; but within the last few years the gleaners in this department of Irish history have had access to documents written by officers in the Irish army in every way worthy of credit, and which must now induce the calm searcher after truth to very much modify some, and altogether reject other statements put forward by the former, and which have been generally received as facts. To give these latter their fair share of merit, and to weigh and discuss the adverse statements of both parties, would not suit the intention of the present work, and would require a more critical examination of the subject than our space would warrant.†

* A copy of this document was presented by Viscount Ferrard to the Engineer's Library, Dublin, in 1829. It is now in the Ordnance Office. For the use of it we are much indebted to our friend Captain Larcom, R. E., one of the Commissioners of the Board of Works.

† We feel it the less necessary to enter into a critical examination of the history of the battle of the Boyne in this place, because there is a work now in process of publication by the Irish Archæological Society,—“*Macariz Excidium*, or the Destruction of Cyprus,” edited by John C. O’Callaghan, Esq., Author of “The Green Book,” a gentleman of literary acquirements and critical research. In the mean time we may refer our readers to the various Lives of King William which have appeared: to a continuation of the impartial History of the Wars of Ireland, &c., London, 1793, written by “George Story, chaplain to the regiment formerly Sir Thomas Gour’s, now the Earl of Drogheda’s,” who appears to have been himself at the battle of the Boyne, and whose statements, until they are contradicted by irreproachable evidence, must, as far as mere matters of fact, be received as historic evidence. A Captain John Richardson, who was an “eye-witness of the scene,” published a plan of the battle, to which is appended a short account of the engagement. The second edition of the Green Book, by Mr. O’Callaghan, should be consulted by those wishing to make a minute inquiry into the history of the battle. The Memoirs of the Duke of Berwick and the Memoirs of King James II. should also be examined, and their statements carefully compared with writers on the other side of the ques-







We should like, 'tis true, to fight this battle over again, and record the gallant deeds of the O'Neals and Schombergs,—the Caillemottes and Sarsfields,—of Berwick, Sidney, Ginkle, Geraldine, Hamilton, and others who have left material for many a tribute to their fame. But this, at present, is denied us; perhaps some other day we'll try our hand at this "grievous battle," so bravely fought by a comparatively young, but experienced general,—gallant in the field and wise in council, with a highly disciplined army, a part of which had been trained in many a hard contested battle,—against a weak and vacillating prince, advanced in years, and borne down by misfortunes, neither wise in council nor gallant in action, standing in the reere of, but not commanding an army, which, however great its devotion, was totally unable to cope with its opponent.

The army of King William amounted, according to the most moderate calculation, to 36,000 men; all well-disciplined soldiers; numbers of them tried veterans, whose prowess had been tested and their courage schooled in many a well-fought field in Europe; hardy warriors, well-appointed, and composed of the greatest number of nations that ever fought for or against the crown of England before or since—Danes, Dutch, and Flemings, Swiss, French Huguenots, English, Anglo-Irish, and Germans,—led by some of the most esteemed officers of the day, the Schombergs, Douglas, Sidney, and La Mellonere, and commanded by one of the greatest generals of the age, personally brave, energetic, and well-skilled in war. To this was opposed an army scarcely three and twenty thousand strong, a large portion of which, the French excepted, was composed of raw levies; undisciplined, and but ill supplied with arms; under generals no doubt brave and skilful, but whose interests

tion. In 1791 there was printed at Amsterdam a little work styled, "*Histoire de la Revolution d'Irlande, arrivé sous Guillaume III.*," which contains a description of the battle of the Boyne, some extracts from which we have given, because it has not as yet appeared in English, at least that we are aware of, while that by Story has been the principal ground-work for all modern writers. We are indebted for the use of this work to our friend Dr. Cane of Kilkenny. A portion of the *Macaria Excidium*, edited by T. Crofton Croker, Esq., has been printed by the Camden Society. In the Royal Hospital there is a large oil painting of the Battle of the Boyne, and the scene is represented on the tapestry still remaining in the House of Lords (in the Bank of Ireland); there also exists an old mezzotinto engraving of the battle, from an original painting by Wyke, in the possession of the Earl of Leicester.

were so constantly clashing that it was with great difficulty they could even be brought to act in unison; and moreover commanded by a Prince whose weakness, imbecility, and bigotry, had already lost him a crown, who was totally unskilled in war, and whose heart was not in the country nor the cause of the men who fought for him. With all their faults the Stuarts elicited more loyalty than the world will ever witness again. We will not say that James II. was a coward,—he had previously shown his bravery upon sea,—but certainly he was no general. His defeat here was, however, inevitable. Under the circumstances he should not have delayed nor fought at the Boyne, where he had got into a most unlucky position, the apex of a triangle, one side of which was formed by the sea; and when William hemmed him round, defeating him at every point, not only by the superior discipline of his troops, which, after all, is courage, but by force of numbers and generalship, then retreat—flight, was the inevitable, the last resource. Looking back at this distance of time, it would appear to have been a safer plan for James to have retreated with his small army, and have garrisoned the principal fortified towns, and by laying waste the country, and destroying, as was intended, the English fleet in the Channel, thus cut off William's supplies, while a guerilla warfare would have greatly harassed and considerably diminished his forces. James cared nothing for Ireland nor the Irish, except so far as they could be made use of to secure him the crown of England; he also hoped that a counter-revolution would have been got up in his favour in England, and that the King of France would have lent him assistance. This, however, is not the place to discuss these subjects further.

There is one point in the battle of the Boyne on which sufficient stress has not been laid, although it would appear to have a greater influence on the issue of the fight than historians are aware. The right wing of the Irish army was completely protected by Drogheda, the Boyne, and the sea; its left towards Slane was unprotected: this could not escape the notice of a skilful opposing general, neither was it unknown to some of the advisers of King James, although he himself does not appear to have paid sufficient attention to it. At break of day upon the morning of Tuesday, the 1st of July, William despatched 10,000 men under the younger Schomberg, General Douglas, and Lord Portland, to cross the river at the fords,

near Slane, of the existence and passability of which he appears to have been well informed. Proceeding behind the hill, now included in the demesne of Townley Hall, and crossing the Mattock river at Monk-Newtown, they were concealed from the Irish until they appeared on the elevated banks near Knowth, above the ford of Rossnaree, where it would appear the cavalry crossed with scarcely any opposition, except from the regiment of Sir Neal O'Neale, who himself was killed in the skirmish. The foot passed round by the bridge of Slane, two miles farther off, but joined the English cavalry before a sufficient force could have been despatched by James to oppose them. Here then was an army, nearly half the size of that of King James, advancing upon the left wing of the latter, and then it was (for William was informed, by express, of Douglas having made good his position) that the passage of the Boyne at Oldbridge was commenced at half-past ten o'clock, A. M., while the left wing of the Irish army was already engaged two miles off with the division under Douglas and Count Schomberg.

We have already remarked upon the admirable position of the English army, protected by the immense battery immediately opposite the ford, and screened by the natural lie of the ground. The tide being out, the passage of the river was attempted in four different places. The Blue Dutch guards, the Irish Enniskilleners, and the French Huguenots, led by the gallant old Schomberg, passed quickly out of the little glen opposite the principal ford, and dashing into the water both there and over the upper end of Grove Island, a little lower down, formed upon the opposite side, and carried the village and rude out-works at Oldbridge; not, however, without considerable opposition, some of the Irish soldiers rushing into the water to meet them. It was here Schomberg, then Duke of Leinster, was killed.* The principal Irish battery, very much inferior in numbre and calibre of guns to the English, placed upon a slight rising ground, nearly opposite the lower end of the Yellow Island, does not appear to have done

* Schomberg's body was immediately carried back across the river, to the English camp. His skull is still shown in the cathedral of St. Patrick's, where Dean Swift caused a monument to be erected to him. The family vault of the Schombergs is in the cathedral of Mayence. The heart of James II. was embalmed, and is now in a shrine in a small chapel on one side of Champs Elysees in Paris.

much execution. The third crossing was made by the Danes and Germans, at a shallow between the two principal islands, where the water must have been up to their arm-pits, while the left wing, entirely composed of cavalry, consisting chiefly of Danes and Dutch, passed or swam across opposite the eastern valley which intersects the hill of Tullyallen, and effected a landing, apparently with little opposition, at a very deep and dangerous part of the river, nearly opposite one of the Irish batteries, and where the margin of the stream is wet and swampy. Here it was, however, that William himself, with his arm in a sling from the effects of his wound, plunged into the stream, with Colonel Woolstey, and passed with great difficulty, "for his horse was bogged on the other side, and he was forced to alight, till a gentleman helped him to get his horse out."

Thus, then, there were six and twenty thousand men, with a large battery, arrayed against fifteen or sixteen thousand, for we must subtract those already engaged, under Lauzun, towards Slane, nearly three miles off. The natural consequences followed: the Irish centre and right wing fell back upon Donore, and finally, towards the close of the day, retreated in tolerable order to Duleek, towards which place the left wing, already beaten above Rossnaree, had retired. Here, with the Nanny Water between them, both parties halted for the night, with the exception of King James, who fled to Dublin, which he reached about ten o'clock, so that he must have left the battlefield between six and seven o'clock in the evening.

The numbers killed at the battle of the Boyne were not considerable. On the Irish side the number killed was upwards of a thousand, and upon the English above four hundred. The orange and green have long been party words in Ireland;—are our readers aware of the fact, that while the Irish troops wore pieces of white paper in their caps, every English soldier was decorated with a branch of *green*?

Thus ended the battle of the 1st of July, 1690, the cause of so much subsequent party feud and so many heart-burnings in this country. To the one party it gave victory; liberty, civil and religious; broad lands, power, and dominant sway: while the other suffered not only present defeat, but subsequent confiscation, penal laws, exile. Since then the fierce advocate of one party has cursed, "bell, book, and candle-light," the Williamite and the Orangeman; and the defender

of the other has, upon bare, bended knees, pronounced a malediction (which, for sentiment and strength of language, is unsurpassed in the cursings of ancient or modern times) upon all who would not drink the "Battle of the Boyne," and the pious memory of the man who first robbed Ireland of her manufactures, and signed the warrant for the massacre of Glencoe! Times, however, are changing, let us hope for the better; mutual asperities are softening down; prejudices of birth, of religion, so-called, of education and position, are happily being removed; men can now calmly discuss those subjects without passion or without offence. The memory of "The Boyne Water" must be dear to every Irish Protestant—every lover of Protestant liberty; let him drink it, if so minded, but couple not with it the idol of Collegegreen.

Had the Scotch Royalists and Lowlanders been allowed to celebrate the anniversary of the victory of Culloden, in processions, with flags flying, drums beating, fifes playing, "in the teeth" of the Highlanders, whose forefathers bled for Charles Edward, Scotland would not be the happy, prosperous country it is to-day.

As the little work already alluded to in the note at p. 248, "*Histoire De la Revolution d'Irlande, arrivée sous Guillaume III.*," is not generally known, we extract the following notice of some facts connected with the Battle of the Boyne from it. It is evidently written in support of the Williamite side of the question, but it seems tolerably correct.

King William, it says, advanced at break of day towards Drogheda and the River Boyne, along which King James's army was encamped, in order to prevent the English crossing the river. The infantry and artillery did not arrive until very late, so that nothing could be done by King William that day, except to reconnoitre the enemy's position, and to try and find out the fords by which a passage could be effected, for haste was now very necessary. This work then gives an account of the wounding of King William the day before the battle by a six-pound shot, but it adds little to the account of that transaction already related: "As soon as the king's wound was dressed, he again took horse, and acted for four hours more before retiring to his tent, and resolved to cross the river with

his army the next day. On the evening of the same day on which His Majesty was wounded, he ordered Count Menard de Schomberg, with the cavalry of the right wing, two regiments of dragoons of the left wing, the infantry brigade of Trelawney, and five small field-pieces, to go next morning to a ford known to be about three miles higher up than the camp, to try and pass it, and to take the enemy in flank, or compel them to retire. The Count Schomberg having passed the night in giving orders and disposing of the army for the passage, advanced early in the morning to this ford, and found on the other side of it eight squadrons of the enemy drawn up to oppose his passage. He entered the river with his troops and crossed to the other side, and attacking the enemy roughly, routed them and disposed his troops in battle array, intending to march against the enemy at the first order of the King, who was immediately informed of his position, in order that he should in other places attack the army of King James, lest all the enemy should fall on him (Schomberg). The King then sent word to the Count that he was going to cross over to the other side with the rest of his army."

The account of the passage at Oldbridge is nearly the same as that given by Story. Regarding the death of Duke Schomberg, he writes: "This brave general had crossed one of the first, being only preceded by the regiment of La Mellonniere, which had roughly repulsed the enemy. The Duke had crossed over to a village very near the river in order to pursue them. Unfortunately Tyrconnel's guards, taken by a desperate fury, charged this regiment with such impetuosity that they brake through it, and tried to prevent the crossing of those who were still in the water, but the greater part of them having been cut down, and the few remaining being unable to execute their purpose, they turned towards the village, where having met General Schomberg, they gave him two sabre cuts in the head, and, as many reported, a pistol shot. Nevertheless it is certain, as it is known to all those who belong to La Mellonniere's regiment, that when it was evident that Tyrconnel's guards were running towards that village, the officers commanded the fire to be directed that way, and that on all sides the words were heard, 'kill, kill'" [*tue, tue.*] So that it is probable some shots might have been unwittingly directed towards

the Duke of Schomberg, who was killed by a ball which penetrated his throat, and died soon after without being able to utter a word.

In years gone by the Corporation of Drogheda paid an anniversary visit to the obelisk erected to commemorate the first of July,* when they used to drink "the glorious, pious, and immortal memory" in the waters of the Boyne, and sing—

"July the first, in Oldbridge town,
There was" * * * *

No—we'll not finish, but present our readers with the following graphic ballad, which has been forwarded to us by some unknown correspondent, to whom we here offer our best thanks. As it is, on the whole, for a Williamite ballad, honest, spirited, and historically true, we insert it instead of the old party song.

THE BOYNE WATER.

THE OLD BALLAD RETOUCHEE.

'Twas bright July's first morning clear,
Of unforgotten glory,
That made this stream, through ages dear,
Renown'd in song and story.
Yet, not her charms on history's page—
For Nature's own I sought her;
And took my pleasant pilgrimage,
To see the sweet Boyne water.

Here, musing on these peaceful banks,
The mind looks back in wonder;
And visions rise of hostile ranks,
Impatient, kept asunder:
From every land a warrior band—
For Europe owns the quarrel—
His hand shall clench no barren branch,
That snatches this day's laurel.

All-conquering William—great Nassau!
Her crown a realm decreed him;
And here he vindicates her law,
And champions here her freedom.

* There is a long inscription on the base of the obelisk, descriptive of the passage of the Boyne, and the death of Schomberg, which took place immediately opposite, on the other side of the river.

And ne'er let valour lose its meed—
 A foe right nobly banded,
 Though changeless love for king and creed
 With treason's stain be branded.

Ah, wherefore cannot kings be great,
 And rule with man approving?
 Or why should creeds enkindle hate,
 And all their precepts, loving?
 Here, on a cast, land, life, and fame,
 Faith, freedom,—all abide it:
 A glorious stake!—play out the game,
 Let war's red die decide it!

Now strike the tents—the rolling drums,
 Their loud defiance beating,
 Right for the ford brave Schomberg comes,
 And Sarsfield gives him greeting.
 Grenade and musket—hut and hedge
 In flame unintermitting;
 I' the very sedge, by the water's edge,
 The angry fuse is spitting.

The banks are steep, the stream is deep,
 The cannon deadly knelling;
 On man and horse, o'er many a corse,
 Th' impeded tide is swelling;
 Yet firm, as 'twere some pageant brave,
 To their trumpets' notes advancing;
 And plumes and pennons proudly wave,
 And their eager swords are glancing.

With arms held high, and powder dry,
 Fast on the bank they're forming:—
 Shame on those Kerne! the steeps they fly,
 Should baffle England's storming.
 But stand together—firmly stand!
 Down the defile, and crushing
 Like loosen'd rocks, to the crowded strand,
 Come headlong squadrons rushing.

Gallantly done, bold Hamilton!
 The scared Dane flies before him;
 What can the Huguenot's pikeless gun
 'Gainst the sabres flashing o'er him?
 Their leader down—down in his blood—
 And William at a distance
 Unhors'd, but toiling through the flood
 To back their brave resistance.

And back they go, the unsated foe,
Still threatening, though retreating.
Away! the Walloon broadsword's blow
Will never need repeating.
And away together, hilt to hilt,
Through the frightened hamlet going;
The lavish blood, like water spilt,
In its narrow street-way flowing.

The heights are carried: far and wide
Are battle-lines extended;
Morass and mound—on every side,
And at every point defended;
A moment well might William halt,
In front a force so shielded;
But prompt th' impetuous assault,
And post on post is yielded.

But still the rattle and the roar,
And flight, and hot pursuing;
And Berwick rallies on Donore,
The conflict fierce renewing.
No toil too great that wins renown:
The fight seems still beginning;
Proud valour's meed is fortune's crown,
And that crown is William's winning.

But where is James? What? urged to fly
Ere quailed his brave defenders!
Their dead in Oldbridge crowded lie,
But not a sword surrenders:
Again they've found the 'vantage ground;
Their zeal is still untiring;
As slowly William hems them round
In narrowing ring still firing.

O'Neill's upon the English front
With whirlwind fury wheeling;
And, flank or front, where'er the brunt,
Their stoutest columns reeling:
Up, Brandenburg! the bravest yield,
The hoof they're trodden under:
On, Inniskillings! and the field
Shakes to their tramp of thunder!

And through and through the stubborn spears
Such awful gaps they're cleaving—
Though Hamilton, still charging, cheers,
The field's beyond retrieving.

Oh, Hamilton ! a hero now
 O'er prostrate foemen riding :
 A moment more, and where art thou ?
 A foe thy rein is guiding.

Thy routed comrades crowd the pass ;
 The weak impede the stronger ;
 And terror strikes the yielding mass,
 And the brave are bold no longer.
 'Tis done : that beacon of the fight—
 That hope—the crown redeeming !
 In heaven's sight, in victory's light,
 The English Banner's gleaming !

Now, Drogheda, undo thy gate—
 Saint Mary's bells are ringing ;
 The Mill-Mount captives, snatch'd from fate,
 Their grateful hymns are singing :
 From dale and down, from field and fell,
 The sulphurous clouds are clearing ;
 The Boyne, with full but gentle swell,
 In beauty re-appearing.

But search the field, what friends are lost
 May claim our brief lamenting :
 No victory wanting victory's cost
 Its scenic show presenting.
 Schomberg, the silver-hair'd, is down—
 Caillemotte no trump awaketh—
 And Walker, with his mural crown,
 His last, deep slumber taketh !

Well—honour'd be the graves that close
 O'er every bold and true heart !
 And sorrows sanctified repose
 Thy dust, discrown'd Stuart !
 O'er scenes like these our hearts may ache,
 When calmly we review them—
 Yet each awake its part to take,
 If time should e'er renew them.

Here from my hand as from a cup
 I pour this pure libation ;
 And ere I drink, I offer up
 One fervent aspiration—
 Let man with man—let kin with kin
 Contend through fields of slaughter—
 Whoever fights, may FREEDOM win !
 As then at the Boyne water.

Leaving the field of Oldbridge, and passing down the left bank of the river, we now approach the last remaining point of interest upon the Boyne, the ancient city of Drogheda; if, indeed, our readers can feel much interest in one of the dirtiest and most ill-ventilated towns in Ireland; and yet, though we thus express ourselves, Drogheda possesses many objects that peculiarly attract attention. It is pleasingly as well as most advantageously situated; abounds in ruins, and has been intimately associated with the history of this country for many centuries. Our excellent friend, John D'Alton, has lately written a History of Drogheda and its Environs, and to that work we must specially refer those among our readers who seek further information upon the subject than the limits of a guide-book can afford.

The early Irish name of this place, to which we alluded at page 202, was *Drochat-Atha* (the Bridge of the Ford); and the grave of the wife of Gobhan, the smith, one of those great sepulchral mounds which were rifled by the Danes in the ninth century, is the Mill-Mount on which the fortress of Drogheda now stands, on the right or southern bank of the river. In after times the name was anglicised Tredagh.

We already remarked upon the landing of St. Patrick in 432, at Inver Colpe, at the Boyne's mouth, upon the southern side of the river. From that time to 1641, when it was besieged by Oliver Cromwell, we could trace its annals from year to year, almost without a break.

Drogheda was a strongly fortified city, and considerable portions of its walls, with two of its gates, still remain. St. Laurence's Gate, upon the northern side of the river, here shown, is one of the finest specimens of its kind in Ireland. "The walls of Drogheda," writes Mr. D'Alton, "extended in their circumference, including the breadth of the river, somewhat more than a mile and a half,



and enclose an area of about sixty-four acres of the old Irish measure, the general height being from twenty to twenty-two feet, and their thickness from four to six, diminishing toward the summit, so as to allow a space of about two feet, with embrasures for the soldiery to act from. In latter times, probably after the invention of gunpowder, this space was augmented by an addition of three or four feet, supported by columns of stone and elliptic arches, on and through which a passage led round the town, with doorways through the gates, castles, and turrets. The banks of the river were also fortified by walls and turrets, projecting into the water, as appears by a painting of Drogheda in the hall of Beaulieu House, taken in the reign of Charles II.* Upon the Meath or southern side, the West Gate forms a most pleasing and picturesque ruin. It appears to have been one of the flanking towers in the original town wall, and in one of the old maps of this place it is called the Butter Gate. The groove for the portcullis is still quite perfect. There were also in ancient times several castles here, and the mound from which Cromwell battered the town is still shown upon the south-eastern side of the river, behind the present poor-house. Several Parliaments were held in this town; the most memorable of these was that in which the bill of Sir Edward Poyning, since called "Poyning's Law," was passed, by which the Irish Parliament was made dependent on that of England.



* See a History of Drogheda with its Environs, and a Memoir of the Dublin and Drogheda Railway. By John D'Alton, Esq., Barrister at Law. 1844. Vol. i. pp. 88, 89. To which work we must refer our readers for a more detailed description of Drogheda. In the Dublin Penny Journals there are also several accounts of this ancient city and its antiquities. See also Wright's Louthiana.

This town contained, according to the last Census, 17,300 inhabitants. In its sunken position within the last defile of the valley of the Boyne, with its narrow, tortuous streets, many of which are ascended by steps, and the number of tall spires and ancient ruins which rise out of the jumble of houses, it bears a resemblance to many continental towns. It is a place of considerable trade; and in the river, below the narrow bridge, the last upon the Boyne, and the only one in Drogheda, may often be seen as many steamers as we find in the Liffey. Up to a very recent period several wooden or bird-cage houses, like those in Chester and some of the old English towns, existed in Drogheda. In one of these it is said Sir Arthur Aston, Governor of this town at the time of Cromwell's siege, resided, and in this house tradition says King James slept the night he arrived in Drogheda, before he encamped at Donore.

From time immemorial Drogheda has been noted for its ecclesiastical establishments, and the ruins of several still remain; but they are, generally speaking, scarcely approachable, owing to the quantity of filth by which they are surrounded. The most remarkable of these ecclesiastical ruins is that shown in the accompanying illustration, the Abbey or Church of St. Mary, which spans a dirty lane, now principally used as a stable-yard, behind the upper end of West-street.

One of the most conspicuous objects in Drogheda is the Magdalen Steeple, figured on the next page, the only remnant of the church of the Dominican friary which once stood here. It occupies an elevated position upon the northern side of the city, near Sunday's Gate, and is immedi-



ately adjoining a series of arches pointed out as the remains of the town wall. It is now surrounded by the most miserable hovels, inhabited by the most wretched portion of the population, and not only is the adjoining locality a disgrace to the town, but the very site itself stands more in need of the efforts of a Sanitary Commission than any other place that we know of in the British dominions.

As soon as the Corporation of Drogheda cleanse their city, we hope to conduct the Boyne tourists round some of its other memorable ruins.

From Drogheda the tourist may visit Duleek, upon the Meath, and Termonfecken, Monasterboice, and Mellifont, upon the Louth side of the river. No visiter to this part of Ireland who has three hours to spare after examining the battle-field of Oldbridge, but should visit these two latter celebrated localities, which abound in ruins of the highest interest, consisting of ancient churches, some of the most magnificent sculptured crosses in Ireland, a round tower, and an ancient octagon church, or baptistry, similar to the Temple Church in London.*



Our pilgrimage is now nearly at an end. There is little further worthy of remark. Below Drogheda the Boyne spreads out into a broad estuary, which is shortly to be crossed by a bridge connecting the Dublin and Belfast Railways. As we sail down the river, several pleasingly situated villas range along the northern bank, and the fine old mansion-house of Beaulieu or Bewley particularly attracts attention. Upon the right or

* By passing up King William's Glen, opposite the Obelisk at Oldbridge, the tourist can with great ease first visit Mellifont, then proceed to Monasterboice, and after that return to Drogheda.

southern bank is Mornington, one of the earliest seats of the Wellesleys, and Colpe, the site of an ancient church, built, it is said, over the spot where the brother of Milesius was buried. Upon this southern shore of the Boyne's mouth stands an ancient square tower about eighty feet high, which has always been known by the name of the Maiden Tower; and at a little



distance from it inland is placed a small pillar of solid masonry, called The Finger. They are evidently landmarks, erected before light-houses were employed in this country. The tower, which is at least three hundred years old, may also have been originally used as a look-out station, for which purpose it is admirably adapted. There is a winding staircase in the centre, and the top, which is flagged, is reached by a small aperture, which could easily be covered with a large stone, so that it might, in case of siege, be rendered inaccessible from within. There are many "old stories" related about this tower,—tales of love, of maiden faith and knightly honour, and, in latter days, of mystery also. Tradition says it was erected by a fair lady, to watch the return of her betrothed from a far-distant country, whither he was obliged to journey upon the eve of their nuptials. It was agreed beforehand that, if the lover returned successful, he should hoist a milk-white banner; but if the contrary, a red flag should float from his mast-head. The preconcerted signal was forgotten, and the knight, seeing the tower,—which his true love had erected during his absence to

watch his return,—and mistaking it for the watch-tower of an enemy and an invader, instantly displayed the blood-red flag, whereon the disconsolate maiden precipitated herself from the top of the tower, and was dashed to atoms. Not many years ago a poor half-witted female recluse took up her abode on the top of the tower, and was, like the hermits of old, supplied with every necessary by the surrounding peasantry. It has been conjectured that the tower was erected during the reign of Elizabeth, and took its name from the Maiden Queen.

INDEX.

- ACHADH Aldai rifled by the Danes in 862, 202 ; supposed to be identical with New Grange, 203.
- Achill, remarkable preservation of primitive habits and manners in, 89, *note*.
- Ancient and modern remains connected, 105.
- Antiquities of the Boyne, general reference to the, 3 ; their variety, 6 ; their abundance, 9 ; Celtic relics and animal remains, 9.
- Architecture, progress and transitions of, in Ireland, 73 ; its advanced condition before the English invasion, 87, 88.
- Ardmulchan church ruins, 165, 166 ; military fort, 166.
- Ardsallagh, 111, 128.
- Assey castle and church ruins, 117.
- Athlumney Castle, 131, 132 ; its destruction by fire, 132, 133 ; church, 132.
- Ath Truim, the ancient name of Trim, 81.
- Babe's bridge, 164.
- Ballad, a new, on the battle of the Boyne, 255.
- Ballybogan, ruins of the church of, 51 ; some historical notices of the priory of, 52 ; inventory of the possessions of the Prior at the Reformation, 53.
- Balsoon, 111 ; ruined church, 117.
- Banqueting-hall of Tara, the, 122.
- Beauparc, 172.
- Bective Abbey, 107, 108 ; the alleged burial-place of Hugh de Lacy, 110 ; cloisters of, 111 ; annals of, 109, 111.
- Bective-bridge, 107 ; demesne, 111.
- Bellinter, 111, 118 ; bridge, 118.
- Bermingham family, 35, 36 ; remains of their castles,—Carbury, 30 ; Mylertown, 33 ; Kinnafad, 37 ; Carrick Oris, 43 ; war occasioned by an insult to, called the war of "Caimin," 86.
- Bermingham, Pierce, his massacre of the O'Conors, 44.
- Bewley, 262.
- Blackcastle, 159.
- Blackwater, the, general view, 136 ; origin of the name, 137.
- Bloomsbury Bridge, 154.
- Boan and Dabella, legend of, 24, 25.
- Bolg-Boinne, the battle of, 75.
- Book of Kells, 149.

- Boyne, the, peculiar character of its beauty, 1, 2; its important historical associations, 8, 4; archaeological remains, 6, 7, 8; attractions at different seasons, 10, 11; the great river of Meath, 11; geographical description of, 21; general view of its course, 21, 22; origin and derivation of its name, 23, 24; legend of Boan and Dabella, 24, 25; portion from Clonard to Trim, 76-102; from Trim to Navan, 103-135; Navan to Slane, 159-183; in Louth, 241; its mouth, 262, 263.
- Boyne, battle of the, the battle-field, 242, 243; position of James's army, 244; of William's, 245; King William wounded, Story's account, 246; account from the Duke of Berwick's Memoirs, 247; materials for a more impartial account of the battle, 248; numbers of the contending armies, 249; disadvantages of James, 250; battle of Rosanaree, 250, 251; passage of Oldbridge, 251; the retreat to Duleek, 252; some consequences of the battle, 253; death of Schomberg, 254.
- Boyne Water, the,—the old ballad retouched, 255.
- Brechin, round tower of, 162.
- Broad Boyne Bridge, 169, 171.
- Brugh-na-Boinne, 171; royal cemetery, 184-187; its true locality, 188.
- Burial, various forms of among the ancient Irish;—the cairn or pyramid, 224; the cromlech, 228; the kistvaen, 231; the urn, 232; mixed forms at Kilbride, 234; at Portaferry, 234, 235.
- Butler, Dean, his laudable efforts to preserve the remains of antiquity at Trim, 80.
- Cannistown, or Cannonstown church, 129.
- Carbury castle, description of, 27, 28; history of, 30, 31.
- Carbury, or Carbery hill, 27, 28, 29; ancient remains on, 29; other localities of the same name, 29; its celebrity in ancient Irish history, 29, 30; extensive view from the summit of, 32.
- Carrick, hill of, 41, 42; rich prospect from the summit of, 42; a place of note in ancient times, 42; castle and church ruins, 43; superstitions connected with the locality, 45.
- Carvings at the mound of New Grange, 192, 193, 197-200.
- Castles, ancient:—Carbury, 30; Kinnafad, 37; Clonmore, 41; Grange, 41; Carrick-Oris, 43; Ticroghan, 75; Trimblestown, 78; Trim, 94; Nangle's and Talbot's, 96; Scurlogstown, 104; Trubly, 106; Assey, 117; Rivers-town, 118; Liscarton, 156; Dexter, 173; Dowth, 210; Proudfootstown, 242.
- Castles built in Ireland antecedent to the English invasion, 88.
- Castle Dexter, 173.
- Celts, who are the? 217.
- Cemeteries, royal, in Ireland, 184.
- Clady, Pagan and Christian remains at, 112-115; the church, 112; font, 113; ancient stone foot-bridge, 113; subterranean chambers, 114, 115.
- Cletty, the house of, 116.
- Cloghlea, stone circle, 211.
- Clonard, roads to, 54; description of the scenery, 55; battle of, in 1798, 56, 57; its early importance as a bishop's see and seat of learning, 58, 59; ecclesiastical annals, 60-63; remains in 1786, now obliterated, 63, 65; ancient

- font of, 64; ancient lavatory of, 65; ancient stoup belonging to, 67; Pagan remains of, 68-70; the moat, 68; military rath, 69.
- Clonmore, ruined castle of, 41.
- Colpe, 263.
- Columbkil, St., his "house" at Kells, 144, 145.
- Cormac Mac Art, death of, 116; interment of, 187.
- Cromwell's Irish campaign, a good history of, wanted, 105.
- Crypts, ancient, 115.
- Curragh of wicker and horse-hide at Slane, 183.
- Cusack, Michael, 158.
- Dagobert, King, 181, 182.
- Dangan, 96.
- Danish origin of ancient Irish monuments once a prevailing opinion, 70.
- Dathi, sepulchre of, 186.
- Dearvorgail, the elopement of, 18; her death, 19.
- De Lacy, Hugh, builds the castle of Trim, 90; true account of his death, 91, 92; his burial, 93, 110; and character, 93.
- Derrinydaly bridge, 78.
- Dexter, Castle, 157, 158.
- Dillon monument at Newtowntrim, 100; Dillon family, 100, 101.
- Domhnall, King, his banquet, and its disastrous consequences, 176-178.
- Donaghmore church and tower, 159-163.
- Donaghpatrick, ancient church of St. Patrick, 155; fine specimen of a military rath at, 155.
- Donore, remains of the church and friary of, 77; castle, 77; hill, position, and bearings of, 248.
- Dowdall, Sir Lancelot, last lord of Athlumney, heroism of, 182, 183.
- Dowdstown, 111.
- Dowth castle and church, 210.
- Dowth, or Dubhadh, mound of, 204; plundered by the Danes, 202, 205; recent examination of, 205; interior chamber, 206; carvings, 207; antiquities found, 209.
- Drogheda, 259; its annals, 259; its walls, 259, 260; St. Laurence's Gate, 259; West Gate, 260; St. Mary's abbey, 261; Magdalen steeple, 262.
- Duleek, 262.
- Dumha-na-nGiall, 124.
- Dunamase, skull found at, 232.
- Dunmoe castle, 166, 167.
- Dun-na-n-Gedh, story of the banquet of, 176; fort of, 211.
- Dunshaughlin antiquities, 127.
- Ecclesiastical structures, modern, want of taste displayed in, 73.
- Edenderry, 34.
- English invasion of Ireland, 17.
- English Pale, origin of the, 19; its extent and boundary, 20; ancient Act relative to, 20, 21.
- Erc's goose eggs, story of, 176.
- Erc, St., hermitage of, 175.

Eschricht, Professor, inquiries by, respecting the races of men whose remains are found in ancient Scandinavian burying places, 225.

Ethnological inquiries, difficulties attending, 214-216.

Ethnology and the means of studying it:—architecture, 212; philosophy, 212; history, 213; ethnography, 214.

Farm, demesne of, 243.

Fennor rock, 173; church and castle ruins, 178.

Finger, the, 263.

Finian, St., first bishop of Clonard, 58; some account of, 59, 60; his baptism, 60.

Finn Mac Cumhaill, or Fin-ma-Cool, death of, 116.

Firbolga, the, 218.

Font of the church of Clonard, 64; of Clady, 112, 113; of Kilcarn, 130, 131.

Forradh, the, 124.

Fothadh Airgthech, burial-place of, 187.

Geneville, or Joinville, Geoffrey de, 85.

Gibbstown, 157.

Grange Castle, 41.

Grove Island, 243.

Headfort demesne, 143.

History of Ireland yet to be written, 5, 6; pleasing evidence of the interest now taken in it, 5.

Holy Wells:—Trinity, 24; Holy Cross, 45; Beautiful Well, 46; Lady Well, 46; St. Bridget's, 128; St. Kieran's, 141; Tober Ruadh, 163; Tober Padraig, 170; Tober Patrick, 183; scenery and legends of, 46, 47; a history of them wanted, 47, 48; indication of materials of such a work, 49; lines on the Irish people's veneration for, 50.

Human bodies found in bogs, 237.

Inchmore Bridge, 77.

Irishmen who have distinguished themselves in foreign military service, 32, 33, *note*.

John, King, visits Ireland, 93.

Kells, 143; St. Columbkille's home, 144, 145; round tower, 146; inscription on the church tower, 147; crosses, 147; great cross, 148; annals of, 149; book of, 149.

Kieran, St., ancient church and crosses of, 138; ludicrous tradition regarding the latter, 139; refuted by authentic history, 140; holy well of, 141, 142; bleeding of the ash-tree, 142.

Kilcarn, 129; church ruins, 129; ancient font, 130, 131.

King William's Glen, 244.

Kinnafad, 37; castle of, 37; account of some ancient weapons found near, 38, 39.

- Knock-a-Raymon**, 163.
Knocklea, tumulus of, 224.
Knockmaroon, tumulus at, 228, 229.
Knockminauna, or Kids' Hill, 163.
Knowth, mound of, 189.
- Lady Well**, 178.
Laracor, the early residence of Dean Swift, 96.
Lavatory, ancient, belonging to Clonard, 65.
Lecan, Book of, 185.
Leinster Bridge, 55.
Lia-Fail, or Stone of Destiny, 124, 125.
Liscarton castle and church ruins, 156, 157.
Lloyd, Hill of, 142.
Loman, St., 83 ; his foundation of the see of Trim, 83, 84.
- Mac Murrough**, Dermot, King of Leinster, the seducer of Dearvorgail, 17, 18.
Maiden tower, the, 263.
Malachy I. defeats a band of outlaws on an island in Lough Ramor, 138.
Meath, or Midhe, ancient kingdom of, the earliest cultivated part of Ireland, 4 ; described, 11 ; early history, 12 ; and extent, 13 ; its four royal palaces, 13 ; Giraldus Cambrensis' account of, 13, 14 ; its present fertility, 15 ; manners and characteristics of the peasantry, 16 ; diocesan school, 96.
Mellifont, 262.
Milesians, the, 223.
Molyneux, Sir Thomas, his investigations into the circumstances of ancient human remains, 224.
Monasterboice, 262.
Monasteroria, ecclesiastical ruins of, 35 ; origin of the name, 35, 36.
Mornington, 262.
Moy Turey, battle of, 222.
Muircheartaigh Mac Earca, death of, at Cletty, 117.
Mule's leap, the, 43.
Mylerstown castle, 33.
- Nangles**, castle of the, at Trim, 96.
Navan, 133, 134 ; extensive souterrain discovered near, 135 ; moat of, 157.
Neamhnach, well of, 125.
Nevinstown, wayside cross of, 157, 158.
New Grange, mound of, 189 ; pillar-stones round it, 190 ; Llhwyd's description of it in 1699, 191-193 ; carved stones at the entrance, 192, 193 ; passage, 194 ; interior chamber, 195, 196 ; its analogy to the ancient remains of other countries, 196, 197 ; carvings in the interior, 197-200 ; basins found in, 201.
Newhaggard, 78.
Newpark demesne, 108.
 Newtown-Trim, monastic remains of, 98 ; monastery and cathedral of St. Peter and St. Paul, 99 ; priory of St. John the Baptist, 102 ; destruction of the remains, 101.

O'Connor, Murtagh, King of Offaly, and his companions, massacred by Comin and Mac Feorais, 44.

Oldbridge battle-field, 242; site of the village of, 243.

Ordnance Survey of Ireland, its value in topographical questions, 29, *note*.

Patron festivals at holy wells, 46, 47, 48.

Peppard, or Pipard, Richard, rebuilder of Trim castle, 94.

Pillar-stones around New Grange, 190, 210.

Proudfootstown castle, 242.

Races, two, of the ancient Irish, distinguished by the form of their heads, 41, 239; modern instances of the same distinction, 231; skulls of the long-headed race, 229, 230; of the globular-headed race, 231, 232.

Ramor, Lough, the source of the Blackwater, 137, 138.

Rath Caelchon on Tara Hill, 123; Rath Grainne, 123; Rath-na-Seanadh, or King's chair, 123; Rath-na-Riogh, 124; Rath of Laoghaire, 125; Rath of Queen Meve, 125.

Raths, or military forts, 54, 69, 103, 112, 138, 155, 166, 169, 170, 211.

Rathaldron castle, 157.

Rathcore, the battle-field of, 74.

Rathmore, old church of, 147, *note*.

Rathnally, 105.

Retzius, Professor A., researches regarding the races whose remains are found in ancient Scandinavian sepulchral monuments, 225.

Riverstown castle, 118.

Rochfort, Simon de, Bishop of Meath, 62, 98.

Roristown, 98.

Rosnaree, or Ros-na-righ, 187.

Round Tower of Kells, 146; of Donaghmore, 161, 162.

Round Towers, general results of Dr. Petrie's investigations respecting, 146.

Royal visits to Ireland, 93.

Saxon not the correct designation of the colonists of Ireland at the English invasion, 89.

Saxons chiefly introduced by Cromwell, 90.

Scandinavian sepulchral monuments, 225-228.

Scariff bridge, 77.

Scurlogstown, 103; church remains, 103; castle, 104.

Senchas-na-Relec, 184, 185.

Sepulchres of Irish kings, 186.

Skulls, ancient, found near Kinnafad, described, 40; belonging to two distinct races, 41; two distinct forms of, found also in Scandinavian sepulchres, 226-228; skulls of the long-headed race, 229, 230; of the globular-headed race, 231, 232; one found beneath the round tower of Drumbo, 226; of Donatus, first Danish Archbishop of Dublin, 237.

Slane, view from the hill of, with its associations, 179, 180; St. Patrick's arrival at, 180; destruction of the cloitheach or round tower of, 181; ancient tomb, 182; ruins of the church and monastery of, 183.

Slane castle, 174.

- Sources of the author's information, 23.
 Spoliation of ancient monuments, instances of, 65, 66, 101.
 Square forts, 138.
 St. Bernard's well, 210.
 St. Bridget's holy well, 128.
 St. Patrick's staff burned, 53 ; his arrival at Slane, 180.
 St. Patrick's hymn, 126.
 St. Patrick and King Loeghaire, 153, 154.
 Stackallan, 169.
 Stella's cottage, 97.
 Stonyford bridge, 76.
 Stoup, ancient, belonging to Clonard, 67.
 Talbot, Sir John, builder of the Talbots' castle at Trim, 96.
 Tara, recollections of, 119, 120 ; how to see, 121 ; brief notice of the chief objects of interest at, 122-126.
 Teach Cormaic, or House of Cormac, 124.
 Teltown, or Tailtean, 149 ; sports and marriages of, 150, 151, 152 ; great fort of, 152 ; stories of St. Patrick connected with, 153, 154 ; ruins of the church of, 154.
 Templar, skeleton of a, found at Larne, 237.
 Termonfecken, 262.
 Ticroghan, ancient fortress of, 75.
 Tober-crogh-neeve, or Well of the Holy Cross, 45, 53.
 Tober Padraig, or St. Patrick's Well, 170.
 Tober Patrick, 183.
 Tober Ruadh, 163.
 Tomb-openers, advice to, 240.
 Townley Hall, 242, 243.
 Trim, 79 ; fine tableaux of ruins, 80 ; statistics of, 81 ; its early ecclesiastical history, 82 ; St. Mary's Abbey, 83 ; Yellow Steeple, 84 ; monastic annals, 85 ; grey friary, 85 ; black friary, 85 ; nunnery, 87 ; Greek church, 87 ; military buildings, 87 ; castles, 90, 94.
 Trimblestown castle, 78.
 Trinity Well and its legend, 24.
 Trubly, 106 ; remains of the castle of, 106.
 Tuatha de Danaan, 219 ; their religion, physical character, and arts, 220-222.
 Tumuli, ancient, 68, 77, 97, 103, 132, 163, 188, 204, 224.
 Tyrrell, Lieut., his gallant defence against a superior force in 1798, 56, 57.
 Urns, ancient, found in Ireland, 232.
 Virginia, 138.
 Weapons, ancient, found near Kinnafad, described, 38, 39 ; conjectures as to the races who used them, 40.
 Well of the Holy Cross, 45.
 Wells, holy. *See* Holy Wells.
 Wellesley family, pedigree of, 31, 32, *note*.

Wellington, Duke of, his birth-place, 95 ; his early days in connexion with Trim, 96.


Witch's Stone, the, on the Hill of Carrick, 42.


Yellow Island, 243.

Yellow River, 41.

Yellow Steeple, Trim, 83, 84.

THE END.





AUGUST, 1849.

BOOKS ILLUSTRATIVE OF IRELAND,

IN

HISTORY,
AGRICULTURE,
RESOURCES,
MUSIC,

BOTANY,
STATISTICS,
LANGUAGE,
JURISPRUDENCE,

PUBLISHED BY

HODGES AND SMITH, GRAFTON-STREET, DUBLIN.

History.

Petrie's Round Towers, and Ecclesiastical Architecture of Ireland. Illustrated by 250 fine Woodcuts, from Drawings by Mr. Petrie. 1 vol., 8vo., in embossed binding, price 28s.

"A work which can only be paralleled by the labours of the great Niebuhr. Since the Union with Great Britain, there has not issued from the Press any work at all comparable with this splendid and learned volume."—*Dublin Evening Mail*.

"Mr. Petrie has brought to his inquiry extreme caution, pure candour, and all the temperateness of an accurate and a calm scholar. . . . This is unquestionably the first work on British Antiquities of the age."—*Dublin University Magazine*.

"Mr. Petrie has brought to light a great mass of most interesting facts, illustrative of Irish history and antiquities, which, we confess, have surprised us, and added a dignity and character to the history of Ireland."—*Literary Gazette*.

History of the Irish Brigade in the Service of France, and Military Memoirs of the Irish Nation. By the late MATTHEW O'CONOR, Esq., Barrister-at-Law. 1 vol. 8vo., bds., 9s.

"A work that will be read with much interest. Its charm consists in the passionate love of Mr. O'Conor for his subject; in his fervent attachment to his country; in his glowing descriptions of battles, which are so graphic as to pass vividly before us; in his religious tolerance, and in the spirit of honour and fidelity which makes him ready to praise valour in the worst enemies of Ireland."—*Athenaeum*.

The Annals of the Four Masters. from 1172 to the Conclusion in 1616; consisting of the Irish Text from the Original MSS., and an English Translation, with copious Explanatory Notes. By JOHN O'DONOVAN, Esq., M. R. I. A., Barrister-at-Law. 8 vols., 4to., price Eight Guineas.

"The numberless minute verbal criticisms; the elaborate topographical annotations with which each page is loaded; the historical, genealogical, and biographical notices; the lucid and ingenious illustrations drawn from the ancient laws, customs, traditions, and institutions of Ireland; the parallelisms and discrepancies of the narrative with that of other annalists, both native and foreign; the countless authorities which are examined and adjusted; the errors which are corrected, the omissions and deficiencies supplied; in a word, the curious and various learning which is everywhere displayed. Let him remember that the mine from which all those treasures have been drawn is, for the most part, unexplored; that the materials thus lavishly applied to the illustrations of the text are in great part manuscripts,—manuscripts, too, which Usher and Ware, even Waddy and Colgan, not to speak of Lynch and Lanigan, had never seen, or had left unexamined; many of them in a language which is, to a great extent, obsolete. Let him remember this, and he will cease to wonder how, commenced in January, 1832, it is only after fifteen or sixteen years of patient study and investigation that it is at last given to the public."—*The Dublin Review*.

History, continued.

Ecclesiastical Antiquities of

Down, Connor, and Dromore; comprising an ancient Taxation of those Dioceses, compiled A. D. 1291. With Notes and other early Documents. By the Rev. William Reeves, M. B. 1 vol., thick 4to., price 20s.

"In the work now under notice, Mr. Reeves has offered another contribution towards an ecclesiastical history of his country; and the honest and painstaking labour he has bestowed on his work does honour to himself and reflects credit on the Irish Church. The history of these taxations of the clergy is very curious. In the Notes and Appendix of this volume, Mr. Reeves has collected a vast quantity of information regarding the benefices mentioned in the Taxation. It is sincerely hoped this work will be received with the attention it deserves, and that Mr. Reeves may be encouraged to prosecute his studies, and to throw still further light on the ecclesiastical history of Ireland."—*British Magazine*.

The History of the County

of Dublin, and Memoirs of the Archbishops of Dublin. By JOHN D'ALTON, Esq., M. R. I. A. 2 vols., 8vo., 25s.

Fasti Ecclesie Hibernicæ.

The Succession of the Prelates and Members of the Cathedral Bodies in Ireland. By HENRY COTTON, D. C. L., Archdeacon of Cashel.

Vol. I.—MUNSTER, 8vo., bds., 14s.

Vol. II.—LEINSTER, " 14s.

The Life of James Gandon,

M. R. I. A., F. R. S., Architect of the present Custom House, Four Courts, King's Inns, and West View of the Bank of Ireland. From Materials collected by his Son, and edited by the late T. J. Mulvany, R. H. A. 1 vol., 8vo., with Portrait, 10s. 6d.

"Mr. Gandon's connexion with our city, as the architect of the noblest of our public edifices, has associated his name with the history of Art in Ireland; and the volume, besides the details of his own private life, is filled with interesting notices of the contemporary artists."—*Dublin Review*.

"The profession he so eminently distinguished will, we are confident, treasure this work."—*Evening Post*.

Agriculture and Resources.

Industrial Resources of Ire-

land. With Maps illustrating the Geological and Industrial Structure of the Country. By SIR ROBERT KANE, M. R. I. A. Second Edition. 1 vol., cloth, price 7s.

"The author handles his subject with the dexterity of a master, and condenses in one volume as much of scientific and statistical information as we have ever seen thrown together."—*Athenæum*.

The Tenant Right of Ulster,

considered Economically; being an Essay read before the Dublin University Philosophical Society; with an Appendix, containing the Evidence of JOHN NEILSON HANCOCK, Esq., taken before the Landlord and Tenant Commission. By W. NEILSON HANCOCK, Esq., Barrister-at-Law. 8vo., sewed, 1s.

Land Commissioners' Report.

Digest of Evidence taken before Her Majesty's Commissioners of Inquiry into the State of the Law and Practice in respect to the Occupation of Land in Ireland. 2 vols., 8vo., boards, 15s.

The Condition and Prospects

of Ireland, and the Evils arising from the present Distribution of Landed Property, with Suggestions for a Remedy. By JONATHAN PIM.

"The most practically valuable work on Ireland."—*Athenæum*.

"We confidently recommend Mr. Pim's volume as the most luminous, earnest, and faithful review of the condition of Ireland question that has hitherto been presented to the English public."—*Atlas*.

"This is a very valuable publication, written in an earnest spirit, replete with facts, impartial, argumentative, and suggestive. The author is perfectly master of his subject."—*Jerrold's Newspaper*.

Music.

Bunting's Ancient Music of Ireland; consisting of upwards of 165 Airs, few of which have before been published; with Historical Notices, Biographies of the eminent Harpers, &c. New Edition, illustrated with Steel Engravings. 1 vol., royal 4to., elegantly ornamented binding, price 81s. 6d.

"The name of Edward Bunting must be ever dear to the lovers of Irish music. From the year 1792 down to the present time, he has been indefatigable in his efforts to rescue the exquisite airs of our country from oblivion. His name will be honourably mentioned in the republic of letters, as well as in the world of music."—*Evening Packet*.

Botany.

The Irish Flora; comprising the Flowering Plants and Ferns. Second Edition. 1 vol., 12mo., fancy cloth, 5s.

"This work should be read by every man, woman, and child interested in becoming acquainted with the vast amount of botanical treasures with which nature has blessed our lovely island."—*Irish Farmer's Gazette*.

A Practical Treatise on the Management of Orchidaceous Plants, with a Monthly Calendar of Work to be done, and an alphabetical descriptive Catalogue of upwards of 1000 Species; with Directions for their Growth and Flowering. By J. C. LYONS. Second Edition, greatly enlarged, 1 vol., 8vo., boards, 10s.

Statistics.

The Ecclesiastical Index of Ireland, with the Rectories, Vicarages, and Curacies, arranged alphabetically, with their Value, Glebe Lands, Patrons, &c. &c.; also the Unions of all the Dignitaries at present existing, and the Episcopal Incomes. Edited by the REV. ROBERT KNOX, now Lord Bishop of Down and Connor, and Dro-more. 1 vol., 8vo., cloth, 6s.

Moore's Manual of the Poor Law Statistics of Ireland. Containing all the Information necessary for the use of Proprietors in general, classified and arranged in the most intelligible and convenient form, presenting at a glance the Population of each Electoral Division, its Extent in Statute Acres, Net Annual Value, and the Names of the Baronies in which each Electoral Division is situate, with the Valuation of the several portions of the same contained in the Electorates; with Summaries of the Unions, Counties, Baronies, and Provinces, with their Population, Area, and Valuations; Lists of Marriage Registrars' Districts, &c. &c. 1 vol., 8vo., price 6s.

Language.

A Grammar of the Irish Language, published for the Use of the Senior Classes in the College of St. Columba. By JOHN O'DONOVAN, Member of the Irish Archaeological Society. In one large volume, with engraved specimens, from early Irish Manuscripts. Price 16s.

"One need not be a master, nor even a student of the Irish language, to find interest and knowledge in this work. It is no regiment of rules without reason, illustration, or authority, like most grammars. It is a profound and discursive treatise on the pronunciation, inflections, structure, and prosody of the most perfect of the Celtic tongues. There is not, we are sure, an antiquarian or philologist in Europe but will grasp it as the long-wished-for key to facts locked in the obscurity of a language whose best grammarians had only the dialect of their own parishes, and whose most notable grammars were the works of pretenders. Yet no one must suppose that this work is merely an antiquarian miscellany, or a philosophical treatise, or both. It is a thoroughly practical Irish Grammar."—*Nation*.

A Primer of the Irish Language, for the Use of the Students in the College of St. Columba. 1 vol., 12mo., boards, 3s.

Jurisprudence.

Incumbered Estates Act.—

Act to further facilitate the Sale of Incumbered Estates in Ireland, with an Introduction, Notes, Index, and Forms. By JAMES BURKE, Esq., Barrister at Law. 1 vol., 12mo.

Thompson on the Grand Juries

in Ireland. A Digest of Acts consolidating and amending the Laws relating to the Presentment of public Moneys by Grand Juries in Ireland; with all the recent Decisions, Notes, &c. By BOWEN THOMPSON, Esq., Barrister at Law. 1 vol., 12mo., boards, 7s. 6d.

An Analysis of the Criminal

Law of Ireland, with Notes, Appendix of Forms, &c. &c. By THOMAS P. LEFFROY, Esq., Barrister at Law. 1 vol., crown 8vo., price 14s.

"Nothing so accessible, so full, and with such facilities, has hitherto been printed. The Magistrate has, as it were, in a nutshell, the legal knowledge of the experienced lawyers, arranged in the best manner for reference and convenience."—*Dublin Evening Post*.

"In arrangement the most rigid regard has been paid to accuracy, accompanied by such simplicity and lucidness as literally to make confusion or mistake impossible. It cannot fail to be the manual of every magistrate in Ireland."—*Dublin Evening Press*.

The Law of Ecclesiastical Residences in Ireland.

By GEORGE MILLER, D. D., Vicar-General of Armagh. 8vo., 1s. 6d.

A Popular Treatise on the

Law of Landlord and Tenant in Ireland. By WILLIAM HENRY FILGATE, Esq., Barrister at Law. 1 vol., 8vo., price 14s.

"We think no landlord who has any property left, or agent who expects to be able to collect even the small sum that would pay for it, ought to be without it."—*Dublin Evening Mail*.

"It is an invaluable manual to every man who is remote from, or unable to procure, professional guidance on every ordinary subject. Concise, clear, and practical, it is a safe and plain guide in every practical emergency."—*The Warder*.

"We recommend it to every individual interested in land; it cannot fail to be of the utmost importance to the proprietors of estates, their agents, and tenants."—*Farmer's Gazette*.

The Powers and Duties of Justices of the Peace in Ireland,

with a copious Collection of Statutes and Forms. By RICHARD NUN and JOHN EDWARD WALSH, Esqrs. Second Edition, 2 vols., 8vo., cloth, price £1 16s.

Oulton's Index to the Statutes

at present in force in, or affecting Ireland, from the Year 1810 to 1839 inclusive. By ANDREW N. OULTON, Esq., Barrister at Law. 1 vol., royal 8vo., price £2 2s.

Oulton's Index to the Statutes.

The Supplements, containing the Index to the Acts from 1839 to 1846, inclusive. 1 vol., royal 8vo., 30s.

~~~~~  
*Preparing for Publication,*

ILLUSTRATED BY ENGRAVINGS FROM ORIGINAL DRAWINGS,

**The Architecture, History, and Antiquities**

OF THE

**CATHEDRAL CHURCH OF ST. CANICE, KILKENNY.**

BY THE REV JAMES GRAVES, A. M.,

Of St. Patrick's, Kilkenny; and

JOHN G. A. PRIM, ESQ.

Subscribers' Names received by the Publishers.

DUBLIN: HODGES AND SMITH, GRAFTON-STREET.



**RETURN TO: CIRCULATION DEPARTMENT**  
**198 Main Stacks**

|             |   |   |   |
|-------------|---|---|---|
| LOAN PERIOD | 1 | 2 | 3 |
| Home Use    |   |   |   |
|             | 4 | 5 | 6 |

**ALL BOOKS MAY BE RECALLED AFTER 7 DAYS.**

Renewals and Recharges may be made 4 days prior to the due date.  
 Books may be renewed by calling 642-3405.

**DUE AS STAMPED BELOW.**

|                |  |  |
|----------------|--|--|
| SENT ON ILL    |  |  |
| JUL 21 2003    |  |  |
| U. C. BERKELEY |  |  |
|                |  |  |
|                |  |  |
|                |  |  |
|                |  |  |
|                |  |  |
|                |  |  |
|                |  |  |
|                |  |  |
|                |  |  |
|                |  |  |
|                |  |  |
|                |  |  |

FORM NO. DD6  
 50M 5-03

UNIVERSITY OF CALIFORNIA, BERKELEY  
 Berkeley, California 94720-6000

LD 21A-50m-12,'60  
 (B6221s10)476B

U/celey

DA990  
B7W6

219386

Wilde

